

ENVIRONMENTAL ASSESSMENT


Air Quality Technical Report Appendices

February, 2020




**Appendix A: Average Daily Traffic Mainline Forecasts and 2018
Intersection Baseline Volumes**

SHEET 1



NOT TO SCALE

2025 No-Build ADT Volumes Sheet 1




2025 No-Build ADT Volumes

Sheet 2



To Dulles/Leesburg
←

To Washington DC
→



- Existing DAAR Lanes
- Existing GP Lanes
- Existing Express Lanes

684


495

123

NOT TO SCALE

2025 Build ADT Volumes


Sheet 1



NOT TO SCALE

2025 Build ADT Volumes

Sheet 2



- Existing DAAR Lanes
- Existing GP Lanes
- - - GP Lane improvements by others
- Existing Express Lanes
- Express Lanes improvements as part of this project

684


495

123

267

NOT TO SCALE


2045 NO BUILD ADT VOLUMES SHEET 1



NOT TO SCALE

2045 Build ADT Volumes

Sheet 1



NOT TO SCALE

2045 Build ADT Volumes

Sheet 2




To Dulles/Leesburg ←

To Washington DC →

EXIT 17

ROUTE 267 EXIT 18/I-495 EXIT 45

EXIT 19




- Existing DAAR Lanes
- - - DAAR improvements
- Existing GP Lanes
- - - GP Lane improvements by others
- - - GP Lane improvements as part of this project
- Existing Express Lanes
- - - Express Lanes improvements by others
- - - Express Lanes improvements as part of this project

* DTR 15,000
** DTR 17,700

NOT TO SCALE

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kinney-Horn and Associates, Inc. shall be without liability to Kinney-Horn and Associates, Inc.



Legend

-  Intersection Group Number
-  Intersection Number
-  Project Study Area



*DRAFT WORKING PRODUCT -
NOT FOR PUBLIC DISTRIBUTION*



AM (PM) Peak Hour Existing
Intersection Volumes








FIGURE
KEY

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



NOTE - Intersection Volumes Inset Boxes are oriented to the North

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kinley-Horn and Associates, Inc. shall be without liability to Kinley-Horn and Associates, Inc.



NOTE - Intersection Volumes Inset Boxes are oriented to the North



DRAFT WORKING PRODUCT - NOT FOR PUBLIC DISTRIBUTION

Legend



 Intersection Number



AM (PM) Peak Hour Existing Intersection Volumes

FIGURE 3

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kinley-Horn and Associates, Inc. shall be without liability to Kinley-Horn and Associates, Inc.



NOTE - Intersection Volumes Inset Boxes are oriented to the North

**Appendix B: Scoping Framework Document for I-495 NEXT
Project - FHWA Concurrence for Approach and Methodology**

I-495 Express Lanes Northern Extension Project (I-495 NEXT Project)

FINAL EXECUTED VERSION

Scoping Framework Document for *I-495 NEXT Project*

FHWA Concurrence for Approach and Methodology

VDOT Contract ID No. 45978 /Project No. 113414

NOVEMBER 15, 2018

Prepared for:



NOVA District, Fairfax
Central Office, Richmond



Virginia Division, Richmond

Prepared by:



Table of Contents

- Introduction..... 1
 - Background 1
 - Current Studies..... 1
 - Document Purpose..... 2
- Purpose & Need..... 2
- Project Scope & Assumptions Summary 4
 - Scoping Definitions:..... 4
 - Two Express Lanes 4
 - Four General Purpose Lanes 4
 - Auxiliary Lanes..... 4
 - Dulles Interchange Long Range Plan 4
 - Milestone Schedule Approach & IJR Review Process 4
- Assumptions..... 5
 - Study Area Limits 5
 - Data Collection 8
 - Traffic Volumes 8
 - Origin-Destination Data..... 10
 - Speeds and Travel Times..... 10
 - Queueing Data..... 10
 - Analysis Scenarios 11
 - Proposed Modifications in Access (Express Lanes Access Alternatives)..... 12
 - Travel Demand Modeling Methodology and Key Assumptions..... 16
 - Methodology and Key Assumptions for Post-Processing of Modeling Results..... 17
 - Traffic Operational Analysis Methods/Parameters 17
 - Traffic Analysis Tools..... 17
 - Measures of Effectiveness..... 17
 - Traffic Modeling Methodology and Main Assumptions..... 18
 - Calibration Methodology for Base Models 18
 - Seeding Time, Simulation Time, and Number of Runs 20
- Safety Analysis..... 23
 - Reported Crash Data, Crash Summaries & Collision Diagrams 23
 - Qualitative Analysis 24
 - Quantitative Analysis 25

Deliverables..... 25

Report Deliverables..... 27

Review Process..... 27

List of Figures

Figure 1: Project Study Area..... 7

Figure 2: Traffic Count Locations..... 9

Figure 3: Alternatives / Options Development and Screening Process..... 12

Figure 4: Express Lane Access Movements Interim Year 2025..... 14

Figure 5: Express Lane Access Preferred Alternative 2045..... 15

Figure 6: VDOT TOSAM Calibration Criteria and Acceptance Targets..... 19

Figure 7: INRIX Speed Heat Map for I-495 Northbound GP and Proposed Analysis Periods 22

List of Tables

Table 1: VISSIM Calibration Criteria and Acceptance Targets..... 20

ATTACHMENTS/APPENDICES

1. I-495 NEXT Traffic Operation Analysis Framework Memorandum
2. I-495 NEXT Travel Demand Forecasting Memorandum
3. I-495 NEXT VISSIM Calibration Memorandum
4. I-495 NEXT Crash Analysis Framework Memorandum
5. I-495 NEXT Air/Noise Analysis Framework Memorandum

INTRODUCTION

This document outlines the scope of work for the traffic forecasting and analysis associated with the I-495 NEXT Project. The consultant team will provide technical support of the National Environmental Policy Act (NEPA) studies (documented in an Environmental Assessment), Preliminary Engineering and Options Development, and other analyses performed in support of the associated technical reports prepared to inform the NEPA decision making process. This task will primarily focus on efforts to prepare a Traffic and Transportation Technical Report (TATTR) and a system Interchange Justification Report (IJR) based on the guidance from VDOT Central Office that is updated from the previous IIM 200.9, in order to be consistent with the May 2017 update to FHWA policy on NEPA and IJR for federal actions involving interchanges and interstate access. The TATTR and IJR will serve to support the technical studies as a part of VDOT's I-495 NEXT Project, and to document the project traffic analysis.

Background

The Virginia Department of Transportation (VDOT), in partnership with the Federal Highway Administration (FHWA), is developing transportation improvements in the I-495 corridor from the Dulles Toll Road (State Route 267) to the vicinity of the American Legion Bridge and the Maryland state line, called the I-495 Express Lanes Northern Extension (NEXT) project. The project proposes to add two (2) managed lanes in each direction, and the study corridor extends approximately three miles from the I-495 interchange with the Dulles Toll Road to the George Washington Memorial Parkway (GWMP) in the McLean area of Fairfax County.

The Capital Beltway, or I-495, is a 64-mile multi-lane circumferential freeway centered around Washington, D.C. and passing through Maryland and Virginia. The Virginia portion of I-495 is 22 miles, extending from the Woodrow Wilson Bridge in Alexandria to the American Legion Bridge in Fairfax County. The existing I-495 facility within the study area currently has four northbound and four southbound general purpose lanes, with auxiliary lanes or collector-distributor roadways provided at several interchanges. North of the study area, I-495 at the American Legion Bridge has a total of 10 lanes, eight general purpose through lanes and two auxiliary lanes that connect Clara Barton Parkway in Maryland and the GWMP in Virginia.

The existing I-495 Express Lanes extend for 14 miles along I-495, from the I-95/I-495/I-395 interchange in Springfield to south of Old Dominion Drive in McLean (just north of the Dulles Toll Road interchange). The two existing northbound Express Lanes end just south of Old Dominion Drive by merging into a single lane-controlled shoulder/travel lane, which is open to traffic during the AM and PM peak periods. This fifth lane continues for a total length of approximately 1.8 miles before merging with the general purpose lanes at the GWMP interchange. The Express Lanes are separated from the general purpose lanes by flexible bollards. All buses and vehicles with two axles can access the Express Lanes 24 hours a day, seven days a week. High-Occupancy Vehicles (HOV) with three or more occupants are not charged a toll. No trucks are currently permitted to use the Express Lanes.

Current Studies

The proposed effort will be comprehensive in its scope and multi-purpose. The analysis will serve to develop the environmental documentation needed per NEPA, the operational analysis report needed for interchange justification/modification, preliminary engineering, and an assessment of potential costs and revenues from variably-priced express lanes.

The following studies have been conducted to support the further development and documentation of specific infrastructure and operations recommendations for the I-495 NEXT Project:

- Final EIS Completed April 2006 (Project northern terminus near George Washington Parkway)
- ROD Issued June 2006
- IJR Approved December 2007 (northern terminus revised to north of Lewinsville Road, 5th GP lane south of Rte. 193)
- NEPA Reevaluations Completed (May 2007, June 2008, December 2008, May 2009, July 2009)
- Dulles Interchange NEPA Reevaluation November 2009
- Dulles Interchange IJR Approved December 2009
- Express Lanes and Dulles Interchange Open to traffic November 2012
- I-495 North Shoulder Lane Use Project (1½ Mile Express Lanes Merge to GW Parkway)

Document Purpose

This IJR scoping document describes the format and content of an IJR for one combination of access options and a single Build Alternative concept, as identified in the EA. This combination will be referred to as the *Preferred Alternative*. In terms of the IJR, the Preferred Alternative consists of the following:

- General purpose lanes
- Express Lanes carrying HOV-3 traffic, toll-paying traffic, and trucks (assumed conservative case)
- Transportation system management
- ITS

The I-495 NEXT Project EA and IJR will document the need for new and modified access to support and accommodate the Express Lanes, and general purpose lane modifications. The IJR will be submitted in coordination with preliminary design plans and the EA prepared by VDOT. The EA and preliminary engineering plans are being prepared concurrently with the IJR.

It should also be noted that the Express Lanes carrying HOV, toll-paying vehicles, trucks, and any potential new transit service will have connectivity to the existing high-occupancy, variably priced Express Lanes along I-495 and recently-constructed Express Lanes along I-66 Inside the Beltway between I-495 and the Washington, DC, boundary (via the Dulles Toll Road Connector).

PURPOSE & NEED

The Purpose and Need for the EA has not yet been fully established but will be developed as part of NEPA scoping process and included in the IJR. A number of corridor transportation needs have been identified in the Draft In-progress Purpose and Need. Needs for the I-495 corridor are related to issues such as:

- Reduce congestion and improve roadway safety
- Provide additional travel choices
- Improve travel reliability

Reduce Congestion and Improve Roadway Safety. In the fourth quarter of 2017, I-495 between I-66 and the I-270 Spur, including the study area and the American Legion Bridge, was ranked second on the list of top ten bottlenecks in the Washington, D.C. region by the National Capital Region Transportation Planning Board, up from being ranked fifth in 2016 (TPB, 2017). The GWMP is used as a primary commuting route and also experiences moderate congestion throughout its length, but particularly on the on ramp to I-495 northbound in the PM peak period (NPS NCR Long Range Transportation Plan, 2018).

Congestion and unsafe weaving movements of vehicles at the northern terminus of the I-495 Express Lanes also results in crashes and safety concerns in the study area. According to crash data collected along northbound I-495 from the Dulles Toll Road interchange to the American Legion Bridge over an approximate nine-month period starting November 17, 2012 (the opening of the existing I-495 Express Lanes), a total of 81 crashes were recorded in the study area. Of the 81 crashes recorded, 57 (approximately 70 percent) of the crashes occurred between south of the Dulles Toll Road interchange to the off-ramp at Georgetown Pike. The most common contributing circumstances recorded by police officers were congestion and vehicles changing lanes. Furthermore, the segment within the study area between Old Dominion Drive and the off-ramp to Georgetown Pike had the highest crash density with a crash rate of 152 (per 100 million VMT), which is far above the Northern Virginia Average Interstate Crash Rate of 99 (per 100 million VMT) (VAP3, Detail-Level Project Screening Report, 2014).

Provide Additional Travel Choices. The existing I-495 and I-95 Express Lanes create a 40-mile HOV and bus network in northern Virginia and provide additional travel choices for a variety of users. However, because the existing Express Lanes end at Old Dominion Drive, travel choices for all northbound travelers are limited. No commuter bus service is offered within the study area or over the American Legion Bridge due to the absence of dedicated or managed lanes that would allow buses to travel more efficiently. Both HOV and single-occupant vehicles choosing to use the existing Express Lanes are forced to rejoin the GP lanes north of Old Dominion Drive with no options to bypass congestion or bottlenecks. Travelers are therefore less likely to choose carpooling, vanpooling, or transit options because these options are no more efficient than driving alone.

Commuter choices are also affected by access. The northbound and southbound I-495 Express Lanes are accessible in both directions from Westpark Boulevard and Jones Branch Drive. From Route 7 and eastbound Route 267, only the southbound Express Lanes are accessible. There is currently no direct access to the northbound Express Lanes from Route 267 or Route 7. There is also no direct access to and from the Express Lanes in either direction from GWMP. Also, the planned I-495/I-270 Managed Lanes Study is evaluating the feasibility of Express Lanes along the entire I-495 corridor in Maryland, including the American Legion Bridge. Because the I-495 Express Lanes in Virginia currently end two miles south of the American Legion Bridge, there would be a two-mile gap in the I-495 Express Lanes network, representing the only interruption in Express Lanes service for the entire 64-mile I-495 loop. Travel choices for both northbound and southbound travelers would continue to be limited within this two-mile stretch because all Express Lanes users would be forced to merge into GP lanes, with no options to bypass congestion or bottlenecks.

Improve Travel Reliability. A 2016 commuter survey conducted by MWCOG revealed that over 80 percent of commuters in the region add extra time to their commutes to account for travel time variability due to congestion, bottlenecks, crashes, weather events, and other factors. These issues contribute to highly variable travel speeds and travel times for all users within the study area, including single occupancy, HOV, transit, and freight vehicles alike. Motorists who report using HOV or Express Lanes save an average of 20 minutes on their commute; however, due to congestion and reduced travel speeds at the northern terminus of the northbound I-495 Express Lanes, users traveling to Maryland or the GWMP are not able to reap the full benefits of the existing Express Lanes. The duration and extent of congestion within the study area is expected to increase with population, employment, and subsequent traffic volumes. Variability in travel speeds and travel times is therefore expected to worsen in the future. The proposed project will extend the I-495 Express Lanes from their existing northern terminus to Maryland, providing a seamless reliable travel option for HOV or toll-paying motorists traveling to or from Maryland and the GWMP.

PROJECT SCOPE & ASSUMPTIONS SUMMARY

The proposed project scope for the EA includes four general purpose lanes (keeping the same number of general purpose lanes that are utilized now) and two Express Lanes in each direction of I-495, consistent with the existing I-495 Express Lanes configuration south of the project limits. The approach to the preparation of the EA, IJR, preliminary engineering effort, and supporting technical studies will be closely coordinated among VDOT, VAP3, FHWA, and MDOT/SHA.

Scoping Definitions:

Two Express Lanes

Two lanes in each direction of I-495 that would operate as a high-occupancy variably priced toll facility with non-toll vehicles required to carry three or more persons or as required by the Code of Virginia.

Four General Purpose Lanes

Four non-tolled general purpose lanes in each direction at all times open to all traffic with shoulders [no traffic use of shoulders].

Auxiliary Lanes

The CLRP and previously approved IJR and NEPA documents commit to implementing one northbound and one southbound auxiliary lane between the Dulles Toll Road and Georgetown Pike by 2030, consistent with the CLRP.

Dulles Interchange Long Range Plan

The CLRP and previously approved IJR and NEPA documents reference a master plan for the Dulles Interchange that was developed in coordination with MWAA and FHWA in 2009 and 2010. The plan provides for full connectivity between the Dulles Toll Road, Dulles Airport Access Road, and I-495 General Purpose Lanes and Express Lanes. The plan was approved in concept by FHWA and the original I-495 Express Lanes were constructed to facilitate the future construction of the additional ramp movements. Several ramps included in the Long Range Plan are proposed to be constructed as part of the scope of this project.

Milestone Schedule Approach & IJR Review Process

- IJR Scoping Framework Document Concurrence – FHWA meetings required.
- Development of IJR simulation models for the Preferred Alternative:
 - 2018 Existing Conditions
 - 2025 and 2045 No-Build Conditions
 - 2025 and 2045 Build Conditions
- VISSIM model simulation – walk-through meeting with FHWA and VDOT.
 - Will include base model summary and calibration of existing model
- Interim results review – submittal of revised/post-processed Measures of Effectiveness (MOEs).
- Submittal of Draft IJR document.
- Concurrent VDOT/FHWA review of Draft IJR document.

- Comment resolution meeting with FHWA and VDOT.
- Comments responses and IJR revisions – Prepare Final IJR document.
- Submit Final IJR document – Northern Virginia (NOVA) District Office => VDOT Central Office => FHWA Virginia Division Field Office => FHWA Headquarters.
- 30 days required for VDOT and FHWA final review processing to issue a *Finding of Engineering and Operational Acceptability* => Confirmation of NEPA compliance => **Final IJR Approval.**

Interstate Access Request Review occurs on 3 levels:

- **Traffic forecasts** – VDOT Northern Regional Operations (NRO) - Traffic Engineering and Transportation Planning.
- **Draft IJR Report** – VDOT NOVA District Office, VDOT Central Office, FHWA Virginia Division, and FHWA Headquarters (HQ).
- **Final IJR Report** – VDOT Central Office, FHWA Virginia Division, and FHWA HQ.

ASSUMPTIONS

Study Area Limits

The Project Footprint Study Area for the I-495 NEXT Project spans I-495 from the Dulles Toll Road interchange (Route 267) to the American Legion Bridge (north of the George Washington Memorial Parkway [GWMP]). The Traffic Operational Analysis Study Area includes the full extent of the Project Footprint Study Area as well as one additional intersection north and south, extending from just south of the Chain Bridge Road (Route 123) interchange to the bridge over Seven Locks Road in Maryland, which is just south of the Cabin John Parkway interchange. The Traffic Operational Analysis Study Area also includes the following interchanges and intersections:

- The GWMP from I-495 to the bridge over Turkey Run loop road, which is just west of the Turkey Run Farm interchange
- Clara Barton Parkway and its interchange with I-495, including all ramps at that interchange, from a location just east of the Clara Barton Parkway/Carderock interchange to a location just east of the Clara Barton Parkway/Clara Barton Access Road interchange
- Georgetown Pike (VA Route 193), including its interchange with I-495 and all ramps, ramp terminals and road segments contained therein, as well as the section of Georgetown Pike from the Spring Hill Road intersection to the Dead Run Drive intersection, including intersections with: Swinks Mill Rd, Linganore Drive/Helga Place and Balls Hill Road
- Old Dominion Drive (VA Route 738), from the Spring Hill Road intersection to the Balls Hill Road intersection, including the intersections at the termini and the intersection with Swinks Mill Road
- Swinks Mill Road (VA Route 684) from its intersection with Georgetown Pike to its intersection with Lewinsville Road, including the intersections at the termini and its intersection with Old Dominion Drive
- Lewinsville Road (VA Route 694), from its intersection with Spring Hill Road to its intersection with Dolley Madison Road, including the intersections at the termini and its intersections with Swinks Mill Road and Balls Hill Road
- Chain Bridge Road (VA Route 123), including its interchange with I-495 with all ramps, ramp terminals and road segments contained therein, as well as the section from its intersection with Tysons Blvd/Tysons Mall Ring Road entrance to its intersection with Great Falls Street / Lewinsville Road, inclusive, and its intersections with Old Meadow Road / Capital One Tower Drive, Scotts Crossing Road / Colshire Drive, and Anderson Road / Dulles Toll Road Connector ramp terminal within that section

- Dulles Toll Road (VA Route 267) / Dulles Airport Access Road from just west of the Spring Hill Road to the bridge over Magarity Road, which is east of the Dulles Toll Road / Dolley Madison Boulevard (VA Route 123) interchange
- Spring Hill Road (VA Route 684), including its interchange with Dulles Toll Road with all ramps, ramp terminals and road segments contained therein, and the section of Spring Hill Road from its intersection with Georgetown Pike to its intersection with Tyco Road/Jones Branch Road intersection, inclusive, and its intersections with Old Dominion Drive and Lewinsville Road within that section

Figure 1 shows the various components of the project study area for the I-495 NEXT Project:

- **Yellow – Project Footprint Study Area.** The I-495 NEXT Project Study area includes I-495 from the Dulles Toll Road interchange to the American Legion Bridge, including all ramp termini of interchanges over that section
- **Blue – Traffic Operations Analysis Study Area.** The Traffic Operations Analysis Study Area, described in detail above, includes the full extent of the Project Footprint Study Area as well as one interchange north and south on I-495, and a number of additional intersections and interchanges which directly affect, and are affected by operations on I-495 within the Project Footprint Study Area

Figure 1: Project Study Area



Data Collection

Traffic Volumes

Intersection turning movement counts were conducted for a 15-hour time period from 5 AM to 8 PM which would include AM and PM peak period. For mainline segments, traffic counts were conducted before and after each major interchange along with all the ramps in the Study area. Data was collected in May and June 2018, prior to the end of the school year, and was summarized in 15-minute intervals.

Traffic count locations are shown in Figure 2 and listed in **the I-495 NEXT Traffic Operation Analysis Framework Memorandum**.

Traffic volumes used in the traffic and operations analysis will consist of the following:

- **Existing (2018)** – Developed from field counts (ramps, freeway mainline, and intersection turning movements) conducted during typical weekdays in May and June 2018 while Fairfax County schools were still in session. Traffic counts were taken on the same days as other locations wherever possible to minimize variability in the calibration process. Count data will be post-processed and balanced between all adjacent locations in the traffic operations analysis study area.
- **Opening Year (2025)** – No Build and one Build alternative developed through modifications to the MWCOG 2025 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.
- **Design Year (2045)** – No Build and one Build alternative developed through modifications to the MWCOG 2045 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.




Figure 2: Traffic Count Locations

Origin-Destination Data

The traffic simulation modeling effort will route vehicles through the traffic network according to origin-destination routing. Origin-destination data will be reviewed from the following sources:

- StreetLight Data, which via a VDOT subscription provides customized origin-destination data with a very high level of spatial accuracy based on aggregated cellular device GPS/location-based services data. StreetLight Data allows for a user to provide custom origins and destinations, such as on- and off-ramps for all freeways in a study area or entry/exit links to a study area. It is anticipated that StreetLight Data will be used as the basis for origin-destination routing for the existing conditions traffic analysis, at the very least for the freeway and ramp segments of the study area.
- MWCOC regional travel demand model, which outputs O-D matrices for various vehicle types between each traffic analysis zone (TAZ) in the Washington, DC, metropolitan area. The travel patterns within the model base year (2017) have been calibrated against 2007/2008 regional household travel survey data, so the travel patterns are somewhat dated. Additionally, this dataset is not as granular as needed to account for freeway weaving proportions. However, given that the travel demand model provides O-D matrices for future years, it is anticipated that these may be used as the basis for vehicle routing in future analysis year scenarios.

Speeds and Travel Times

Floating car travel were conducted in June 2018 during the AM and PM peak periods. Wherever possible, travel times were collected on the same days as traffic counts to minimize variability in the calibration process. Travel time segments are listed in the **I-495 NEXT Traffic Operation Analysis Framework Memorandum**.

Time Periods:

- Weekday (Tuesday, Wednesday or Thursday) AM Peak Period: runs beginning no earlier than 5:30 AM and concluding not later than 9:30 AM
- Weekday (Tuesday, Wednesday or Thursday) PM Peak Period: runs beginning no earlier than 3:00 PM and concluding not later than 7:00 PM

In addition, INRIX vehicle probe speed data has been queried for the corridor using the RITIS Congestion Scan tool, which provides a “heat map” of vehicle speeds temporally and spatially along a corridor. This data has been pulled for “average weekdays” (Tuesday, Wednesday, and Thursday) for the 12 most recently available months of data (July 2017 through June 2018).

Queueing Data

Queueing within the study area is notably inconsistent and can oscillate numerous times within the peak periods, or be absent altogether on some days. A qualitative subjective assessment will be conducted for queue lengths at targeted locations in addition to the review of freeway mainline congestion/queues against the speed heat maps. Queueing along the freeway segments of the corridor will be provided via the INRIX heat map and verified against Google Maps’ typical traffic. Queueing along arterials and ramps will be obtained via screen captures from Google Maps’ typical traffic. Targeted spot locations and the methodology have been identified in the I-495 NEXT Traffic Analysis Microsimulation Calibration Methodology Memorandum. This memorandum was approved and signed by the VDOT NoVA District Traffic Engineer on July 27, 2018.

Analysis Scenarios


All analysis scenarios will be evaluated against the typical weekday AM peak period and PM peak period. The exact hours of analysis hours will be determined after assessing the traffic data and diurnal patterns.

- **Existing Conditions** – Calibrated against 2018 traffic conditions and the 2017 MWCOC model.
- **No-Build (w/ CLRP) Conditions (2025 and 2045)** – The 2025 and 2045 No-Build scenario assumes the existing transportation system in addition to all projects funded for construction in the *National Capital Region's Draft 2017 CLRP* through 2025 and 2045. The TPB adopted the 2016 CLRP in November 2016. Some of the regionally significant and corridor-specific projects include the following (taken from <http://www.mwcog.org/clrp/projects/highway.asp>):
 - I-495 Managed Lanes / I-270 Managed Lanes in Maryland
 - Transform I-66 Outside the Beltway – widening and express lanes, plus HOV-3
 - Transform I-66 Inside the Beltway – widening and dual-direction express lanes by 2045, plus HOV-3; note that the regional CLRP assumes that by 2045, I-66 is tolled in both directions during the peak period east of I-495, but it currently is only tolled in one direction in the peak period (eastbound in the AM and westbound in the PM).
 - Dulles Toll Road interchange ramps and Dulles Airport Access Road ramps by 2030
 - Metro Silver Line Extension to Dulles Airport and Loudoun County
 - Completion of the Jones Branch Connector
- **Build Conditions** – Assumes the No-Build configuration as a base condition and will reflect geometry, access points, and lane configuration proposed in the preliminary I-495 express lanes design concepts developed by the NEPA team and preliminary design team. The Consultant team will code express lanes, new access points, and other network changes, along with updated traffic demand and routing decisions for the 2025 and 2045 Build scenarios.

Proposed Modifications in Access (Express Lanes Access Alternatives)

Proposed modifications in access will be determined as part of the Preliminary Engineering and Options Development. The Consultant Team will use an iterative process to refine and improve roadway design based on traffic operations results. For this process, the team will develop “mini” VISSIM models for access options which will be utilized to test and evaluate traffic impacts of concept refinements. The Consultant Team will incorporate these improvements and additions that are ultimately adopted for the build concept into the overall VISSIM models used to perform the traffic analysis for the IJR. Any modifications in access adopted for the build concept will be documented in the IJR.

Figure 3: Alternatives / Options Development and Screening Process



Drafts of the Express Lane access locations for an interim year (2025) and a Preferred Alternative (2045) are shown in **Figure 4** and **Figure 5**. VDOT will coordinate with MDOT/State Highway Administration to reach an agreement that will allow HOV-3+ users to get in and out of the Virginia Express Lanes without paying a toll. The existing entrance to the southbound I-495 Express Lanes will be modified to account for the proposed system connection with Maryland’s future Express Toll Lanes, and a new entrance ramp from the general purpose lanes is anticipated to be constructed north of the American Legion Bridge as part of Maryland’s project.

VDOT is considering potential phasing of the project improvements at the Dulles Interchange. This includes constructing the proposed southbound Express Lanes ramp to eastbound Dulles toll Road (Route 267). The ramp will be included in the NEPA action / footprint and will be included in the design horizon year (2045) in the IJR, but will be assumed as not part of the opening year (2025) in the IJR.

Figure 4: Express Lane Access Movements Interim Year 2025





Figure 5: Express Lane Access Preferred Alternative 2045



Travel Demand Modeling Methodology and Key Assumptions

The latest MWCOG travel demand model version based on the 3,722 traffic analysis zone (TAZ) system will be used in conjunction with Round 9.1 Cooperative Forecasts (socioeconomic data) for the Existing, Opening, and Design model years. The MWCOG model base year is 2017; a project Existing Conditions (year 2018) model will be prepared, modified and calibrated to reflect field counts. Modifications will be carried forward into future analysis year model scenarios.

The MWCOG model will be strategically modified with specific alterations to improve the accuracy and reliability of forecasts for the I-495 study corridor, roadways connected to the corridor, and transit services in the vicinity of the corridor. The calibration targets will be based on guidance from the FHWA Transportation Model Improvement Program (TMIP) *Travel Model Validation and Reasonableness Checking Manual* and the Virginia *Travel Demand Modeling Policies and Procedures Manual*. Because the MWCOG/TPB Model is already subject to scrutiny as a regional model which has been a subject of FHWA's TMIP Peer Review process, the validation process for the I-495 Project NEXT model will focus on the I-495 Traffic Operations Analysis Study Area and will compare: daily counts versus model forecasts, peak period traffic counts to modeled data during the same periods, and AM and PM observed speeds and travel times to model speeds and travel times.

Toll Diversion Curves from OP3's consultant, based on existing express lane usage on the Capital Beltway Express Lanes, will also be validated in order to increase confidence in the model and maintain relative consistency between traffic and revenue studies for I-495 in Virginia, and regional planning studies of MDOT's proposed managed lanes system in Maryland. The MWCOG model will be used as the starting point for estimating usage of the Express Lanes and the breakdown of toll-paying versus HOV trips. The MWCOG model is a "four-step," trip-based regional travel demand model with a macroscopic, static equilibrium traffic assignment. Toll values provided as inputs in dollars are converted to value-of-time for the assignment process. These toll values can vary according to different vehicle classes and time of day; additionally, tolls can be represented by a fixed point or be distance-based tolls (as is the case with the Express Lane system in Northern Virginia). The model uses a speed feedback (SFB) loop which iterates through all four steps to ensure that travel speeds output from the traffic assignment are the same as those used as inputs to the trip distribution and mode choice. Output volumes from the model will be post-processed using NCHRP 255/765 guidance.

Travel demand forecasting activity will be coordinated between the traffic and revenue study, IJR, and NEPA effort in order to maintain consistency in forecasting among these efforts to the maximum extent practical. Alterations to the MWCOG travel demand model to improve corridor calibration may include:

- Highway network modifications to better represent study area facilities as they exist and are planned, such as modifications to link facility types. Ramps will be micro-coded to improve forecasts and correlation to the microsimulation process.
- Traffic Analysis Zone (TAZ) splits and centroid connector location changes to improve model loading for all modeled modes of transportation.
- Changes to external trip assumptions to improve consistency with origin-destination data and traffic and revenue evaluations.
- Use of toll diversion methodology to forecast Express Lane trips.
- Changes in the time-of-day distribution to improve forecasting of peak period trips, changes in the Volume Delay Function (VDF) curves, and changes in the default speed and capacity of some facility types.

Key assumptions associated with the travel forecasting process are included in the **I-495 NEXT Travel Demand Forecasting Framework Memorandum**.

Methodology and Key Assumptions for Post-Processing of Modeling Results

Post-processing of travel demand model output is necessary to develop traffic volume forecasts for analysis of operations during peak periods/peak hours. Post-processing of travel demand forecasts for vehicular volumes will follow NCHRP 255/765 guidelines and the TFlowFuzzy methodology included in the VISUM planning tool for estimating balanced No-Build and Build peak period volumes. The post-processing methodology will account for peak spreading of demand, as the hourly capacity of a given link will be used as a threshold for forecast volumes. Forecasted volumes above this threshold will be post-processed onto adjacent shoulder hours.

Existing balanced volumes will be developed outside of the MWCOC travel demand model using field count data; origin-destination (O-D) routing will be obtained utilizing StreetLight Data and the O-D matrix will be adjusted using VISUM's TFlowFuzzy methodology to match target balanced volumes along the corridor.

Traffic Operational Analysis Methods/Parameters

Traffic Analysis Tools

VISSIM Version 9.0, Build 13 will be used for a comprehensive network traffic analysis performed within the study area limits. (Reference analysis tool selection matrix, *VDOT Traffic Operations and Safety Analysis Manual [TOSAM] V1.0*¹, Appendix D.) Additional calibration, based on simulated volume processed, travel times, queues, and speed profiles, will be performed against 2018 measured field conditions and traffic data.

Surface street intersection operations will be evaluated through a combination of Synchro 10 (in order to develop preliminary optimization for phasing and signal timing) and VISSIM (for microsimulation and analysis). Transit routes and stops will be coded into the study area VISSIM network where they affect or could affect I-495 and related facility operations.

Vehicle Classes

The following vehicle classes will be assumed for the traffic operations analysis VISSIM modeling:

- General purpose (non-toll-paying) cars
- HOV3+ cars
- HOT (toll paying) cars
- GP (non-toll-paying) trucks
- HOT (toll paying) trucks

Measures of Effectiveness

The following measures of effectiveness (MOEs) will be used for the operational analysis of the roadway network under existing and future Build and No-Build conditions. Wherever possible, MOEs will be provided in graphical format or GIS maps. These MOEs will be developed according to guidance from the VDOT TOSAM.

¹ <http://www.virginiadot.org/business/resources/TOSAM.pdf>

Freeway Performance Measures

- Simulated Average Speed (mph)
- Simulated Average Density (simulated vehicles per lane per mile, color-coded similar to the analogous HCS Density-Based LOS Thresholds but not reported as LOS)
- Simulated Volume (vehicles per hour)

The VISSIM freeway MOEs will be reported for each freeway segment. Methodology for the merge/diverge/weave segment analyses will be consistent with procedures outlined in the *Highway Capacity Manual* for the area of influence within the designated segments. This methodology will be consistent with the TOSAM. In addition, the following freeway MOEs also are proposed for reporting in the IJR:

- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).
- **Simulated Ramp Queue Length.** Reported average and maximum queue lengths (feet).
- **Simulated Travel Time.** Reported for select network origin-destination travel paths (seconds).
- **Congestion Heat Maps.** Incremental speeds reported for aggregated lanes, by time interval (mph).

Additionally, for freeway segments, lane-by-lane MOE graphics will be produced showing individual lane speeds and densities.

Arterial/Intersection Performance Measures

- **Simulated Intersection Level of Service (LOS) and Average Control Delay.** Reported by approach and by intersection (seconds per simulated vehicle, color-coded in similar fashion as the analogous Highway Capacity Manual (HCM) Delay-Based LOS Thresholds but again not reported as LOS). Delay will be reported as “microsimulation delay” per guidance from the VDOT TOSAM.
- **Simulated Intersection Approach Queue.** Reported by movement (feet).
- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).

Traffic Modeling Methodology and Main Assumptions

Calibration Methodology for Base Models

The VISSIM base models will be calibrated based on guidance from the *VDOT Traffic Operations and Safety Analysis Manual (TOSAM)*, Version 1.0 which takes into account the FHWA guidance. Figure 6 shows the criteria and acceptance targets from the TOSAM.

Figure 6: VDOT TOSAM Calibration Criteria and Acceptance Targets

Simulated Measure	Calibration Threshold	
<p>Simulated Traffic Volume (vehicles per hour) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds. The traffic volumes identified in the calibration thresholds are actual traffic volumes as opposed to simulated traffic volumes.</p>	<p>Within ± 20% for <100 vph Within ± 15% for ≥100 vph to <300 vph Within ± 10% for ≥300 vph to <1,000 vph Within ± 5% for ≥1,000 vph</p>	
<p>Simulated Average Speed (miles per hour) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds.</p>	<p>Within ± 5 mph of average observed speeds on arterials Within ± 7 mph of average observed speeds on freeways</p>	
<p>Simulated Travel Time (seconds) Eight-five percent (85%) of the travel time routes, or a select number of critical routes, as determined by the RTE or his/her designee, shall meet the calibration thresholds. Travel time routes should be determined in cooperation with the VDOT project manager based on project needs and goals.</p>	<p>Within ± 30% for average observed travel times on arterials Within ± 20% for average observed travel times on freeways The travel time should be calibrated for segments and routes separately or as deemed appropriate by the VDOT project manager.</p>	
<p>Simulated Queue Length (feet) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds.</p>	<p>Undersaturated conditions (refer to Section 2.6 for guidance)</p>	<p><i>Average queue length on arterials:</i> Within ± 30% for movements ≤10 vph Within ± 20% for movements >10 vph</p>
		<p><i>Maximum queue length on arterials:</i> Within ± 25%</p>
	<p>Oversaturated conditions (refer to Section 2.6 for guidance)</p>	<p><i>Average queue length:</i> Within ± 20% on arterials Within ± 30% on freeways</p>
		<p><i>Maximum queue length:</i> Within ± 20% on arterials Within ± 35% on freeways</p>

Table 1 shows the criteria and thresholds proposed for VISSIM model calibration. The criteria listed below deviates from TOSAM requirements for simulated average speeds and simulated queue length. Speeds are highly variable on the interstate mainline as well as on the local arterial network and residential roadways, and can vary substantially by hour and by day. Instead, the simulated average speed will be captured as part of the travel time calibration process and the visual review of bottleneck locations against speed heat maps will be conducted. Average speeds will still be extracted from the VISSIM models along the freeway corridors (I-495 general purpose, I-495 HOT, and SR 267) at one-half mile intervals and compared visually against speed heat maps generated from INRIX vehicle probe data.

Similarly, queuing within the study area is notably inconsistent and can oscillate numerous times within the peak periods, or be absent altogether on some days. A qualitative subjective assessment will be conducted for queue lengths at targeted locations in addition to the review of freeway mainline congestion/queues against the speed heat maps. The targeted locations have been identified in **I-495 NEXT VISSIM Calibration Memorandum** which was approved and signed by the VDOT NoVA District Traffic Engineer on July 27, 2018

Table 1: VISSIM Calibration Criteria and Acceptance Targets

Calibration Item	Basis	Criteria	Target
Simulated Traffic Volume (Intersections)	By Intersection Approach	Within $\pm 20\%$ for <100 vph	At least 85% of all Intersection Approaches
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Traffic Volume (Freeways)	By Freeway Segment	Within $\pm 20\%$ for <100 vph	At least 85% of all Freeway Segments
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Travel Time	By Route	Within $\pm 30\%$ for average travel times on arterials	At least 85% of all Travel Time Routes (Including Segments)
		Within $\pm 20\%$ for average travel times on freeways	
Maximum Simulated Queue Length	By Approach for Targeted Critical Locations	Modeled queues qualitatively reflect the impacts of observed queues	Qualitative Visual Match
Visual Review of Bottleneck Locations	Targeted Critical Locations	Speed heat maps qualitatively reflect patterns and duration of congestions	Qualitative Subjective Assessment

Potential Adjustments for Calibration

Adjustments to the VISSIM model during the calibration process will follow guidance from the VDOT TOSAM. These adjustments could include modifications to lane change distance for connectors, driver behavior along freeways and arterials, adjustments to desired speeds for vehicles at the network termini (such as along I-495 northbound leaving the study area), etc. The technical memorandum detailing calibration results will identify any potential deviations from TOSAM guidance.

Quality Control and Assurance

The development of VISSIM models includes an extensive quality assurance/quality control process. All network inputs entered by a modeler will be checked by another modeler not associated with the development of the section. All routes and signal settings will be checked by a second modeler different from the one who entered the inputs into the VISSIM models. Close coordination will be maintained throughout the modeling effort to incorporate adequate geometric improvements into the VISSIM models.

Seeding Time, Simulation Time, and Number of Runs

After assessing the existing traffic counts and the diurnal patterns, the initialization/seeding time and the model simulation run time will be determined. Figure 7 shows the INRIX speed heat map for the I-495

northbound general purpose lanes (pulled from RITIS for average Tuesdays, Wednesdays, and Thursdays from July 2017 to June 2018) and proposed analysis time periods and “network representative” or peak hours (for volume balancing purposes and MOE summaries). Upon review of the INRIX speed data, the slowest speeds and heaviest queues during both the AM and PM are along I-495 northbound.

- AM: proposed analysis period from 6:45 AM to 9:45 AM; network representative hour from 7:45 AM to 8:45 AM. Queue spillback is tied to the on-ramp from GWMP and the weave across the American Legion Bridge, with the slowest speeds and longest queues occurring during the peak hour.
- PM: proposed analysis period from 2:45 PM to 5:45 PM; network representative hour from 3:45 PM to 4:45 PM. During the early afternoon hours (after approximately 2 PM), queue spillback and congestion along I-495 northbound is again tied to the on-ramp from GWMP and the weave across the American Legion Bridge. During the later afternoon hours (after approximately 3:30 PM, queues from downstream congestion in Maryland have spilled back across the American Legion Bridge, resulting in a single continuous queue. At this point, the back of the queue is observed to stabilize for several hours, essentially suggesting that demand is not increasing and being processed at the same rate as it arrives.

The model simulation period will be longer than the three-hour analysis period, as a seeding period will be provided prior to this analysis period to allow traffic volume to load into the network. The actual seeding period time will be established during the calibration process. MOEs will be reported for all three hours of the analysis period.

Given the stochastic nature of the VISSIM models, they need to be run with several different random seeds (to be determined based on statistical analysis) and the results need to be post-processed and averaged to determine the current state of traffic operations in the corridor. The total number of runs necessary for the analysis will be determined based on guidance from the TOSAM. The VDOT Sample Size Determination Tool, which was developed based on FHWA’s statistical process to ensure that an appropriate number of microsimulation runs are performed at a 95th percentile confidence level, will be used per guidance from the TOSAM.

Demand Review

As shown in Figure 7, the study area experiences severe congestion for several hours each day. The I-495 corridor is oversaturated and processes less traffic than its capacity, as observed in existing field counts. The existing demand is likely much higher than these processed throughput counts. The project team has received estimated demand volumes from Maryland SHA for overlapping segments of the project study area (from just south of Georgetown Pike to all points north). VISSIM inputs may be revised using an iterative manual process taking into account MDSHA demand estimates and unconstrained 15-minute flow data from various input locations. The INRIX data allows for estimation of the duration and distance of queues along the I-495 mainline, which can in turn be used to estimate the unserved demand during the peak period. The end result will still be a VISSIM model in which demand has been increased, but throughput aligns with balanced counts and speeds match field data.

SAFETY ANALYSIS

A safety analysis will be conducted, consistent with VDOT IIM-LD-200.9. The analysis will involve the analysis of existing highway safety conditions and reported motor vehicle crashes on roads in the study area for a period of five (5) years, and the development of qualitative and quantitative measures to evaluate proposed alternatives and assess the safety effects of interstate access modifications on I-495 and the adjacent arterial network within the study area. The Enhanced Interchange Safety Analysis Tool (ISATe) will be used to evaluate the quantitative safety impacts of interstate access modifications on I-495. Since the ISATe model was not developed for and is therefore not appropriate for the analysis of facilities with express lanes, this proposed safety analysis will feature the development of Safety Performance Functions for express lanes and inclusion of crash predictions from the application of those functions. In addition, Highway Safety Manual (HSM) methodologies will be used to evaluate the quantitative safety effects of the proposed interstate access modifications, notably geometric changes at the interchanges and ramp terminals on the intersecting arterial system adjacent to the interchanges and the resulting changes in traffic volumes projected to occur. In addition, a qualitative safety analysis will be performed.

Reported Crash Data, Crash Summaries & Collision Diagrams

Data on motor vehicle crashes reported on I-495 mainline, ramps, Collector-Distributor Road sections, selected arterial segments and at-grade intersections within the IJR study area will be analyzed and summarized. Data on reported crashes from January 1, 2013, to December 31, 2017, will be solicited and obtained from the Virginia Department of Transportation, the Maryland Department of Transportation, and the National Park Service for roads in the study area that were previously identified for the traffic operations analysis. The study area includes sections of the George Washington Memorial Parkway and sections of the Clara Barton Parkway, which are maintained by NPS, and sections of I-495 in Maryland which are maintained by the MDSHA of the MDOT.

The crash data will be summarized in a tabular format for up to 10 crash factors, such as weather conditions, lighting conditions, type of collision, day-of-week/time-of-day, and severity of crash, among others. The data will be summarized to identify trends in reported crashes, crash patterns and high-crash locations.

Crash location maps and crash density “heat” maps will be developed to display the following crash types along the I-495 study corridor:

- Total number of crashes
- Fatal + Injury crashes
- Crashes reported during the Weekday AM peak period (e.g., 5 AM to 10 AM)
- Crashes reported during the Weekday PM peak period (e.g., 3 PM to 8 PM)
- Rear-end crashes
- Sideswipe, same direction crashes
- Fixed-object, ran-off-road crashes

Mainline crash density histograms will be developed for I-495 from the Dulles Toll Road (VA 267) to the American Legion Memorial Bridge over the Potomac River, summarized in logical segments. The type and severity of crashes for each segment within the safety analysis study area also will be summarized.

Crash rates will be estimated and summarized, in tabular format, for the I-495 general purpose lane segments for the latest 5-year period and compared using the following crash rates provided by VDOT Central Office:

- Total Crash rates and Fatal+Injury crash rates for all Interstates in Virginia
- Total crash rates and Fatal+Injury crash rates for the Capital Beltway, which includes sections of I-495 and I-95 in Virginia.

Exposure estimates for the calculation of crash rates will be based on best available estimates of Average Annual Daily Traffic (AADTs). The results of this safety analysis will be used during the preliminary design phase of the project and during the development and screening of proposed interchange concepts phase of the project.

A field review will be conducted to complement the analysis of crashes reported over the five-year period. The results of this field review will be summarized in a brief technical memorandum to be used during the development of the design concepts. Crash trends and crash patterns will be described within hot spot locations.

Qualitative Analysis

A qualitative analysis of proposed improvements for one Preferred Build alternative will be completed. Engineering judgment, human factors analysis techniques to assess the ability of drivers to safely perform driving task and make speed, steering, and navigational decisions, and published literature will be used in this qualitative safety assessment. Concept plans will be reviewed and potential safety issues that warrant mitigation will be identified. These potential safety deficiencies will be identified in description detail, and the rationale for the safety concern will be documented in a concise memo. Extensive use will be made of relevant documents, positive guidance principles, human factors manuals, guidelines and processes for highway engineers and geometric design, and NCHRP and FHWA reports on safety effects related to interchanges, intersections, freeways, arterials, and ramp junctions. Notable documents include NCHRP report 600, "Application of Human Factor Guidelines for Road Systems", AASTHO's "Highway Safety Design and Operations Guide" (i.e., the old AASHTO Yellow Book), ITE's "Human Factors Issues in Intersection Safety," FHWA reports such as "Driver Expectations When Navigating Complex Interchanges, materials cited in the National Highway Institute's "Human Factors for Transportation Engineers," and other relevant literature, such as "Human Factors Associated with Interchange Design Features." Drivers, often have difficulties following through the sequence of driving tasks, which leads to driving errors. The most common driving errors include improper lookout (faulty visual surveillance), inattention, false assumption, excessive speed, improper maneuvers, improper evasive action, and internal distraction.

The objective of the qualitative safety analysis is to identify assess the relative level of safety that is likely to result from proposed improvements by considering the potential effect of the following on driver expectancies, the demands on and capabilities of the driver to perform all subtasks of the driving tasks, driver information processing capabilities, and driver decision making capabilities especially at route choice decision points:

- Geometric characteristics, including grades, vertical alignment, horizontal alignment, cross-sections,
- Roadside features.
- Conflict points

- Traffic operations, including weaving, lane changing, merging, diverging and stopping
- Relative safety hazards

A brief summary of the qualitative safety assessment for the Preferred Build alternative will be prepared.

Quantitative Analysis

A quantitative analysis to evaluate the No-Build scenario and the benefits of the proposed improvements for the I-495 general purposes mainline and ramps associated with the Preferred Build improvement conditions. To minimize cost and schedule impacts, the quantitative analysis will be performed using an approach tailored to fit the intended purpose of the IJR document.

For the IJR, a planning-level crash analysis will be performed using the aforementioned tools to compare only the differences between the No-Build and Preferred Build alternatives corresponding to I-495 interchanges, freeway segments, ramp segments, intersections, and arterials affected by new ramps or access to/from the Express Lanes facility.

Assumptions regarding safety and crash analysis:

- Safety analyses will only be conducted on the roadway sections identified in the study area, consisting of interstate mainline segments, ramp segments, C-D Road segments, ramp termini, and at selected at-grade intersections.
- ISATe will be used to evaluate freeway and interchange safety for the general purpose lane sections, based on FHWA/AASHTO regulations and guidance. Using reported crash history and best available exposure estimates for the sections of the I-495 Express Lanes, safety performance functions will be developed for Express Lane sections. Then, those safety performance functions will be applied to develop estimated crash predictions for the future years (2025 and 2045) for both the No-Build and the Preferred Build alternatives.
- HSM NCHRP 17-38 spreadsheets (Virginia edition) will be used to analyze 5 years of continuous crash data for the crossroad segments. ISATe will be used to analyze the crossroad ramp terminal intersections within these segments.
- Freeway analysis will be limited to the I-495 mainline facility, and no analysis will be performed for the Express Lane facility, since current analysis tools do not provide for crash prediction and safety performance evaluation on Express Lane facilities.
- Quantitative analysis will be performed within the analysis limits of the available safety analysis tools; however, it should be noted that some geometric configurations are not able to be modeled using these tools. In these situations, qualitative analysis will be incorporated into the evaluation to supplement any gaps in the quantitative analysis.
- All crash data will be provided by VDOT in GIS shapefile or geodatabase format. The consultant team will rely on the crash data directly from the VDOT Roadway Network System (RNS) and will not review individual crash reports to verify the accuracy of the information.

Deliverables

- Crash field review technical memorandum

- Existing safety conditions memorandum
- Qualitative Safety Assessment of the Preferred Build Alternative memorandum
- Crash/safety analysis sections for the IJR and TTR.

REPORT DELIVERABLES

The following documents will be produced as deliverables during the course of the project and for the culmination of analysis and data collection.

- **Existing Conditions Technical Memorandum.** The following will be included within the Existing Conditions Technical Memorandum:
 - Data collection overview
 - Review of volumes development process (describing count data post-processing and volume balancing)
 - Travel demand forecast model calibration and outputs
 - Traffic simulation model calibration
 - Documentation of existing conditions (outputs from traffic simulation model supplemented by discussion of field conditions)
 - Safety analysis for the study area
- **Draft Traffic and Transportation Report (TATTR).** Prepared in support of the EA (to be included as an appendix to the NEPA documentation). For the entire study area, a technical report will be prepared to document and support all analysis that is performed for the determination of traffic volume forecasts, traffic impacts as they relate to NEPA and the proposed action, the inputs and analysis that feed the Air Quality Analysis, and the data to support the Noise Analysis. This document also will be used as a supporting technical report for the system-wide IJR described below.
- **Final TATTR.** Incorporate VDOT/FHWA comments and submit modified document that will secure interstate access approval from FHWA. It is assumed that concurrent reviews will occur on the preliminary Final TATTR, with a consolidated set of review comments at the conclusion of the draft review.
- **Draft IJR.** Incorporate traffic engineering and operational analysis as well as results from the VAP3's Proposed Design Plans and EA into the IJR. IJR will be prepared based on the guidance set forth in IIM-LD200.9 with exceptions to be consistent with the May 2017 update to FHWA policy on NEPA and IJR's per VDOT's direction. This document will note any potential Limited Access changes required, as well as any potential Design Exceptions or Design Waivers being requested. The IJR will also include a discussion on the use of available typical section width and how that width will be distributed for the proposed typical, showing a hierarchy for distributing the available width between shoulders, travel lanes, and median width. A draft version of the document will be provided to VDOT Central Office and FHWA (Virginia Division Office and Headquarters Office) for review and comments. For budgeting purposes, it is assumed that concurrent reviews will occur, with a consolidated set of review comments at the conclusion of the draft review.
- **Final IJR.** Incorporate VDOT and FHWA comments and submit modified document that will secure IJR approval from FHWA. It is assumed that concurrent reviews will occur on the preliminary Final IJR, with a consolidated set of review comments at the conclusion of the preliminary final review.

Review Process

It is anticipated that a two-week comment period will be provided for review of the Draft IJR. These comments will be addressed within 3 weeks of being received upon which a final report will be submitted.

Accepted and agreed upon by FHWA & VDOT:

Virginia Department of Transportation Northern Virginia District/Virginia MegaProjects Project Manager	Date
---	------

Virginia Department of Transportation Northern Virginia District/Virginia MegaProjects Project Director	Date
--	------

Virginia Department of Transportation Northern Virginia District/Traffic Engineering	Date
---	------

Virginia Department of Transportation Northern Virginia District/Location and Design	Date
---	------

Virginia Department of Transportation Central Office	Date
---	------

FHWA Virginia Division Office	Date
-------------------------------	------

MEMORANDUM

To: Rahul Trivedi, P.E., VDOT NoVA District Transportation Planning Manager
Amir Shahpar, P.E., VDOT NoVA District Modeling Manager
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E.
Raj Paradkar, P.E.
Anthony Gallo, P.E.
Sarah Knox, P.E.
Kimley-Horn and Associates, Inc.

Date: August 26, 2018

Subject: I-495 NEXT Travel Demand Forecasting Framework

Introduction

This memorandum documents the travel demand forecasting framework associated with the I-495 NEXT Project. This memorandum is intended to supplement the overarching I-495 NEXT Project Scoping Framework Document.

The following elements of the traffic operations analysis are laid out in detail in this document:

- Travel demand modeling assumptions and calibration/validation
- Traffic volume post-processing for use in traffic operations and air/noise analysis

Travel Demand Modeling Methodology

Existing Conditions Model Calibration and Validation

The latest MWCOG travel demand model version on the 3,722 traffic analysis zone (TAZ) system will be used in conjunction with Round 9.1 Cooperative Forecasts (socioeconomic data) for the Existing, Opening, and Design model years. The MWCOG model base year is 2017; a project Existing Conditions (year 2018) model will be prepared, modified and calibrated to reflect field counts. Modifications will be carried forward into future analysis year model scenarios.

The MWCOG model will be strategically modified with specific alterations to improve the accuracy and reliability of forecasts for the I-495 study corridor, roadways connected to the corridor, and transit services in the vicinity of the corridor. The calibration targets will be based on guidance from the FHWA Transportation Model Improvement Program (TMIP) *Travel Model Validation and Reasonableness Checking Manual* and the Virginia *Travel Demand Modeling Policies and Procedures Manual*. Because the MWCOG/TPB Model is already subject to scrutiny as a regional model which has been a subject of FHWA's TMIP Peer Review process, the validation process for

the I-495 Project NEXT model will focus on the I-495 Traffic Operations Analysis Study Area and will include the following comparisons:

- Regional comparisons to VDOT AADTs at the daily level (daily level only)
 - Percent difference in total volume for cutlines
- I-495 NEXT study area comparisons to field traffic counts (AM/PM periods and daily)
 - R-squared between modeled volumes and counts on links
 - Percent difference in total volumes for freeways/arterials
 - Percent root mean squared error (%RMSE) by volume group or facility type
- Travel time comparisons of model outputs to floating car runs data collected (AM/PM periods only; reasonableness checks only)

Table 1 provides a listing of travel demand model calibration criteria, which were discussed and verbally approved by VDOT during a call on July 24, 2018.

Table 1. Travel Demand Forecast Model Calibration Criteria


Calibration Scale	Calibration Check	Calibration Threshold			
Regional	% Difference in Total Volume for Cutlines (24-Hour Volumes)	Cutline Volume	VTM	FHWA	Proposed
		50,000	10%	35%	10%
		100,000	8.75%	25%	10%
		150,000	7.50%	20%	10%
		200,000	6.25%	18%	8%
		250,000	5%	15%	7%
Study Area	R-Squared between modeled volume and counts on links (AM Period, PM Period, and 24-Hour Volumes)	VTM	FHWA	Proposed	
		0.9	0.88	0.9	
	% Difference in Total Volume by Facility Type (AM Period, PM Period, and 24-Hour Volumes)	Facility Type	VTM	FHWA	Proposed
		Freeways	6%	7%	6%
		Major Arterials	7%	10%	10%
		Minor Arterials	10%	15%	15%
	%RMSE by Facility Type (AM and PM Period)	Facility Type	VTM	FHWA	Proposed
		Freeways	30%	-	30%
		Major Arterials	45%	-	45%
		Minor Arterials	60%	-	60%
		Overall	40%	-	40%
	%RMSE by Facility Type (24-Hour Volumes)	Facility Type	VTM	FHWA	Proposed
		Freeways	20%	-	20%
		Major Arterials	35%	-	35%
		Minor Arterials	50%	-	50%
	Overall	30%	-	30%	
Travel Times (AM and PM Period)	No specific measures in VTM or FHWA; compare model outputs to floating car travel runs and check to see if travel times are within min and max of observed travel times. <u>Note that these are reasonableness checks only.</u>				

The following regional cut-lines will be used in the calibration process:

- East/west travel west of study area
 - Georgetown Pike west of Spring Hill Road
 - Old Dominion Drive west of Spring Hill Road
 - Lewinsville Road west of Spring Hill Road
 - Route 267 between Route 7 and Spring Hill Road
 - Route 7 just east of Route 267
- East/west travel east of study area
 - George Washington Memorial Parkway east of I-495
 - Georgetown Pike east of I-495
 - Old Dominion Drive between Balls Hill Road and Route 123
 - Route 123 east of Lewinsville Road/Great Falls Street
 - Chain Bridge Road east of Great Falls Street
 - Great Falls Street east/south of Chain Bridge Road
 - Route 267 east of Route 123
- North/south travel north of study area
 - I-495 American Legion Bridge
- North/south travel within study area
 - Spring Hill Road south of Georgetown Pike
 - Swinks Mill Road south of Georgetown Pike
 - I-495 south of Georgetown Pike
 - Balls Hill Road south of Georgetown Pike
 - Douglas Drive south of Georgetown Pike
 - Route 123 west/south of Georgetown Pike

Figure 1 shows a map of the proposed cut-lines for the calibration process.

Figure 1. Proposed Cut-Lines for Travel Demand Model Calibration Process.



Toll Diversion Curves from OP3’s consultant, based on existing express lane usage on the Capital Beltway Express Lanes, will also be validated in order to increase confidence in the model and maintain relative consistency between traffic and revenue studies for I-495 in Virginia, and regional planning studies of MDOT’s proposed managed lanes system in Maryland.

Travel demand forecasting activity will be coordinated between the traffic and revenue study, and IJR/NEPA effort in order to maintain consistency in forecasting among these efforts to the maximum extent practical. Alterations to the MWCOG travel demand model to improve corridor calibration may include:

- Highway network modifications to better represent study area facilities as they exist and are planned, such as modifications to link facility types. Ramps will be micro-coded to improve forecasts and correlation to the microsimulation process.
- Traffic Analysis Zone (TAZ) splits and centroid connector location changes to improve model loading for all modeled modes of transportation.
- Changes to external trip assumptions to improve consistency with origin-destination data and traffic and revenue evaluations.
- Use of toll diversion methodology to forecast Express Lane trips.

- Changes in the time-of-day distribution to improve forecasting of peak period trips, changes in the Volume Delay Function (VDF) curves, and changes in the default speed and capacity of some facility types.

Future Analysis Scenario Assumptions

The I-495 NEXT traffic analysis will assess operations for a project Design Year of 2045 and Interim Year of 2025. The traffic analysis will account for a No-Build scenario and one Build alternative. Separate travel demand model networks will be developed for each of the future-year scenarios to be used for forecasting traffic volumes.

The travel demand model No-Build networks will include all roadway projects in the most up-to-date regional CLRP. In addition, the No-Build networks will account for the following elements:

- **I-495/Dulles Toll Road Interchange Ramps** – currently unbuilt ramps at the I-495/Dulles Toll Road, including ramps to and from the I-495 Express Lanes and Dulles Airport Access Road, for which preliminary engineering has completed and construction is anticipated prior to the I-495 NEXT project being in place.
- **Auxiliary lanes along I-495** – general-purpose auxiliary lanes to be added along I-495 between the Dulles Toll Road interchange and the Georgetown Pike interchange
- **Express Lanes in Maryland** – the I-495 NEXT team will be coordinating closely with the Maryland Department of Transportation (MDOT) on plans for a network of express lanes in Maryland, including lanes along I-495 and I-270. These plans are currently ongoing, but the I-495 NEXT No-Build and Build networks will contain the same assumptions for the Express Lanes in Maryland:
 - Locations of access and network structure
 - Vehicle types allowed in express lanes, including those which must pay a toll and those which are exempt (if any) – could include HOV2/HOV3+ or trucks

Summary of Travel Demand Modeling Assumptions

Table 1 lists key assumptions associated with the travel forecasting process.

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments												
<i>Model</i>														
Analysis Years 2018 (Existing) 2025 (Interim Year) 2045 (Design Year)	MWCOG Model 2018 (Validation Year) 2025 2045	MWCOG travel demand model has model inputs at 5-year increments plus a year 2017 input dataset. Intermediate years can be developed by interpolating input data and modifying networks to represent planned conditions.												
Time Periods	Four time periods are modeled in the forecasts. The sum of the four time periods represents average weekday daily traffic: <table border="1" style="margin-left: 20px;"> <thead> <tr> <th>Period</th> <th>Hours</th> </tr> </thead> <tbody> <tr> <td>AM</td> <td>6 a.m. – 9 a.m.</td> </tr> <tr> <td>Midday</td> <td>9 a.m. – 3 p.m.</td> </tr> <tr> <td>PM</td> <td>3 p.m. – 7 p.m.</td> </tr> <tr> <td>Night</td> <td>7 p.m. – 6 a.m.</td> </tr> </tbody> </table>	Period	Hours	AM	6 a.m. – 9 a.m.	Midday	9 a.m. – 3 p.m.	PM	3 p.m. – 7 p.m.	Night	7 p.m. – 6 a.m.	Hours split based on MWCOG household survey data (2007/2008).		
Period	Hours													
AM	6 a.m. – 9 a.m.													
Midday	9 a.m. – 3 p.m.													
PM	3 p.m. – 7 p.m.													
Night	7 p.m. – 6 a.m.													
Speed	Consistent with current conditions in the HOV and general purpose (GP) lanes.	Consistent with existing conditions. Same as speed/travel time curves based on MWCOG unless validation suggests modification.												
Link Capacity	Lane capacities are defined consistent with the MWCOG model approach.	The MWCOG facility and area type capacity tables are used to determine link capacities. Use same speed-flow curves consistent with TPB model unless validation suggests modification.												
Peak Factors	Peak period to peak hour factors: <table border="1" style="margin-left: 20px;"> <thead> <tr> <th>Period</th> <th>2010</th> <th>2025</th> <th>2040</th> </tr> </thead> <tbody> <tr> <td>AM</td> <td>0.417</td> <td>0.38</td> <td>0.34</td> </tr> <tr> <td>PM</td> <td>0.294</td> <td>0.272</td> <td>0.25</td> </tr> </tbody> </table>	Period	2010	2025	2040	AM	0.417	0.38	0.34	PM	0.294	0.272	0.25	Existing peak period values were derived from the 2007/2008 MWCOG Household Travel Survey. The peak hour factors decline in future years in recognition of the increased congestion expected in the region causing less peaked periods. This assumption spreads the traffic evenly over the entire peak period.
Period	2010	2025	2040											
AM	0.417	0.38	0.34											
PM	0.294	0.272	0.25											
Socioeconomic Data	MWCOG Round 9.1 socioeconomic data will be used.													

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments
<i>Network</i>		
Project Description (I-495 Northern Extension)	Two Express Lanes in each direction along I-495 between the Dulles Toll Road (Route 267) and George Washington Memorial Parkway. Specifics to be addressed in the preliminary design effort.	
Project Extent	Dulles Toll Road in Tysons to GWMP near Maryland State Line	
I-495 (Capital Beltway) Express Lanes	Existing: Express Lanes on I-495 between I-95/I-395 and Dulles Toll Road Future: Existing Express Lanes on I-495 plus new Express Lanes in Maryland along I-495 and I-270.	Access, tolling parameters, and vehicle restrictions for I-495 Express Lanes in Maryland to be determined in coordination with MDOT.
HOV	Beginning in 2020, all HOV facilities in the Northern Virginia area are assumed to become HOV-3+.	I-495 and I-95 Express Lanes are free to HOV-3 vehicles currently; HOV lanes along I-66 and Dulles Toll Road are HOV-2 currently. HOV restrictions in Maryland to be determined in coordination with MDOT. See Table 3 for further explanation.
<i>Toll Assumptions</i>		
Tolling Methodology	Tolling assumptions will be kept consistent with MWCOG's default factors for I-495, I-95/395, and I-66 HOT Lanes in the final assignment iteration.	
Toll Approach	Variable toll rates by roadway segment, based on maintaining Express Lane speed goal of 55 mph.	Adopted to account for varying demand levels along the length of the project.
<i>Mode Assumptions in I-495 NEXT Express Lanes</i>		

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments
Vehicle Class	HOV-3+: Free Other cars and medium trucks: Toll Heavy trucks: Are permitted in the I-495 Express Lanes from the Dulles Toll Road to the project terminus north of the GWMP.	Vehicle class restrictions for I-495 Express Lanes in Maryland to be determined in coordination with MDOT
HOV Vehicles	Use the MWCOG model HOV module. Beginning in 2020, all HOV facilities in Northern Virginia area will be HOV-3+.	The HOV estimates provided are an output of the <i>mode choice</i> and <i>carpool occupancy</i> models developed by MWCOG.

Table 3. HOV and Tolling Assumptions for Facilities in Study Area

Facility	2018	2025	2045
I-495 (Existing Express Lanes Network)	All vehicles except trucks permitted in barrier-separated express lanes. All vehicles except HOV3+ must pay a toll.		
Dulles Toll Road (SR 267)	HOV2+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	HOV3+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	
I-66 (Outside the Beltway)	HOV2+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	All vehicles (including trucks) permitted in barrier-separated express lanes. All vehicles except HOV3+ must pay a toll.	
I-66 (Inside the Beltway)	All vehicles except trucks permitted. During AM peak eastbound and PM peak westbound, lanes are tolled except for HOV2+ vehicles.	All vehicles except trucks permitted. During AM peak eastbound and PM peak westbound, lanes are tolled except for HOV3+ vehicles.	All vehicles except trucks permitted. During AM peak and PM peak in both directions, lanes are tolled except for HOV3+ vehicles.

Traffic Volume Post-Processing

Post-processing of travel demand model output is necessary to develop traffic volume forecasts for analysis of operations during peak periods/peak hours. Post-processing of travel demand forecasts for vehicular volumes will follow NCHRP 255/765 guidelines for estimating balanced No-Build and Build peak period volumes. Existing balanced volumes will be developed outside of the MWCOG

travel demand model using field count data; origin-destination (O-D) routing will be obtained utilizing StreetLight Data or the MWCOG model, and the O-D matrix will be adjusted using VISUM's TFlowFuzzy methodology to match target balanced volumes along the corridor. The O-D matrix will be imported into VISSIM for traffic microsimulation analysis.

Traffic volumes for the traffic operations analysis and air quality and noise analyses for future scenarios will be developed using travel demand model outputs and NCHRP 255/765 guidelines. For future scenario VISSIM microsimulation analysis, O-D routing will again be developed using MWCOG model outputs as a seeding matrix and VISUM's TFlowFuzzy process to create an adjusted O-D matrix that matches target forecast volumes in the study area.

Conclusion

The travel demand model methodology and calibration/validation criteria were reviewed with VDOT staff on a call on July 24, 2018. This methodology will be carried forward for travel demand forecasting for the I-495 NEXT project.

MEMORANDUM

To: Ivan Horodyskyj, P.E., VDOT NoVA District Traffic Engineer
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E.
Raj Paradkar, P.E.
Anthony Gallo, P.E.
Kimley-Horn and Associates, Inc.

Date: August 29, 2018

Subject: I-495 NEXT Traffic Operations Analysis Framework

Introduction

This memorandum documents the traffic operations analysis framework associated with the I-495 NEXT Project. This memorandum is intended to supplement the overarching I-495 NEXT Project Scoping Framework Document.

The following elements of the traffic operations analysis are laid out in detail in this document:

- Traffic data collection
- Traffic analysis tools and measures of effectiveness (MOEs)
- Traffic simulation model calibration methodology and assumptions

Traffic Data Collection

Traffic Volumes

The following intersection locations will have traffic counts conducted in the year 2018 and be analyzed as part of the traffic operations analysis:

1. Westpark Drive Connector at I-495 Express Lane ramp terminals
2. Westpark Drive Connector at West Park Drive
3. Route 123 at Tysons Boulevard / Entrance to Tysons Mall Ring Road
4. Route 123 at Old Meadow Road / Capital One Tower Drive
5. Route 123 at Scotts Crossing Road / Colshire Drive
6. Route 123 at Anderson Road / Dulles Toll Road Connector ramp terminal
7. Route 123 at Great Falls Street / Lewinsville Road
8. Lewinsville Road at Balls Hill Road
9. Lewinsville Road at Swinks Mill Road
10. Lewinsville Road at Spring Hill Road
11. Spring Hill Road at Dulles Toll Road WB ramp terminals
12. Spring Hill Road at Dulles Toll Road EB ramp terminals
13. Spring Hill Road at International Drive / Jones Branch Drive

14. Jones Branch Drive at Jones Branch Connector
15. Jones Branch Connector at I-495 Express Lane ramp terminals
16. Old Dominion at Spring Hill Road
17. Old Dominion at Swinks Mill Road
18. Old Dominion at Balls Hill Road
19. Georgetown Pike at Dead Run Drive
20. Georgetown Pike at Balls Hill Road
21. Georgetown Pike at NB I-495 GP NB ramp terminals
22. Georgetown Pike at SB I-495 GP NB ramp terminals
23. Georgetown Pike at Linganore Drive / Helga Place
24. Georgetown Pike at Swinks Mill Road
25. Georgetown Pike at Spring Hill Road
26. Georgetown Pike at Douglass Drive
27. Route 123 at Ingleside Avenue
28. Route 123 at Old Dominion Drive

The following interchanges will have traffic counts conducted in the year 2018 and will be analyzed as part of the traffic operations analysis:

1. I-495 GP at Route 123
2. I-495 Express Lanes at Westpark Drive Connector
3. I-495 Express Lanes at Jones Branch Connector
4. I-495 GP at Dulles Toll Road and Dulles Airport Access Road
5. I-495 Express Lanes at Dulles Toll Road
6. I-495 at Georgetown Pike
7. I-495 at George Washington Memorial Parkway
8. I-495 at Clara Barton Parkway
9. Dulles International Airport Access Highway ramps to / from Dulles Toll Road (VA Route 267), east and west of I-495
10. Dulles Toll Road (VA Route 267) at Spring Hill Road (VA Route 684)
11. Dulles Toll Road (VA Route 267) at Dolley Madison Road (VA Route 123)
12. George Washington Memorial Parkway and Turkey Run Park

Traffic count locations are shown in Figure 1.

Traffic volumes used in the traffic and operations analysis will consist of the following:

- **Existing (2018)** – Developed from field counts (ramps, freeway mainline, and intersection turning movements) conducted in June 2018. Count data will be post-processed and balanced between all adjacent locations in the traffic operations analysis study area.
- **Opening Year (2025)** – No Build and one Build alternative developed through modifications to the MWCOG 2025 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.
- **Design Year (2045)** – No Build and one Build alternative developed through modifications to the MWCOG 2045 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.

Origin-Destination Data

The traffic simulation modeling effort will route vehicles through the traffic network according to origin-destination routing. Origin-destination data will be reviewed from the following sources:

- StreetLight Data, which via a VDOT subscription provides customized origin-destination data with a very high level of spatial accuracy based on aggregated cellular device GPS/location-based services data. StreetLight Data allows for a user to provide custom origins and destinations, such as on- and off-ramps for all freeways in a study area or entry/exit links to a study area. It is anticipated that StreetLight Data will be used as the basis for origin-destination routing for the existing conditions traffic analysis, at the very least for the freeway and ramp segments of the study area.
- MWCOC regional travel demand model, which outputs O-D matrices for various vehicle types between each traffic analysis zone (TAZ) in the Washington, DC, metropolitan area. The travel patterns within the model base year (2017) have been calibrated against 2007/2008 regional household travel survey data, so the travel patterns are somewhat dated. Additionally, this dataset is not as granular as needed to account for freeway weaving proportions. However, given that the travel demand model provides O-D matrices for future years, it is anticipated that these may be used as the basis for vehicle routing in future analysis year scenarios.

Speeds and Travel Times

Floating car travel time runs were conducted in June 2018 during the AM and PM peak periods for the following segments:

Corridor #	Corridor Name
1	I-495 Northbound – From south of Route 123 to River Road CD road;
3	I-495 Southbound – From River Road CD road to south of Route 123;
2	I-495 Northbound to DTR Westbound – From Route 123 to Spring Hill Road;
8	DTR Eastbound to I-495 Southbound – From west of Spring Hill Road to south of Route 123
4	I-495 Southbound to DTR Connector Eastbound from River Road CD road to east of Route 123
10	DTR Westbound Connector to I-495 Northbound – from east of Route 123 to River Road CD road.
5	I-495 Southbound to DTR Westbound – From River Road CD road to Spring Hill Road;
7	DTR Eastbound to I-495 Northbound – From west of Spring Hill Road to River Road CD road;
6	DTR Eastbound – From west of Spring Hill Road to east of Route 123;
9	DTR Westbound – From east of Route 123 to west of Spring Hill Road

In addition, INRIX vehicle probe speed data has been queried for the corridor using the RITIS Congestion Scan tool, which provides a “heat map” of vehicle speeds temporally and spatially along a corridor. This data has been pulled for “average weekdays” (Tuesday, Wednesday, and Thursday) for the 12 most recently available months of data (July 2017 through June 2018).

Queueing Data

Queueing along the freeway segments of the corridor will be provided via the INRIX heat map and verified against Google Maps’ typical traffic. Queueing along arterials and ramps will be obtained via screen captures from Google Maps’ typical traffic. Targeted spot locations will be verified in the field.

Traffic Operational Analysis Tools and Measures


Traffic Analysis Tools

VISSIM Version 9.0 will be used for a comprehensive network traffic analysis for the freeways, interchanges, and adjacent intersections within the traffic operations analysis area limits. (Reference analysis tool selection matrix, *VDOT Traffic Operations and Safety Analysis Manual [TOSAM] V1.0*¹, Appendix D.) Additional calibration, based on simulated volume processed, travel times, queues, and speed profiles, will be performed against 2018 measured field conditions and traffic data.

Surface street intersection operations will be evaluated through a combination of Synchro 10 (in order to develop preliminary optimization for phasing and signal timing) and VISSIM (for microsimulation and analysis). The expanded arterial network beyond intersections immediately adjacent to freeway interchanges in the corridor will be evaluated solely through Synchro. Transit routes and stops will be coded into the study area VISSIM network where they affect or could affect I-495 and related facility operations. The VISSIM and Synchro study areas are shown in Figure 2.

¹ <http://www.virginiadot.org/business/resources/TOSAM.pdf>

Figure 2. I-495 NEXT Traffic Operations VISSIM and Synchro Analysis Areas



Vehicle Classes

The following vehicle classes will be assumed for the traffic operations analysis VISSIM modeling:

- General purpose (non-toll-paying) cars
- HOV3+ cars
- HOT (toll paying) cars
- GP (non-toll-paying) trucks
- HOT (toll paying) trucks

Measures of Effectiveness

The following measures of effectiveness (MOEs) will be used for the operational analysis of the roadway network under existing and future Build and No-Build conditions.

Freeway Performance Measures

- Simulated Average Speed (mph)
- Simulated Average Density (pc/ln/mile, color-coded similar to the equivalent Density-Based LOS Thresholds)
- Simulated Volume (vehicles per hour)

The VISSIM freeway MOEs will be reported for each freeway segment. In addition, the following freeway MOEs also are proposed for reporting in the IJR:

- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).
- **Simulated Ramp Queue Length.** Reported for 50th and 95th percentiles (feet).
- **Simulated Travel Time.** Reported for select network origin-destination travel paths (seconds).
- **Congestion Heat Maps.** Incremental speeds reported for aggregated lanes, by time interval (mph).

Arterial/Intersection Performance Measures

- **Simulated Intersection Level of Service (LOS) and Average Control Delay.** Reported by approach and by intersection (sec/veh, color-coded in similar fashion as the equivalent Highway Capacity Manual (HCM) Delay-Based LOS Thresholds).
- **Simulated Intersection Approach Queue.** Reported by movement (feet).
- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).

Traffic Modeling Methodology and Assumptions

Calibration Methodology for Base Models

The VISSIM base models will be calibrated based on guidance from *VDOT Traffic Operations and Safety Analysis Manual (TOSAM)*, Version 1. A full review of the criteria and acceptance targets is provided in the attached **I-495 NEXT Traffic Analysis Microsimulation Calibration Methodology Memorandum**. This memorandum was approved and signed by the VDOT NoVA District Traffic

Engineer on July 27, 2018. The following criteria and thresholds are proposed for VISSIM model calibration:

Calibration Item	Basis	Criteria	Target
Simulated Traffic Volume (Intersections)	By Intersection Approach	Within $\pm 20\%$ for <100 vph	At least 85% of all Intersection Approaches
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Traffic Volume (Freeways)	By Freeway Segment	Within $\pm 20\%$ for <100 vph	At least 85% of all Freeway Segments
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Travel Time	By Route	Within $\pm 30\%$ for average travel times on arterials	At least 85% of all Travel Time Routes (Including Segments)
		Within $\pm 20\%$ for average travel times on freeways	
Maximum Simulated Queue Length	By Approach for Targeted Critical Locations	Modeled queues qualitatively reflect the impacts of observed queues	Qualitative Visual Match
Visual Review of Bottleneck Locations	Targeted Critical Locations	Speed heat maps qualitatively reflect patterns and duration of congestion	Qualitative Subjective Assessment

The following locations have been proposed for queue length calibration and reporting:

Queue Type	Location
Ramp	Ramp from SR 267 EB to I-495 NB GP
Ramp	Ramp from DAAR EB to I-495 NB GP
Ramp	Ramp from SR 267 EB to I-495 SB GP
Ramp	Ramp from SR 267 EB to Route 123 NB
Ramp	Ramp from Georgetown Pike (SR 193) to I-495 NB GP
Ramp	Ramp from George Washington Memorial Parkway NB to I-495 NB GP
Approach	Georgetown Pike (SR 193) EB approaching I-495 NB GP ramps
Approach	Georgetown Pike (SR 193) WB approaching I-495 NB GP ramps

Approach	Balls Hill Rd NB approaching Georgetown Pike
Approach	Spring Hill Rd NB approaching Lewinsville Road
Approach	Route 123 NB approaching Great Falls St
Approach	Lewinsville Road EB approaching Balls Hill Road

Potential Adjustments for Calibration

Adjustments to the VISSIM model during the calibration process will follow guidance from the VDOT TOSAM. These adjustments could include modifications to lane change distance for connectors, driver behavior along freeways and arterials, adjustments to desired speeds for vehicles at the network termini (such as along I-495 northbound leaving the study area), etc. The technical memorandum detailing calibration results will identify any potential deviations from TOSAM guidance.

Simulation Time, Seeding Time, and Number of Runs

The I-495 NEXT traffic operations study area is a severely oversaturated network during the weekday AM and PM peak periods, with several hours of congestion in both directions along I-495, especially along I-495 northbound approaching the American Legion Bridge. During these congested periods, traffic volume throughput is constrained due to low speeds and can be much lower than the actual maximum counted volumes along the freeway. Due to the oversaturated conditions, the analysis period was selected based on the heaviest periods of congestion and slowest speeds experienced along the corridor.

Figure 3 shows 15-minute average speeds along the I-495 northbound general purpose lanes through the study area for average weekdays (Tuesday, Wednesday, and Thursday) from July 2017 through June 2018. Note that during both the AM and PM peak periods, speeds along I-495 northbound are slower than speeds along I-495 southbound due to the downstream bottleneck at the American Legion Bridge. Thus, the analysis period and peak hours have been selected specifically based on congestion in the I-495 northbound general purpose lanes.

Figure 3 also show the proposed simulation analysis periods, which were also approved by the VDOT NoVA District Traffic Engineer as documented in the attached memorandum. These analysis periods would each be preceded by a 30-minute seeding period in the VISSIM models:

- AM peak: 6:45 AM to 9:45 AM (peak hour 7:45 AM to 8:45 AM). This will capture the onset of queueing back from the American Legion Bridge and the start of the dissipation of the queue. The peak hour captures the current worst extent of queueing.
- PM peak: 2:45 PM to 5:45 PM (peak hour 3:45 PM to 4:45 PM). This peak period is intended to capture queue formation from the American Legion Bridge *before the queue from points further north in Maryland spill back and create a single continuous queue*. This can be observed in the figure, as prior to approximately 3:30 PM, congestion in Virginia does not continue into Maryland. By approximately 4:00 PM, a single continuous area of congestion is present from north of the study area through the Route 123 interchange. Between approximately 4:00 PM and 7:00 PM, however, the extent of queueing stays relatively consistent – to the Route 123 interchange. The congestion does not fully dissipate until after 8:00 PM on average – note that the proposed traffic analysis period is not recommended to last until this point. Rather, the proposed traffic analysis period captures the onset of queueing (from when the queue is not due to spillback from Maryland) until it reaches its maximum.

Although the peak period in the afternoon and evening typically extends beyond six hours of congestion, the proposed analysis periods will still capture the onset of congestion and maximum extents of congestion, while allowing for the analysis to proceed in a streamlined manner within the scope and schedule of the project.

Conclusion

The VISSIM calibration criteria and simulation analysis peak hours and peak periods have been reviewed and approved by the VDOT NoVA District Traffic Engineer. The elements of the traffic analysis framework were presented to VDOT staff on July 20, 2018. The analysis tools and framework described in this document will be carried forward for the I-495 NEXT project.



MEMORANDUM

To: Ivan Horodyskyj, P.E., VDOT NoVA District Traffic Engineer
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E.
Raj Paradkar, P.E.
Anthony Gallo, P.E.
Kimley-Horn and Associates, Inc.

Date: July 24, 2018

Subject: I-495 NEXT Traffic Analysis Microsimulation Calibration Methodology

Introduction

This memorandum documents the proposed calibration methodology for the I-495 Northern Extension (NEXT) project traffic operations analysis in support of the project National Environmental Policy Act (NEPA) studies and Preliminary Engineering and Operations Development. The ATCS/Kimley-Horn consultant team (henceforth referred to as “consultant team”) has proposed a traffic microsimulation calibration methodology based on guidance set forth in the VDOT *Traffic Operations and Safety Analysis Manual (TOSAM)*¹, Version 1.0 (released November 2015). This manual, which is currently being updated to Version 2.0, contains direction related to calibration of VISSIM models that are considered mandatory conditions in which any deviations require approval from the Regional (now District) Traffic Engineer or his/her designee. The consultant team is requesting approval for deviations in calibration methodology for specific criteria (simulated average speeds and simulated queue lengths), given the volatile traffic flows and inconsistent queuing in the study area, as well as the direction from VDOT to streamline the project scale and schedule. The proposed alternative methodologies for calibration of these measures are documented below.


In conjunction with the VISSIM calibration, this memorandum also includes a discussion of the proposed simulation analysis period. The consultant team also requests approval for using these proposed periods in the VISSIM microsimulation analysis.

VISSIM Calibration Methodology

Existing conditions (2018) microsimulation networks will be developed using VISSIM 9.0 software. The VISSIM study area is shown in Figure 1.

¹ <http://www.virginia-dot.org/business/resources/TOSAM.pdf>

Figure 1. I-495 NEXT Traffic Operations Analysis Study Area



The VISSIM base models will be calibrated based on guidance from the *FHWA Traffic Analysis Toolbox Volume III* and the TOSAM. **Error! Not a valid bookmark self-reference.** shows the criteria and acceptance targets from the FHWA Toolbox that are recommended to be used in determining when calibration is achieved; Figure 3 shows the criteria and acceptance targets from the TOSAM.

Figure 2: FHWA Toolbox Calibration Criteria and Acceptance Targets

Criteria and Measures	Calibration Acceptance Targets
Hourly Flows, Model Versus Observed	
Individual Link Flows	
Within 15%, for 700 veh/h < Flow < 2700 veh/h	> 85% of cases
Within 100 veh/h, for Flow < 700 veh/h	> 85% of cases
Within 400 veh/h, for Flow > 2700 veh/h	> 85% of cases
Sum of All Link Flows	Within 5% of sum of all link counts
GEH Statistic < 5 for Individual Link Flows*	> 85% of cases
GEH Statistic for Sum of All Link Flows	GEH < 4 for sum of all link counts
Travel Times, Model Versus Observed	
Journey Times, Network	
Within 15% (or 1 min, if higher)	> 85% of cases
Visual Audits	
Individual Link Speeds	
Visually Acceptable Speed-Flow Relationship	To analyst's satisfaction
Bottlenecks	
Visually Acceptable Queuing	To analyst's satisfaction
*The GEH statistic is computed as follows:	
$GEH = \sqrt{\frac{(E - V)^2}{(E + V)/2}} \quad (4)$	
where:	
E = model estimated volume	
V = field count	

Figure 3: VDOT TOSAM Calibration Criteria and Acceptance Targets

Simulated Measure	Calibration Threshold	
<p>Simulated Traffic Volume (vehicles per hour) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds. The traffic volumes identified in the calibration thresholds are actual traffic volumes as opposed to simulated traffic volumes.</p>	<p>Within $\pm 20\%$ for <100 vph Within $\pm 15\%$ for ≥ 100 vph to <500 vph Within $\pm 10\%$ for ≥ 300 vph to $<1,000$ vph Within $\pm 5\%$ for $\geq 1,000$ vph</p>	
<p>Simulated Average Speed (miles per hour) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds.</p>	<p>Within ± 5 mph of average observed speeds on arterials Within ± 7 mph of average observed speeds on freeways</p>	
<p>Simulated Travel Time (seconds) Eight-five percent (85%) of the travel time routes, or a select number of critical routes, as determined by the RTE or his/her designee, shall meet the calibration thresholds. Travel time routes should be determined in cooperation with the VDOT project manager based on project needs and goals.</p>	<p>Within $\pm 30\%$ for average observed travel times on arterials Within $\pm 20\%$ for average observed travel times on freeways The travel time should be calibrated for segments and routes separately or as deemed appropriate by the VDOT project manager.</p>	
<p>Simulated Queue Length (feet) The top 85% of the network links, based on link traffic volume, or a select number of critical links and/or movements, as determined by the RTE or his/her designee, shall meet the calibration thresholds.</p>	<p>Undersaturated conditions (refer to Section 2.6 for guidance)</p>	<p><i>Average queue length on arterials:</i> Within $\pm 30\%$ for movements ≤ 10 vph Within $\pm 20\%$ for movements > 10 vph.</p>
		<p><i>Maximum queue length on arterials:</i> Within $\pm 25\%$</p>
	<p>Oversaturated conditions (refer to Section 2.6 for guidance)</p>	<p><i>Average queue length:</i> Within $\pm 20\%$ on arterials Within $\pm 30\%$ on freeways.</p>
		<p><i>Maximum queue length:</i> Within $\pm 20\%$ on arterials Within $\pm 35\%$ on freeways.</p>



The following criteria and thresholds are proposed for VISSIM model calibration:

Calibration Item	Basis	Criteria	Target
Simulated Traffic Volume (Intersections)	By Intersection Approach	Within ± 20% for <100 vph	At least 85% of all Intersection Approaches
		Within ± 15% for ≥ 100 vph to < 300 vph	
		Within ± 10% for ≥ 300 vph to < 1,000 vph	
		Within ± 5% for ≥ 1,000 vph	
Simulated Traffic Volume (Freeways)	By Freeway Segment	Within ± 20% for <100 vph	At least 85% of all Freeway Segments
		Within ± 15% for ≥ 100 vph to < 300 vph	
		Within ± 10% for ≥ 300 vph to < 1,000 vph	
		Within ± 5% for ≥ 1,000 vph	
Simulated Travel Time	By Route	Within ± 30% for average travel times on arterials	At least 85% of all Travel Time Routes (Including Segments)
		Within ± 20% for average travel times on freeways	
Maximum Simulated Queue Length	By Approach for Targeted Critical Locations	Modeled queues qualitatively reflect the impacts of observed queues	Qualitative Visual Match
Visual Review of Bottleneck Locations	Targeted Critical Locations	Speed heat maps qualitatively reflect patterns and duration of congestion	Qualitative Subjective Assessment

DEVIATIONS FROM TOSAM REQUIREMENTS

The following requirements from the TOSAM have been modified for the proposed VISSIM calibration process for this project:

- Simulated Average Speed – the TOSAM requires that the top 85 percent of network links (based on link traffic volumes) or a select number of critical links and/or movements, as determined by the DTE or his/her designee, meet a calibration threshold of average speeds within 5 mph for arterials and 7 mph for highways.
 - *Speeds are highly variable on the interstate mainline as well as on the local arterial network and residential roadways, and can vary substantially by hour and by day. The consultant team proposes that simulated average speed be captured as part of the travel time calibration process and the visual review of bottleneck locations against speed heat*



maps. Average speeds will still be extracted from the VISSIM models along the freeway corridors (I-495 general purpose, I-495 HOT, and SR 267) at one-half mile intervals and compared visually against speed heat maps generated from INRIX vehicle probe data.

- Simulated Queue Length – the TOSAM requires that the top 85 percent of network links (based on link traffic volumes), or a select number of critical links and/or movements, as determined by the DTE or his/her designee, meet calibration thresholds of measured queue lengths depending on whether conditions are oversaturated or undersaturated. These thresholds are detailed in Figure 3.
 - *Queuing within the study area is notably inconsistent and can oscillate numerous times within the peak periods, or be absent altogether on some days. The consultant team proposes that a qualitative subjective assessment be conducted for queue lengths at targeted locations in addition to the review of freeway mainline congestion/queues against the speed heat maps. Targeted locations will be determined in conjunction with the DTE for freeway ramps and arterials. Several proposed targeted locations are suggested in the following table:*

Queue Type	Location
Ramp	Ramp from SR 267 EB to I-495 NB GP
Ramp	Ramp from DAAR EB to I-495 NB GP
Ramp	Ramp from SR 267 EB to I-495 SB GP
Ramp	Ramp from SR 267 EB to Route 123 NB
Ramp	Ramp from Georgetown Pike (SR 193) to I-495 NB GP
Ramp	Ramp from George Washington Memorial Parkway NB to I-495 NB GP
Approach	Georgetown Pike (SR 193) EB approaching I-495 NB GP ramps
Approach	Georgetown Pike (SR 193) WB approaching I-495 NB GP ramps
Approach	Balls Hill Rd NB approaching Georgetown Pike
Approach	Spring Hill Rd NB approaching Lewinsville Road
Approach	Route 123 NB approaching Great Falls St
Approach	Lewinsville Road EB approaching Balls Hill Road

POTENTIAL ADJUSTMENTS FOR CALIBRATION

Adjustments to the VISSIM model during the calibration process will follow guidance from the VDOT TOSAM. These adjustments could include modifications to lane change distance for connectors, driver behavior along freeways and arterials, adjustments to desired speeds for vehicles at the network termini (such as along I-495 northbound leaving the study area), etc. The technical memorandum detailing calibration results will identify any potential deviations from TOSAM guidance.

Simulation Analysis Period

The I-495 NEXT traffic operations study area is a severely oversaturated network during the weekday AM and PM peak periods, with several hours of congestion in both directions along I-495, especially along I-495 northbound approaching the American Legion Bridge. During these congested periods,

traffic volume throughput is constrained due to low speeds and can be much lower than the actual maximum counted volumes along the freeway. Figure 4 shows an example of this phenomenon along the I-495 northbound general purpose lanes over three days in June 2018. During the PM peak period, starting around 2 PM, traffic counts decrease and do not get above 5,000 vph across a four-lane section, which theoretically should be able to carry much higher volumes. Due to the oversaturated conditions, the consultant team does not recommend using the maximum recorded values from traffic counts to represent peak conditions in the study area; rather, the consultant team recommends selecting an analysis period based on the heaviest periods of congestion and slowest speeds experienced along the corridor.

Figure 4. Hourly Traffic Counts along I-495 Northbound GP south of Route 267




Figure 5 shows 15-minute average speeds along the I-495 northbound general purpose lanes through the study area for average weekdays (Tuesday, Wednesday, and Thursday) from July 2017 through June 2018. Note that during both the AM and PM peak periods, speeds along I-495 northbound are slower than speeds along I-495 southbound due to the downstream bottleneck at the American Legion Bridge. The consultant team recommends selecting an analysis period based specifically on congestion in the I-495 northbound general purpose lanes.

Figure 5 also shows the consultant team’s proposed simulation analysis periods. These analysis periods would each be preceded by a 30-minute seeding period in the VISSIM models.



- AM peak: 6:45 AM to 9:45 AM (peak hour 7:45 AM to 8:45 AM). This will capture the onset of queueing back from the American Legion Bridge and the start of the dissipation of the queue. The peak hour captures the current worst extent of queueing.
- PM peak: 2:45 PM to 5:45 PM (peak hour 3:45 PM to 4:45 PM). This peak period is intended to capture queue formation from the American Legion Bridge *before the queue from points further north in Maryland spill back and create a single continuous queue*. This can be observed in the figure, as prior to approximately 3:30 PM, congestion in Virginia does not continue into Maryland. By approximately 4:00 PM, a single continuous area of congestion is present from north of the study area through the Route 123 interchange. Between approximately 4:00 PM and 7:00 PM, however, the extent of queueing stays relatively consistent – to the Route 123 interchange. The congestion does not fully dissipate until after 8:00 PM on average – note that the proposed traffic analysis period is not recommended to last until this point. Rather, the proposed traffic analysis period captures the onset of queueing (from when the queue is not due to spillback from Maryland) until it reaches its maximum.

While neither of the proposed analysis periods capture the entire period of congestion along the northbound direction of I-495, the consultant team does not recommend creating a microsimulation analysis for those full periods, based on VDOT's request to streamline the analysis and focus on the areas and times of greatest importance. For example, although the peak period in the afternoon / evening typically extends beyond six hours of congestion, the proposed analysis periods for study will still capture the onset of congestion and maximum extents of congestion, while allowing for the analysis to proceed in a streamlined manner within the scope and schedule of the project.



Conclusion

Recognizing the large scale of the I-495 NEXT traffic analysis efforts and constrained schedule, the consultant team requests that the District Traffic Engineer approve these proposed deviations in simulated speeds and simulated queue lengths from the VDOT TOSAM for the traffic microsimulation calibration. These deviations will not impact the ability of the microsimulation model to accurately represent typical real-world traffic conditions, and will instead focus the traffic analysis efforts on the most critical locations to the project.

Similarly, the consultant team requests that the District Traffic Engineer approve the proposed simulation analysis periods for the microsimulation model. These periods will capture the onset of congestion and maximum extents of congestion.

VDOT NoVA District Traffic Engineer Concurrence

Date

MEMORANDUM

To: Ivan Horodyskyj, P.E., VDOT NoVA District Traffic Engineer
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E., Kimley-Horn
Warren E. Hughes, P.E., ATCS, P.L.C.
Ram Jagannathan, ATCS, P.L.C.
ATCS, PLC

Date: August 27, 2018

Subject: I-495 NEXT Crash Analysis Framework

Introduction

This memorandum documents the details associated with the crash analysis framework for the I-495 Express Lanes Northern Extension Project. This memorandum is intended to supplement the information presented in the I-495 NEXT Project Scoping Framework Document.

The following elements of the crash and safety analysis are laid out in detail in this document:

- Data collection
- Existing crash analysis methodology, measures of effectiveness, and assumptions
- Development of Safety Performance Function (SPF) for Express Lanes
- Crash prediction methodology for freeway and ramp segments
- Crash prediction methodology for ramp junctions, at-grade intersections and arterial segments
- Qualitative safety analysis methodology

Data Collection

Five years of crash data (January 1, 2013 to December 31, 2017) will be used in this study. Available VDOT crash data will be collected for crashes reported on arterial segments, at-grade intersections, ramps and freeway segments within the study area that are in Virginia. Crash data will also be collected from the Maryland State Highway Administration (MDSHA) for those segments of roads in Maryland that are within the traffic operations study area. Due to the fact that National Park Service (NPS) Police report crashes on the George Washington Memorial Parkway (GWMP) and the Clara Barton Parkway using a different crash report form, crash data will also be collected from the National Park Service for segments of those parkways that are within the traffic operations study area.

In addition, the Consultant Team will make use of the VDOT's Tableau tool to extract data on reported crashes from VDOT's crash database. The Consultant Team will request copies of FR300 reports only for specific crashes to develop more detailed crash summaries and collision diagrams where appropriate. Since the study area includes roads that are under the responsibility of the National Park Service (i.e., George Washington Memorial Parkway and Clara Barton Parkway) and the Maryland State Highway

Administration, the Consultant Team will solicit data on reported crashes on their roads within the traffic operations study area. This will ensure that all reported crashes that occur in and near the GWMP / I-495 interchange and on the American Legion Bridge can properly be included in the analysis. We recognize that VDOT, MWAA, MDSA/MDOT and NPS may have different thresholds for crash reporting, specifically with respect to crash severity. We plan to use the crash severity determined by the agencies as-is while including the reporting criteria in the appendix of the document. All crash data will be provided by VDOT in GIS shapefile or geodatabase format. The Consultant Team will rely on the crash data directly from the VDOT RNS and will not review individual crash reports to verify the accuracy of that information.

To develop crash rates, data on vehicle exposure will be gathered from all available sources, including Average Daily Traffic (ADT) flows contained in the Virginia DOT annual traffic count books and data on historical ADT flows from the Maryland State Highway Administration. In addition, exposure data will be solicited from the operators of the I-495 Express Lanes for the last five years, since data is not reported by VDOT for these express lanes. Lastly, exposure data will be requested from the NPS for the parkway segments, including ramps and other roadway facilities maintained by the NPS that are within the traffic operations study area.

Existing Crash Analysis Methodology, Measures of Effectiveness, and Assumptions

The Consultant Team will analyze and summarize VDOT-provided crash data for I-495 and Dulles Toll Road mainline and ramps and intersecting (at an interchange) surface streets within the IJR study area. To the extent possible, the Consultant Team will develop a simplified crash “pin” map for the segments of the GWMP within the traffic operations study area. In addition, the Consultant Team will develop summaries and graphics of reported crashes on the segments of I-495 in Maryland to better understand crash patterns that may be affected by traffic conditions in Virginia.

The Consultant Team will summarize crash data in a tabular format for up to 10 elements such as weather conditions, lighting conditions, type of collision, and severity of crash. The Consultant Team will summarize data to identify crash patterns and high crash locations.

The Consultant Team will develop directional crash density “heat” maps to display the following crash patterns along the I-495 and Dulles Toll Road study corridors:

- Total number of crashes;
- Injury crashes;
- Lighting conditions;
- AM peak period conditions;
- PM peak period conditions;
- Rear-end crashes;
- Sideswipe same direction crashes; and
- Fixed-object off-road crashes.

The Consultant Team will develop mainline crash density histograms for I-495 from Route 123 to the American Legion Bridge, and along the Dulles Toll Road / Dulles Airport Access Road from Spring Hill Road to Route 123 (Dolley Madison Blvd), summarized in half-mile segments. The Consultant Team also will summarize the type of crashes for each half-mile segment within the study area.

The Consultant Team will identify high-crash locations along the corridor. The Consultant Team will use a 95th percentile confidence interval (average plus two standard deviations) for the corridor as a threshold for determining high crash locations. Sections with total crashes above the 95th percentile confidence interval will be considered a high-crash location. The Consultant Team will provide a summary of crashes at these locations in tabular format.

The Consultant Team will summarize crashes, in tabular format, for the latest five-year period and compare the following crash rates provided by VDOT Central Office:

- Crash, injury, and fatality crash rates for I-495 and Dulles Toll Road within the study area;
- Crash, injury, and fatality crash rates for I-495 and Dulles Toll Road statewide; and
- Statewide crash, injury, and fatality average crash rates for interstates.

Safety performance will be investigated to understand the nuances and impacts of weather, roadway lighting, traffic volumes, pavement condition, driver impairment and distraction, presence of work zone, work zone activity levels, etc. In this analysis, crash frequency, crash rate, crash severity and magnitude of crashes will be investigated to better understand past safety performance of I-495 Express Lanes in order to develop relationships (i.e., safety performance functions) for the analysis of future year traffic conditions under the Build and the No Build alternatives.

The implications with respect to existing and current safety issues and crash patterns from this safety analysis will be used to inform the roadway designers during the preliminary design phase of the project and during the development and screening of proposed interchange concepts phase of the project.

Development of Safety Performance Functions for Express Lanes

The Highway Safety Manual (HSM), first edition, does not have a prediction methodology for estimating the safety performance of urban interstates that also contain Express Lanes. For the I-495 Express Lanes Northern Extension study, the availability of safety performance functions would help predict the expected crash performance on Express Lanes after project completion. Hence, this study will use Interchange Safety Analysis Tool-Enhanced (ISATe) for analyzing the safety performance of the general purpose sections and interchanges. In addition, the study will build safety performance functions for this project using available crash data on I-495 Express Lanes (EL). The objective is to develop the relationships such that future year crash experience can be estimated for both existing express lane sections on I-495 and for new express lane sections that will be included in the Build alternative. Some inherent assumptions used in this study are listed below:

- The driver behavior and familiarity with the roadway are similar for current I-495 Express lanes and I-495 General Purpose lanes.
- The weather conditions on current I-495 EL and I-495 general purpose lanes are similar as they are geographically proximate.
- The traffic composition on current I-495 EL and I-495 NEXT are similar.

For the purpose of building the crash prediction model for the express lanes, the following interchange pairs / segments on I-495 used in the study are listed below:

- South End – Braddock Road
- Braddock Rd - Route 236

- Route 236 – Gallows Road
- Gallows Road - Route 50
- Route 50 - Lee Hwy
- Lee Hwy - I-66
- I-66 - Route 7
- Route 7 - Route 123
- Route 123 – VA 267
- VA 267 – North End

Crash Prediction Methodology for Freeway and Ramp Segments and Assumptions

The Consultant Team will conduct a safety and crash analysis consistent with VDOT's IIM-LD-200.9. The Consultant Team's analysis will involve qualitative and quantitative measures to evaluate proposed alternatives and demonstrate the effects of interstate access modifications on safety of I-495 and the local surface street system. The Consultant Team will use ISATe to evaluate the quantitative effect of interstate access modifications on safety on I-495 general purpose lanes and HSM methodologies to evaluate the safety impacts of the proposed interchange concepts on the arterial system adjacent to the interchanges. Assumptions for the safety analysis are given below:

- Safety analyses will be performed for interstate mainline segments, ramp termini, and adjacent crossroads segments and crossroad intersections within the IJR study area, limited to the area for traffic data collection;
- FHWA's Enhanced Interchange Safety Analysis Tool (ISATe) will be used to evaluate freeway and interchange safety, based on FHWA/AASHTO regulations and guidance;
- The Highway Safety Manual (HSM) and NCHRP 17-38 spreadsheets (VA editions) will be used to analyze five-year continuous crash history for the crossroad segments. ISATe will be used to analyze the crossroad ramp terminal intersections within these segments;
- Freeway analysis will focus on the I-495 Mainline Facility. To the extent possible within the available reported crash data for express lanes in Virginia, the Consultant team will develop a safety performance function for express lane sections. Currently available analysis tools do not provide for crash prediction and safety performance evaluation of managed lane facilities (express lanes). If the review agencies deem that the methodology and results are applicable, then the safety results for the express lanes will be included in the analysis.;
- Qualitative assessments will be performed for conditions where the quantitative analysis is not appropriate.;
- Quantitative analysis will be performed within the limits of the available safety analysis tools. However, it should be noted that some geometric conditions are not able to be modeled using these tools. In these situations, qualitative analysis will be incorporated into the evaluation to supplement any gaps in the quantitative analysis; and
- Using ISATe, the safety performance of the I-495 NEXT interchanges will be predicted for future traffic volumes.

The EL SPF-based crash predictions will be added as a layer on top of the ISATe crash predictions for the GP Lanes and Ramps to compare the safety performance of the Build and No-Build conditions for future years.

Crash Prediction Methodology for Ramp Junctions, At-Grade Intersections and Arterial Segments and Assumptions

For VA Route 193, we will use the HSM to predict crashes on the arterial segments and intersections. Intersection boundaries will encompass 500 feet of roadway on all intersecting approaches. We plan to analyze the interchange ramp terminals and all signalized intersections within a radius of 0.5 mile from the interchange ramp terminals on VA Route 193. We will use the calibration factors for VA and check to see if the crash predictions are reasonable. If needed, we will refine the calibration factors for the SPFs in the HSM using additional VA data. The limit of the crash prediction will be for multiple-vehicle crashes only. Given the limited amount of data, we will not be able to predict additional single-vehicle, vehicle-bicycle, and vehicle-pedestrian crashes.

Qualitative Safety Analysis Methodology and Assumptions

Finally, a driver Info Overload analysis will be conducted. For every 1/10th of a mile, the number of signs needed to be processed by the driver will be documented and the burdensome nature of the same will be qualitatively ranked on a five-point scale (low-effort to extreme-effort). Based on the results of the qualitative analysis, the development of the IJR Guide Sign Plan will be guided to identify concerns with respect to signing deficiencies.

MEMORANDUM

To: Susan Shaw – VDOT MegaProjects Director

From: Kimley-Horn and Associates

Rob Prunty, P.E.

Adrienne Ameel, P.E.

Cc: Abraham Lerner – Associate Manager of Special Project Development

Date: October 31, 2018

Subject: I-495 Project Next – Environmental Traffic Data (ENTRADA) and Air Quality Impact Analysis Traffic Data

ENVIRONMENTAL TRAFFIC DATA (ENTRADA)

Traffic data sets will be prepared for the NEPA-level Noise Impacts analysis. Project level Noise locations will be identified using FHWA and EPA protocol and/or guidance documentation consistent with VDOT's practice. The traffic analysis data required for ENTRADA will include existing (2018) year, and build and no-build scenarios for the design (2045) year. The ENTRADA study area limits were determined based on a meeting with VDOT on August 29, 2018. The ENTRADA study area map is shown in **Figure 1**.

The ENTRADA study area includes the following:

- Mainline roadways;
- Cross streets associated with existing interchanges;
- Intersections/Interchanges; and
- Parallel facilities with an AADT greater than 3,000 within the project corridor (as defined by the second signalized public road intersection on either side of I-495, excluding I-495 ramp termini).

ENTRADA Version 2018-09 from VDOT will be utilized, in combination a macro-driven master database that links the various files for all the segments. Synchro 9 will be utilized for intersection analysis reporting for the NEPA team.

The traffic data for the Noise analysis will be developed using the regional travel demand modeling (TDM) output files encompassing the I-495 study corridor and affected transportation network for the base year and the build and no-build scenario for the design year 2045. The travel demand forecasts will be post processed and developed using NCHRP Report 765 and NCHRP Report 255 guidelines. Each link within the TDM output files will contain a link identifier, link length (miles), AADT, number of lanes, HPMS area type, HPMS functional classification, free-flow speed, and hourly lane capacity (vehicles/hour/lane). The following post-processed environmental traffic volume data will be provided:

- Average annual daily traffic (AADT), levels of service, average annual truck traffic (AATT), and capacity-constrained peak-period volumes as well as operating, posted and congested speeds for each link in the project area;
- Percent trucks with two axles and six tires, the percent trucks with three or more axles, and directional distributions;
- For the mainline, intersections/interchanges and parallel facilities, directional volumes, including turning or ramp movements (vehicles/hr/link);
- Lane configuration diagrams for each mainline roadway and intersection/interchange within the project corridor showing through and turn lanes; and
- Signal timings (cycle lengths and phasing, approach splits), as well as Level of Service based on control delay (includes intersection and approach delays).

The data will be compiled using VDOT's ENTRADA spreadsheets (2018-09) and Synchro files. Both Excel and pdf files of the spreadsheets will be produced.

The following inputs will be set up on a master project database and imported into each specific segment file for the creation of the ENTRADA files:

- Segment Length (miles) - The segment length will be the length of the segment in the 2045 design year;
- Area Type - Will be verified by field observations and confirmed with VDOT;
- Directional Percent Hourly Truck Traffic - Sourced from the MWCOG Model and be consistent with the peak period characteristics being modeled in VISSIM. They will be verified with the available existing traffic data; and
- Existing Hourly Speeds by Direction - Will be verified by existing traffic data and consistent with the peak period characteristics being modeled in VISSIM.

The following physical characteristics will be collected and entered as input (by individual segment) for 2045 build/no-build scenario for the creation of the ENTRADA files. Based on discussions with VDOT, it was determined that 2025 build/no-build scenarios were not necessary for the ENTRADA files. The existing physical conditions would be assumed unless changes are being made in future scenarios.

- Cross Section;
- Number of Lanes;
- Outside Shoulder Width (ft);
- Inside Shoulder Width (ft);
- Lane Width;
- Terrain - The terrain will be consistent with GIS topo and verified with field observations;
- Interchange/Access Density (per mile);
- Posted Speed; and
- Number of Signals (in length of facility).

The following characteristics for signalized facilities will be collected and entered as input (by individual segment) for the existing scenario for the creation of ENTRADA files, and developed for the build/no-build scenarios. Any adjustments and post-processing of volumes made for the peak period characteristics, as used for the detailed traffic operational analysis (for the TATTR and IJR), will be consistently applied for those values in ENTRADA:


- Signal Cycle length;
- Signal Green Time; and
- Segment Delay Adjustment Factor.

The following characteristics for each scenario will be developed for the creation of the ENTRADA files and will be sourced from the MWCOG Model. Any adjustments and post-processing of volumes made for the peak period characteristics, as used for the detailed traffic operational analysis (for the TATTR and IJR), will be consistently applied for those values in ENTRADA:

- Capacity (pcphpl);
- Facility Type;
- ADT - Will be verified with existing traffic data;
- % trucks of the ADT - Will be derived from existing traffic classification count data;
- K-factors for each hour - Will be derived from existing traffic data as a basis and adjusted for future conditions based on factors used for the MWCOG Model; and
- Directional Split (D-factor) for each hour - Will be verified with existing traffic data and derived MWCOG Model outputs for future conditions.

The ENTRADA study area map is shown in **Figure 1**. The study area network extends beyond the 500-foot offset from the project footprint in order to include complete segmentation elements that are located partially within the 500-foot offset area.

Figure 1 – ENTRADA Study Area



AIR QUALITY

MSAT Analysis

Using the regional TDM output files to prepare a quantitative mobile source air toxics (MSAT) analysis for the I-495 study corridor for the existing (2018), opening year (2025, no-build and build), and design year (2045, no-build and build). For purposes of the MSAT analysis, the affected transportation network could include roadways located several miles away from the project corridor, based on the results of the quantitative comparison between the no-build and the build scenarios for increases in traffic forecast volumes (VDOT typically uses +/- 5% per FHWA guidance) on major roadway links within the Northern Virginia region (as determined by model runs using the MWCOC Model).

The following deliverables will be produced:

- ENTRADA information sets for VDOT NEPA team for existing conditions (2018) (five electronic copies in Excel format linked to a macro-driven master database file);
- Synchro files for all intersections identified within the NEPA traffic analysis study area (five electronic copies);
- Lane diagrams for the Existing scenario (five electronic copies);
- Traffic information listed above, compiled into tabular form in a consolidated NEPA Traffic Input Data Report (five electronic copies); and
- MSAT analysis inputs for VDOT NEPA team (five electronic copies).

**Appendix C: I-495 NEXT Travel Demand Forecasting
Framework Memorandum**

MEMORANDUM

To: Rahul Trivedi, P.E., VDOT NoVA District Transportation Planning Manager
Amir Shahpar, P.E., VDOT NoVA District Modeling Manager
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E.
Raj Paradkar, P.E.
Anthony Gallo, P.E.
Sarah Knox, P.E.
Kimley-Horn and Associates, Inc.

Date: August 26, 2018

Subject: I-495 NEXT Travel Demand Forecasting Framework

Introduction

This memorandum documents the travel demand forecasting framework associated with the I-495 NEXT Project. This memorandum is intended to supplement the overarching I-495 NEXT Project Scoping Framework Document.

The following elements of the traffic operations analysis are laid out in detail in this document:

- Travel demand modeling assumptions and calibration/validation
- Traffic volume post-processing for use in traffic operations and air/noise analysis

Travel Demand Modeling Methodology

Existing Conditions Model Calibration and Validation

The latest MWCOG travel demand model version on the 3,722 traffic analysis zone (TAZ) system will be used in conjunction with Round 9.1 Cooperative Forecasts (socioeconomic data) for the Existing, Opening, and Design model years. The MWCOG model base year is 2017; a project Existing Conditions (year 2018) model will be prepared, modified and calibrated to reflect field counts. Modifications will be carried forward into future analysis year model scenarios.

The MWCOG model will be strategically modified with specific alterations to improve the accuracy and reliability of forecasts for the I-495 study corridor, roadways connected to the corridor, and transit services in the vicinity of the corridor. The calibration targets will be based on guidance from the FHWA Transportation Model Improvement Program (TMIP) *Travel Model Validation and Reasonableness Checking Manual* and the Virginia *Travel Demand Modeling Policies and Procedures Manual*. Because the MWCOG/TPB Model is already subject to scrutiny as a regional model which has been a subject of FHWA's TMIP Peer Review process, the validation process for

the I-495 Project NEXT model will focus on the I-495 Traffic Operations Analysis Study Area and will include the following comparisons:

- Regional comparisons to VDOT AADTs at the daily level (daily level only)
 - Percent difference in total volume for cutlines
- I-495 NEXT study area comparisons to field traffic counts (AM/PM periods and daily)
 - R-squared between modeled volumes and counts on links
 - Percent difference in total volumes for freeways/arterials
 - Percent root mean squared error (%RMSE) by volume group or facility type
- Travel time comparisons of model outputs to floating car runs data collected (AM/PM periods only; reasonableness checks only)

Table 1 provides a listing of travel demand model calibration criteria, which were discussed and verbally approved by VDOT during a call on July 24, 2018.

Table 1. Travel Demand Forecast Model Calibration Criteria


Calibration Scale	Calibration Check	Calibration Threshold			
Regional	% Difference in Total Volume for Cutlines (24-Hour Volumes)	Cutline Volume	VTM	FHWA	Proposed
		50,000	10%	35%	10%
		100,000	8.75%	25%	10%
		150,000	7.50%	20%	10%
		200,000	6.25%	18%	8%
		250,000	5%	15%	7%
Study Area	R-Squared between modeled volume and counts on links (AM Period, PM Period, and 24-Hour Volumes)	VTM	FHWA	Proposed	
		0.9	0.88	0.9	
	% Difference in Total Volume by Facility Type (AM Period, PM Period, and 24-Hour Volumes)	Facility Type	VTM	FHWA	Proposed
		Freeways	6%	7%	6%
		Major Arterials	7%	10%	10%
		Minor Arterials	10%	15%	15%
	%RMSE by Facility Type (AM and PM Period)	Facility Type	VTM	FHWA	Proposed
		Freeways	30%	-	30%
		Major Arterials	45%	-	45%
		Minor Arterials	60%	-	60%
		Overall	40%	-	40%
	%RMSE by Facility Type (24-Hour Volumes)	Facility Type	VTM	FHWA	Proposed
		Freeways	20%	-	20%
		Major Arterials	35%	-	35%
		Minor Arterials	50%	-	50%
	Overall	30%	-	30%	
Travel Times (AM and PM Period)	No specific measures in VTM or FHWA; compare model outputs to floating car travel runs and check to see if travel times are within min and max of observed travel times. <u>Note that these are reasonableness checks only.</u>				

The following regional cut-lines will be used in the calibration process:

- East/west travel west of study area
 - Georgetown Pike west of Spring Hill Road
 - Old Dominion Drive west of Spring Hill Road
 - Lewinsville Road west of Spring Hill Road
 - Route 267 between Route 7 and Spring Hill Road
 - Route 7 just east of Route 267
- East/west travel east of study area
 - George Washington Memorial Parkway east of I-495
 - Georgetown Pike east of I-495
 - Old Dominion Drive between Balls Hill Road and Route 123
 - Route 123 east of Lewinsville Road/Great Falls Street
 - Chain Bridge Road east of Great Falls Street
 - Great Falls Street east/south of Chain Bridge Road
 - Route 267 east of Route 123
- North/south travel north of study area
 - I-495 American Legion Bridge
- North/south travel within study area
 - Spring Hill Road south of Georgetown Pike
 - Swinks Mill Road south of Georgetown Pike
 - I-495 south of Georgetown Pike
 - Balls Hill Road south of Georgetown Pike
 - Douglas Drive south of Georgetown Pike
 - Route 123 west/south of Georgetown Pike

Figure 1 shows a map of the proposed cut-lines for the calibration process.

Figure 1. Proposed Cut-Lines for Travel Demand Model Calibration Process.



Toll Diversion Curves from OP3’s consultant, based on existing express lane usage on the Capital Beltway Express Lanes, will also be validated in order to increase confidence in the model and maintain relative consistency between traffic and revenue studies for I-495 in Virginia, and regional planning studies of MDOT’s proposed managed lanes system in Maryland.

Travel demand forecasting activity will be coordinated between the traffic and revenue study, and IJR/NEPA effort in order to maintain consistency in forecasting among these efforts to the maximum extent practical. Alterations to the MWCOG travel demand model to improve corridor calibration may include:

- Highway network modifications to better represent study area facilities as they exist and are planned, such as modifications to link facility types. Ramps will be micro-coded to improve forecasts and correlation to the microsimulation process.
- Traffic Analysis Zone (TAZ) splits and centroid connector location changes to improve model loading for all modeled modes of transportation.
- Changes to external trip assumptions to improve consistency with origin-destination data and traffic and revenue evaluations.
- Use of toll diversion methodology to forecast Express Lane trips.

- Changes in the time-of-day distribution to improve forecasting of peak period trips, changes in the Volume Delay Function (VDF) curves, and changes in the default speed and capacity of some facility types.

Future Analysis Scenario Assumptions

The I-495 NEXT traffic analysis will assess operations for a project Design Year of 2045 and Interim Year of 2025. The traffic analysis will account for a No-Build scenario and one Build alternative. Separate travel demand model networks will be developed for each of the future-year scenarios to be used for forecasting traffic volumes.

The travel demand model No-Build networks will include all roadway projects in the most up-to-date regional CLRP. In addition, the No-Build networks will account for the following elements:

- **I-495/Dulles Toll Road Interchange Ramps** – currently unbuilt ramps at the I-495/Dulles Toll Road, including ramps to and from the I-495 Express Lanes and Dulles Airport Access Road, for which preliminary engineering has completed and construction is anticipated prior to the I-495 NEXT project being in place.
- **Auxiliary lanes along I-495** – general-purpose auxiliary lanes to be added along I-495 between the Dulles Toll Road interchange and the Georgetown Pike interchange
- **Express Lanes in Maryland** – the I-495 NEXT team will be coordinating closely with the Maryland Department of Transportation (MDOT) on plans for a network of express lanes in Maryland, including lanes along I-495 and I-270. These plans are currently ongoing, but the I-495 NEXT No-Build and Build networks will contain the same assumptions for the Express Lanes in Maryland:
 - Locations of access and network structure
 - Vehicle types allowed in express lanes, including those which must pay a toll and those which are exempt (if any) – could include HOV2/HOV3+ or trucks

Summary of Travel Demand Modeling Assumptions

Table 1 lists key assumptions associated with the travel forecasting process.

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments												
<i>Model</i>														
Analysis Years 2018 (Existing) 2025 (Interim Year) 2045 (Design Year)	<u>MWCOG Model</u> 2018 (Validation Year) 2025 2045	MWCOG travel demand model has model inputs at 5-year increments plus a year 2017 input dataset. Intermediate years can be developed by interpolating input data and modifying networks to represent planned conditions.												
Time Periods	Four time periods are modeled in the forecasts. The sum of the four time periods represents average weekday daily traffic: <table border="1" style="margin-left: 20px;"> <thead> <tr> <th>Period</th> <th>Hours</th> </tr> </thead> <tbody> <tr> <td>AM</td> <td>6 a.m. – 9 a.m.</td> </tr> <tr> <td>Midday</td> <td>9 a.m. – 3 p.m.</td> </tr> <tr> <td>PM</td> <td>3 p.m. – 7 p.m.</td> </tr> <tr> <td>Night</td> <td>7 p.m. – 6 a.m.</td> </tr> </tbody> </table>	Period	Hours	AM	6 a.m. – 9 a.m.	Midday	9 a.m. – 3 p.m.	PM	3 p.m. – 7 p.m.	Night	7 p.m. – 6 a.m.	Hours split based on MWCOG household survey data (2007/2008).		
Period	Hours													
AM	6 a.m. – 9 a.m.													
Midday	9 a.m. – 3 p.m.													
PM	3 p.m. – 7 p.m.													
Night	7 p.m. – 6 a.m.													
Speed	Consistent with current conditions in the HOV and general purpose (GP) lanes.	Consistent with existing conditions. Same as speed/travel time curves based on MWCOG unless validation suggests modification.												
Link Capacity	Lane capacities are defined consistent with the MWCOG model approach.	The MWCOG facility and area type capacity tables are used to determine link capacities. Use same speed-flow curves consistent with TPB model unless validation suggests modification.												
Peak Factors	Peak period to peak hour factors: <table border="1" style="margin-left: 20px;"> <thead> <tr> <th>Period</th> <th>2010</th> <th>2025</th> <th>2040</th> </tr> </thead> <tbody> <tr> <td>AM</td> <td>0.417</td> <td>0.38</td> <td>0.34</td> </tr> <tr> <td>PM</td> <td>0.294</td> <td>0.272</td> <td>0.25</td> </tr> </tbody> </table>	Period	2010	2025	2040	AM	0.417	0.38	0.34	PM	0.294	0.272	0.25	Existing peak period values were derived from the 2007/2008 MWCOG Household Travel Survey. The peak hour factors decline in future years in recognition of the increased congestion expected in the region causing less peaked periods. This assumption spreads the traffic evenly over the entire peak period.
Period	2010	2025	2040											
AM	0.417	0.38	0.34											
PM	0.294	0.272	0.25											
Socioeconomic Data	MWCOG Round 9.1 socioeconomic data will be used.													

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments
<i>Network</i>		
Project Description (I-495 Northern Extension)	Two Express Lanes in each direction along I-495 between the Dulles Toll Road (Route 267) and George Washington Memorial Parkway. Specifics to be addressed in the preliminary design effort.	
Project Extent	Dulles Toll Road in Tysons to GWMP near Maryland State Line	
I-495 (Capital Beltway) Express Lanes	Existing: Express Lanes on I-495 between I-95/I-395 and Dulles Toll Road Future: Existing Express Lanes on I-495 plus new Express Lanes in Maryland along I-495 and I-270.	Access, tolling parameters, and vehicle restrictions for I-495 Express Lanes in Maryland to be determined in coordination with MDOT.
HOV	Beginning in 2020, all HOV facilities in the Northern Virginia area are assumed to become HOV-3+.	I-495 and I-95 Express Lanes are free to HOV-3 vehicles currently; HOV lanes along I-66 and Dulles Toll Road are HOV-2 currently. HOV restrictions in Maryland to be determined in coordination with MDOT. See Table 3 for further explanation.
<i>Toll Assumptions</i>		
Tolling Methodology	Tolling assumptions will be kept consistent with MWCOG's default factors for I-495, I-95/395, and I-66 HOT Lanes in the final assignment iteration.	
Toll Approach	Variable toll rates by roadway segment, based on maintaining Express Lane speed goal of 55 mph.	Adopted to account for varying demand levels along the length of the project.
<i>Mode Assumptions in I-495 NEXT Express Lanes</i>		

Table 2: Travel Demand Forecasting Model Assumptions

Model Parameter	Assumption	Comments
Vehicle Class	HOV-3+: Free Other cars and medium trucks: Toll Heavy trucks: Are permitted in the I-495 Express Lanes from the Dulles Toll Road to the project terminus north of the GWMP.	Vehicle class restrictions for I-495 Express Lanes in Maryland to be determined in coordination with MDOT
HOV Vehicles	Use the MWCOG model HOV module. Beginning in 2020, all HOV facilities in Northern Virginia area will be HOV-3+.	The HOV estimates provided are an output of the <i>mode choice</i> and <i>carpool occupancy</i> models developed by MWCOG.

Table 3. HOV and Tolling Assumptions for Facilities in Study Area

Facility	2018	2025	2045
I-495 (Existing Express Lanes Network)	All vehicles except trucks permitted in barrier-separated express lanes. All vehicles except HOV3+ must pay a toll.		
Dulles Toll Road (SR 267)	HOV2+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	HOV3+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	
I-66 (Outside the Beltway)	HOV2+ vehicles only allowed in left-most lane eastbound (AM peak) and westbound (PM peak)	All vehicles (including trucks) permitted in barrier-separated express lanes. All vehicles except HOV3+ must pay a toll.	
I-66 (Inside the Beltway)	All vehicles except trucks permitted. During AM peak eastbound and PM peak westbound, lanes are tolled except for HOV2+ vehicles.	All vehicles except trucks permitted. During AM peak eastbound and PM peak westbound, lanes are tolled except for HOV3+ vehicles.	All vehicles except trucks permitted. During AM peak and PM peak in both directions, lanes are tolled except for HOV3+ vehicles.

Traffic Volume Post-Processing

Post-processing of travel demand model output is necessary to develop traffic volume forecasts for analysis of operations during peak periods/peak hours. Post-processing of travel demand forecasts for vehicular volumes will follow NCHRP 255/765 guidelines for estimating balanced No-Build and Build peak period volumes. Existing balanced volumes will be developed outside of the MWCOG

travel demand model using field count data; origin-destination (O-D) routing will be obtained utilizing StreetLight Data or the MWCOG model, and the O-D matrix will be adjusted using VISUM's TFlowFuzzy methodology to match target balanced volumes along the corridor. The O-D matrix will be imported into VISSIM for traffic microsimulation analysis.

Traffic volumes for the traffic operations analysis and air quality and noise analyses for future scenarios will be developed using travel demand model outputs and NCHRP 255/765 guidelines. For future scenario VISSIM microsimulation analysis, O-D routing will again be developed using MWCOG model outputs as a seeding matrix and VISUM's TFlowFuzzy process to create an adjusted O-D matrix that matches target forecast volumes in the study area.

Conclusion

The travel demand model methodology and calibration/validation criteria were reviewed with VDOT staff on a call on July 24, 2018. This methodology will be carried forward for travel demand forecasting for the I-495 NEXT project.

**Appendix D: Results of 2025 and 2045 Intersection Operations
Analysis**

2025 No-Build AM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	1,996	25.5	C	32.6	C
		SB	3,975	29.3	C		
		EB	611	66.8	E		
		WB	427	47.4	D		
4	Westpark Drive and Tysons Connector	NB	634	20.5	C	21.4	C
		SB	343	12.2	B		
		WB	908	25.5	C		
5	Tysons Connector and Express Lanes Ramps	NB	638	17.4	B	13.9	B
		SB	281	12.6	B		
		EB	315	8.0	A		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	3,110	86.5	F	77.9	E
		SB	2,116	43.4	D		
		EB	100	556.7	F		
		WB	677	75.4	E		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,427	55.1	E	74.6	E
		SB	2,421	98.7	F		
		EB	391	51.8	D		
		WB	311	67.7	E		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	1,822	46.8	D	106.8	F
		SB	1,964	150.6	F		
		EB	728	99.0	F		
		WB	375	185.1	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,410	88.2	F	136.3	F
		SB	1,529	115.9	F		
		EB	828	53.3	D		
		WB	718	437.1	F		
2	Lewinsville Road and Balls Hill Road	SB	221	138.9	F	22.5	C
		EB	732	18.4	B		
		WB	1,228	4.0	A		
9	Jones Branch Drive and Jones Branch Connector	NB	751	19.2	B	17.6	B
		SB	771	12.9	B		
		WB	908	20.2	C		
10	Jones Branch Connector and Express Lanes Ramps	NB	326	35.8	D	64.7	E
		SB	366	28.1	C		
		EB	829	20.1	C		
		WB	258	35.7	D		
29	Jones Branch Drive and Capital One (West)	SB	207	34.5	C	17.0	B
		EB	931	12.9	B		
		WB	544	8.6	A		
		NB	63	15.0	B		
30	Jones Branch Drive and Capital One (East)	SB	114	14.6	B	5.4	A
		EB	539	3.3	A		
		WB	701	4.7	A		
		NB	444	55.3	E		
11	International Drive and Spring Hill Road/ Jones Branch Drive	SB	1,842	39.9	D	48.3	D
		EB	656	57.9	E		
		WB	375	64.4	E		
		NB	552	23.1	C		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	SB	1,013	48.0	D	159.8	F
		EB	1,081	334.5	F		
		NB	558	16.2	B		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	SB	704	21.3	C	31.9	C
		WB	477	65.7	E		
		NB	501	65.2	E		
14	Spring Hill Road and Lewinsville Road	SB	310	82.1	F	54.1	D
		EB	605	55.2	E		
		WB	651	31.2	C		
		NB	23	6.2	A		
23	Georgetown Pike and Helga Place/ Linganore Drive	SB	8	139.6	F	139.6	F
		EB	1,231	84.7	F		
		WB	670	0.6	A		
		SB	683	23.7	C		
20	Georgetown Pike and I-495 Southbound Ramps	EB	1,273	27.9	C	25.4	C
		WB	535	21.7	C		
		NB	445	43.0	D		
19	Georgetown Pike and I-495 Northbound Ramps	EB	1,408	12.9	B	20.5	C
		WB	841	21.4	C		
		NB	408	47.4	D		
18	Georgetown Pike and Balls Hill Road	SB	84	35.4	D	21.1	C
		EB	892	12.5	B		
		WB	549	13.4	B		
22	Georgetown Pike and Dead Run Drive	NB	104	9.2	A	9.6	A
		EB	636	1.0	A		
		WB	521	0.8	A		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	135	14.7	B	10.9	B
		SB	180	15.2	B		
		EB	870	10.4	B		
		WB	260	7.3	A		
16	Old Dominion Drive at Swinks Mill Road	NB	295	25.3	C	16.2	B
		SB	200	22.8	C		
		EB	785	13.6	B		
		WB	210	6.6	A		
17	Old Dominion Drive at Balls Hill Road	NB	315	120.6	F	101.5	F
		SB	330	115.7	F		
		EB	555	84.6	F		
		WB	255	96.3	F		
21	Route 123 at Old Dominion Drive	NB	1,915	27.7	C	43.7	D
		SB	1,165	24.4	C		
		EB	675	84.2	F		
		WB	690	87.4	F		
24	Georgetown Pike at Swinks Mill Road	NB	640	221.4	F	73.7	F
		SB	0	0.0	A		
		EB	650	0.0	A		
		WB	655	2.2	A		
25	Georgetown Pike at Spring Hill Road	NB	45	18.0	C	1.2	A
		EB	660	0.0	A		
		WB	510	0.7	A		
26	Lewinsville Road at Swinks Mill Road	SB	205	46.7	E	8.9	A
		EB	885	2.7	A		
		WB	555	0.0	A		
27	Route 123 at Ingleside Avenue	NB	1,860	0.4	A	1.0	A
		SB	1,135	0.8	A		
		EB	85	14.0	B		
		WB	45	20.2	C		
28	Douglass Drive at Route 193 (Georgetown Pike)	NB	260	153.7	F	26.4	D
		SB	50	48.5	E		
		EB	595	0.4	A		
		WB	610	1.9	A		

2025 Build AM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	1,992	25.6	C	33.3	C
		SB	4,064	30.7	C		
		EB	612	66.5	E		
		WB	428	46.8	D		
4	Westpark Drive and Tysons Connector	NB	649	19.9	B	22.7	C
		SB	347	11.7	B		
		WB	911	28.9	C		
5	Tysons Connector and Express Lanes Ramps	NB	605	17.8	B	14.1	B
		SB	315	12.4	B		
		EB	329	8.8	A		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	3,188	100.4	F	83.0	F
		SB	2,132	38.6	D		
		EB	98	548.2	F		
		WB	679	74.0	E		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,471	59.2	E	78.4	E
		SB	2,428	100.4	F		
		EB	406	70.9	E		
		WB	317	68.5	E		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	1,842	46.5	D	86.8	F
		SB	1,974	119.3	F		
		EB	725	51.3	D		
		WB	369	183.3	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,361	77.0	E	155.0	F
		SB	1,492	180.8	F		
		EB	837	51.9	D		
		WB	720	477.0	F		
2	Lewinsville Road and Balls Hill Road	SB	221	145.2	F	22.0	C
		EB	737	16.3	B		
		WB	1,220	3.1	A		
9	Jones Branch Drive and Jones Branch Connector	NB	750	19.2	B	18.0	B
		SB	778	13.3	B		
		WB	967	20.8	C		
10	Jones Branch Connector and Express Lanes Ramps	NB	371	37.7	D	65.0	E
		SB	395	29.6	C		
		EB	815	20.8	C		
29	Jones Branch Drive and Capital One (West)	NB	262	37.3	D	17.6	B
		SB	213	37.3	D		
		EB	943	13.4	B		
		WB	600	8.8	A		
30	Jones Branch Drive and Capital One (East)	NB	63	16.2	B	5.3	A
		SB	118	13.5	B		
		EB	561	2.9	A		
		WB	725	4.9	A		
11	International Drive and Spring Hill Road/ Jones Branch Drive	NB	447	55.6	E	49.1	D
		SB	2,084	41.9	D		
		EB	659	58.4	E		
		WB	380	64.4	E		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	NB	571	24.7	C	150.7	F
		SB	1,017	82.9	F		
		EB	1,342	255.6	F		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	NB	608	16.3	B	77.1	E
		SB	712	28.8	C		
		WB	475	227.3	F		
14	Spring Hill Road and Lewinsville Road	NB	547	63.3	E	57.6	E
		SB	316	83.5	F		
		EB	603	65.0	E		
		WB	650	33.5	C		
23	Georgetown Pike and Helga Place/ Linganore Drive	NB	19	6.1	A	39.5	E
		SB	8	39.5	E		
		EB	1,114	9.8	A		
		WB	643	0.5	A		
20	Georgetown Pike and I-495 Southbound Ramps	SB	650	25.3	C	23.9	C
		EB	1,147	22.4	C		
		WB	531	25.4	C		
19	Georgetown Pike and I-495 Northbound Ramps	NB	442	32.1	C	20.7	C
		EB	1,264	17.0	B		
		WB	753	20.3	C		
18	Georgetown Pike and Balls Hill Road	NB	386	46.0	D	23.0	C
		SB	76	73.8	E		
		EB	879	13.7	B		
22	Georgetown Pike and Dead Run Drive	WB	495	13.9	B	9.5	A
		NB	93	8.8	A		
		EB	625	1.5	A		
		WB	480	0.8	A		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	135	14.7	B	10.9	B
		SB	180	15.2	B		
		EB	870	10.4	B		
		WB	260	7.3	A		
16	Old Dominion Drive at Swinks Mill Road	NB	295	25.3	C	16.2	B
		SB	200	22.8	C		
		EB	785	13.6	B		
		WB	210	6.7	A		
17	Old Dominion Drive at Balls Hill Road	NB	315	120.6	F	101.5	F
		SB	330	115.7	F		
		EB	555	84.6	F		
		WB	255	96.3	F		
21	Route 123 at Old Dominion Drive	NB	1,885	27.8	C	43.7	D
		SB	1,185	25.1	C		
		EB	675	83.9	F		
		WB	700	85.3	F		
24	Georgetown Pike at Swinks Mill Road	NB	560	101.9	F	33.4	D
		SB	0	0.0	A		
		EB	570	0.0	A		
		WB	635	2.1	A		
25	Georgetown Pike at Spring Hill Road	NB	40	16.7	C	1.1	A
		EB	585	0.0	A		
		WB	495	0.7	A		
26	Lewinsville Road at Swinks Mill Road	SB	205	47.6	E	9.0	A
		EB	890	2.7	A		
		WB	555	0.0	A		
27	Route 123 at Ingleside Avenue	NB	1,835	0.4	A	1.0	A
		SB	1,155	0.7	A		
		EB	85	14.2	B		
		WB	45	19.9	C		
28	Douglass Drive at Route 193 (Georgetown Pike)	NB	1,835	115.3	F	20.7	C
		SB	1,155	45.2	E		
		EB	85	0.4	A		
		WB	45	2.1	A		

2025 No-Build PM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,160	324.7	F	174.5	F
		SB	2,532	33.6	C		
		EB	1,228	245.6	F		
		WB	471	58.2	E		
4	Westpark Drive and Tysons Connector	NB	926	13.8	B	11.4	B
		SB	891	7.2	A		
		WB	267	17.3	B		
5	Tysons Connector and Express Lanes Ramps	NB	107	17.0	B	7.6	A
		SB	161	6.7	A		
		EB	1,140	6.8	A		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	2,255	329.8	F	177.1	F
		SB	2,387	44.4	D		
		EB	500	139.7	F		
		WB	641	163.4	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,011	111.1	F	76.9	E
		SB	1,940	40.0	D		
		EB	667	69.1	E		
		WB	799	86.9	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	2,164	108.7	F	85.9	F
		SB	1,486	36.7	D		
		EB	136	44.7	D		
		WB	448	150.9	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,007	43.6	D	116.3	F
		SB	2,005	55.0	D		
		EB	1,033	52.8	D		
		WB	669	615.8	F		
2	Lewinsville Road and Balls Hill Road	SB	196	38.7	D	116.6	F
		EB	934	222.5	F		
		WB	767	7.4	A		
9	Jones Branch Drive and Jones Branch Connector	NB	811	14.7	B	16.2	B
		SB	850	11.7	B		
		WB	643	24.0	C		
10	Jones Branch Connector and Express Lanes Ramps	NB	51	27.9	C	149.3	F
		SB	130	41.9	D		
		EB	896	16.2	B		
		WB	687	33.0	C		
29	Jones Branch Drive and Capital One (West)	SB	68	34.4	C	21.0	C
		EB	598	12.6	B		
		WB	489	12.5	B		
		NB	230	16.3	B		
30	Jones Branch Drive and Capital One (East)	SB	144	19.6	B	8.3	A
		EB	557	3.3	A		
		WB	478	6.7	A		
		NB	773	96.9	F		
11	International Drive and Spring Hill Road/ Jones Branch Drive	SB	635	61.8	E	89.0	F
		EB	828	71.7	E		
		WB	1,092	112.2	F		
		NB	1,682	15.1	B		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	SB	518	4.6	A	20.2	C
		EB	316	73.1	E		
		NB	1,413	37.9	D		
		WB	343	211.3	F		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	SB	538	29.0	C	61.8	E
		EB	343	211.3	F		
		NB	716	121.8	F		
		WB	220	75.8	E		
14	Spring Hill Road and Lewinsville Road	EB	383	61.7	E	75.0	E
		WB	818	40.1	D		
		NB	1	6.2	A		
		SB	4	157.9	F		
23	Georgetown Pike and Helga Place/ Linganore Drive	EB	787	59.4	F	157.9	F
		WB	834	1.1	A		
		SB	910	75.8	E		
		EB	816	45.0	D		
20	Georgetown Pike and I-495 Southbound Ramps	WB	727	62.9	E	61.7	E
		NB	176	38.7	D		
		EB	944	14.9	B		
		WB	1,404	20.9	C		
19	Georgetown Pike and I-495 Northbound Ramps	NB	323	184.2	F	19.9	B
		SB	166	41.7	D		
		EB	414	11.9	B		
		WB	1,009	52.5	D		
18	Georgetown Pike and Balls Hill Road	NB	335	55.5	F	65.0	E
		EB	207	0.4	A		
		WB	686	41.1	E		
		SB	166	41.7	D		
22	Georgetown Pike and Dead Run Drive	NB	335	55.5	F	58.6	F
		EB	207	0.4	A		
		WB	686	41.1	E		
		SB	166	41.7	D		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	270	16.2	B	10.8	B
		SB	110	13.7	B		
		EB	490	8.0	A		
		WB	615	10.2	B		
16	Old Dominion Drive at Swinks Mill Road	NB	305	15.7	B	12.1	B
		SB	165	13.8	B		
		EB	455	9.9	A		
		WB	590	11.5	B		
17	Old Dominion Drive at Balls Hill Road	NB	295	214.1	F	189.4	F
		SB	485	218.6	F		
		EB	370	205.7	F		
		WB	685	149.3	F		
21	Route 123 at Old Dominion Drive	NB	1,995	25.9	C	41.9	D
		SB	1,790	26.7	C		
		EB	510	85.8	F		
		WB	890	86.8	F		
24	Georgetown Pike at Swinks Mill Road	NB	360	23.4	C	6.5	A
		SB	0	0.0	A		
		EB	385	0.0	A		
		WB	875	1.3	A		
25	Georgetown Pike at Spring Hill Road	NB	65	13.3	B	1.7	A
		EB	355	0.0	A		
		WB	755	0.8	A		
		SB	225	85.8	F		
26	Lewinsville Road at Swinks Mill Road	EB	755	2.9	A	26.6	D
		WB	780	0.0	A		
		NB	1,895	3.6	A		
		SB	1,700	0.4	A		
27	Route 123 at Ingleside Avenue	EB	135	24.9	C	3.0	A
		WB	50	18.6	C		
		NB	170	280.2	F		
		SB	30	221.9	F		
28	Douglass Drive at Route 193 (Georgetown Pike)	EB	220	0.4	A	28.7	D
		WB	975	2.3	A		
		NB	170	280.2	F		
		SB	30	221.9	F		

2025 Build PM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,111	333.8	F	177.1	F
		SB	2,559	34.4	C		
		EB	1,274	245.8	F		
		WB	473	64.6	E		
4	Westpark Drive and Tysons Connector	NB	946	12.8	B	10.4	B
		SB	904	6.4	A		
		WB	225	16.4	B		
5	Tysons Connector and Express Lanes Ramps	NB	92	18.4	B	7.4	A
		SB	133	6.4	A		
		EB	1,157	6.7	A		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	2,296	329.5	F	178.7	F
		SB	2,366	42.7	D		
		EB	378	175.6	F		
		WB	656	142.9	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,046	109.6	F	71.9	E
		SB	1,932	37.0	D		
		EB	651	32.4	C		
		WB	815	91.4	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	2,226	94.7	F	78.7	E
		SB	1,471	35.0	C		
		EB	135	46.1	D		
		WB	451	152.5	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	1,881	42.4	D	113.9	F
		SB	2,013	50.8	D		
		EB	1,036	52.2	D		
		WB	675	596.2	F		
2	Lewinsville Road and Balls Hill Road	SB	197	37.6	D	117.1	F
		EB	939	221.7	F		
		WB	752	7.4	A		
9	Jones Branch Drive and Jones Branch Connector	NB	842	14.6	B	16.6	B
		SB	868	12.1	B		
		WB	641	25.4	C		
10	Jones Branch Connector and Express Lanes Ramps	NB	60	30.7	C	144.7	F
		SB	145	42.8	D		
		EB	959	16.3	B		
		WB	698	34.1	C		
29	Jones Branch Drive and Capital One (West)	SB	68	35.0	D	20.5	C
		EB	615	11.7	B		
		WB	511	10.5	B		
		NB	233	17.1	B		
30	Jones Branch Drive and Capital One (East)	SB	147	18.7	B	7.2	A
		EB	562	3.0	A		
		WB	491	4.0	A		
		NB	753	133.9	F		
11	International Drive and Spring Hill Road/ Jones Branch Drive	SB	647	60.0	E	99.8	F
		EB	833	79.3	E		
		WB	1,121	114.9	F		
		NB	1,716	15.9	B		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	SB	543	5.1	A	20.1	C
		EB	299	71.7	E		
		WB	1,406	37.8	D		
		NB	535	25.3	C		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	SB	259	80.4	F	39.8	D
		EB	718	120.0	F		
		WB	221	77.1	E		
		NB	382	68.0	E		
14	Spring Hill Road and Lewinsville Road	SB	822	42.3	D	76.5	E
		EB	0	0.0	A		
		WB	4	12.8	B		
		NB	514	0.2	A		
23	Georgetown Pike and Helga Place/ Linganore Drive	SB	865	0.9	A	28.0	D
		EB	986	36.2	D		
		WB	524	22.7	C		
		NB	691	66.5	E		
20	Georgetown Pike and I-495 Southbound Ramps	SB	179	35.6	D	42.5	D
		EB	676	12.8	B		
		WB	1,052	24.7	C		
		NB	247	55.5	E		
19	Georgetown Pike and I-495 Northbound Ramps	SB	138	34.5	C	21.5	C
		EB	426	9.9	A		
		WB	769	43.4	D		
		NB	264	70.3	F		
18	Georgetown Pike and Balls Hill Road	SB	221	0.3	A	35.5	D
		EB	221	0.3	A		
		WB	528	49.3	E		
		NB	264	70.3	F		
22	Georgetown Pike and Dead Run Drive	SB	221	0.3	A	71.5	F
		EB	221	0.3	A		
		WB	528	49.3	E		
		NB	264	70.3	F		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	270	16.2	B	10.8	B
		SB	110	13.7	B		
		EB	490	8.0	A		
		WB	615	10.2	B		
16	Old Dominion Drive at Swinks Mill Road	NB	305	15.7	B	12.1	B
		SB	165	13.8	B		
		EB	455	9.9	A		
		WB	590	11.4	B		
17	Old Dominion Drive at Balls Hill Road	NB	295	225.6	F	181.5	F
		SB	485	207.1	F		
		EB	370	197.3	F		
		WB	680	135.7	F		
21	Route 123 at Old Dominion Drive	NB	1,910	24.7	C	41.7	D
		SB	1,790	26.5	C		
		EB	510	85.8	F		
		WB	890	86.8	F		
24	Georgetown Pike at Swinks Mill Road	NB	260	15.8	C	4.4	A
		SB	0	0.0	A		
		EB	280	0.0	A		
		WB	875	1.2	A		
25	Georgetown Pike at Spring Hill Road	NB	50	12.7	B	1.6	A
		SB	265	0.0	A		
		WB	755	0.7	A		
		EB	225	87.9	F		
26	Lewinsville Road at Swinks Mill Road	SB	760	2.9	A	27.4	D
		EB	785	0.0	A		
		WB	1,825	3.8	A		
		NB	1,700	0.3	A		
27	Route 123 at Ingleside Avenue	SB	135	24.9	C	3.0	A
		EB	50	17.8	C		
		WB	165	144.2	F		
		NB	30	83.5	F		
28	Douglass Drive at Route 193 (Georgetown Pike)	SB	30	83.5	F	18.3	C
		EB	220	0.4	A		
		WB	850	2.7	A		
		NB	165	144.2	F		

2045 No-Build AM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,320	29.6	C	45.4	D
		SB	4,130	49.9	D		
		EB	721	67.0	E		
		WB	461	50.1	D		
4	Westpark Drive and Tysons Connector	NB	537	74.6	E	31.8	C
		SB	384	27.6	C		
		WB	1,728	19.4	B		
5	Tysons Connector and Express Lanes Ramps	NB	1,222	23.0	C	24.0	C
		SB	505	29.3	C		
		EB	399	20.3	C		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	3,667	113.9	F	105.9	F
		SB	2,084	35.8	D		
		EB	294	160.0	F		
		WB	691	251.8	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,806	37.4	D	55.4	E
		SB	2,281	38.3	D		
		EB	621	132.4	F		
		WB	622	122.5	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	1,782	21.9	C	145.6	F
		SB	1,838	275.1	F		
		EB	585	74.7	E		
		WB	280	230.1	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,029	44.7	D	211.0	F
		SB	1,426	348.2	F		
		EB	760	71.4	E		
		WB	666	583.5	F		
2	Lewinsville Road and Balls Hill Road	SB	160	1,033.3	F	102.8	F
		EB	674	32.7	C		
		WB	1,015	2.7	A		
9	Jones Branch Drive and Jones Branch Connector	NB	770	26.0	C	19.3	B
		SB	941	14.8	B		
		WB	929	18.4	B		
10	Jones Branch Connector and Express Lanes Ramps	NB	219	41.1	D	100.2	F
		SB	473	31.4	C		
		EB	941	43.2	D		
		WB	763	18.3	B		
29	Jones Branch Drive and Capital One (West)	NB	320	50.7	D	36.1	D
		SB	247	41.3	D		
		EB	1,004	46.4	D		
		WB	787	15.3	B		
30	Jones Branch Drive and Capital One (East)	NB	112	56.3	E	26.0	C
		SB	137	19.3	B		
		EB	717	39.9	D		
		WB	1,091	14.7	B		
11	International Drive and Spring Hill Road/ Jones Branch Drive	NB	546	56.8	E	45.7	D
		SB	1,656	33.7	C		
		EB	641	58.3	E		
		WB	432	59.0	E		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	NB	714	18.0	B	123.0	F
		SB	1,163	27.0	C		
		EB	717	383.1	F		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	NB	652	17.7	B	26.2	C
		SB	810	17.2	B		
		WB	467	53.8	D		
14	Spring Hill Road and Lewinsville Road	NB	682	86.7	F	57.2	E
		SB	332	71.9	E		
		EB	620	37.4	D		
		WB	543	33.7	C		
23	Georgetown Pike and Helga Place/ Linganore Drive	NB	23	6.1	A	231.7	F
		SB	8	231.7	F		
		EB	1,124	122.4	F		
		WB	724	1.1	A		
20	Georgetown Pike and I-495 Southbound Ramps	SB	523	28.4	C	40.2	D
		EB	1,160	40.4	D		
		WB	798	47.6	D		
19	Georgetown Pike and I-495 Northbound Ramps	NB	797	140.4	F	69.1	E
		EB	1,317	38.1	D		
		WB	964	52.5	D		
18	Georgetown Pike and Balls Hill Road	NB	379	151.7	F	59.7	E
		SB	86	66.1	E		
		EB	1,168	24.8	C		
		WB	694	67.6	E		
22	Georgetown Pike and Dead Run Drive	NB	123	13.4	B	14.3	B
		EB	841	1.5	A		
		WB	680	18.4	C		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	170	15.4	B	11.3	B
		SB	205	15.8	B		
		EB	875	10.5	B		
		WB	220	7.0	A		
16	Old Dominion Drive at Swinks Mill Road	NB	235	26.3	C	15.6	B
		SB	210	25.9	C		
		EB	830	12.4	B		
		WB	200	5.5	A		
17	Old Dominion Drive at Balls Hill Road	NB	270	121.5	F	97.1	F
		SB	340	109.7	F		
		EB	590	78.1	E		
		WB	235	98.3	F		
21	Route 123 at Old Dominion Drive	NB	1,975	37.3	D	48.8	D
		SB	1,335	29.7	C		
		EB	615	84.6	F		
		WB	840	86.2	F		
24	Georgetown Pike at Swinks Mill Road	NB	620	187.8	F	56.9	F
		SB	0	0.0	A		
		EB	615	0.0	A		
		WB	830	2.0	A		
25	Georgetown Pike at Spring Hill Road	NB	60	23.9	C	1.9	A
		EB	640	0.0	A		
		WB	665	1.0	A		
26	Lewinsville Road at Swinks Mill Road	SB	175	31.4	D	5.0	A
		EB	835	2.2	A		
		WB	450	0.0	A		
27	Route 123 at Ingleside Avenue	NB	2,025	0.5	A	1.6	A
		SB	1,230	0.9	A		
		EB	170	17.7	C		
		WB	50	22.8	C		
28	Douglass Drive at Route 193 (Georgetown Pike)	NB	215	478.6	F	55.7	F
		SB	75	45.9	E		
		EB	880	0.3	A		
		WB	650	1.1	A		

2045 Build AM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,331	27.7	C	29.4	C
		SB	4,121	18.4	B		
		EB	721	74.0	E		
		WB	460	66.8	E		
4	Westpark Drive and Tysons Connector	NB	537	81.4	F	35.5	D
		SB	404	29.3	C		
		WB	1,723	22.6	C		
5	Tysons Connector and Express Lanes Ramps	NB	1,284	25.3	C	26.5	C
		SB	439	31.3	C		
		EB	437	25.3	C		
31	Route 123 and EB DTR/SB I-495 C-D Road	NB	2,233	10.0	B	14.5	B
		SB	3,061	8.9	A		
		EB	1,932	28.4	C		
32	Route 123 and NB I-495 Ramp	NB	2,428	16.9	B	42.4	D
		SB	1,850	10.7	B		
		WB	3,077	81.6	F		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	3,897	41.6	D	69.1	E
		SB	1,988	42.0	D		
		EB	232	236.6	F		
		WB	676	249.6	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,852	40.2	D	71.0	E
		SB	2,226	43.2	D		
		EB	659	126.1	F		
		WB	581	265.9	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	1,837	20.0	B	82.4	F
		SB	1,641	80.3	F		
		EB	909	161.1	F		
		WB	284	246.1	F		
33	Route 123 & EB DTR Ramps	NB	1,257	2.7	A	150.5	F
		SB	1,737	257.5	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,450	46.4	D	231.5	F
		SB	1,204	493.4	F		
		EB	787	82.0	F		
		WB	650	625.5	F		
2	Lewinsville Road and Balls Hill Road	SB	212	554.3	F	89.1	F
		EB	660	71.0	E		
		WB	1,000	2.5	A		
9	Jones Branch Drive and Jones Branch Connector	NB	774	23.8	C	18.5	B
		SB	959	13.6	B		
		WB	950	19.0	B		
10	Jones Branch Connector and Express Lanes Ramps	NB	246	33.4	D	29.2	C
		SB	489	31.6	C		
		EB	986	35.7	D		
		WB	800	18.3	B		
29	Jones Branch Drive and Capital One (West)	NB	327	48.0	D	33.6	C
		SB	250	47.7	D		
		EB	1,081	39.2	D		
		WB	815	16.3	B		
30	Jones Branch Drive and Capital One (East)	NB	109	82.3	F	25.7	C
		SB	144	20.5	C		
		EB	764	37.7	D		
		WB	1,034	11.6	B		
11	International Drive and Spring Hill Road/ Jones Branch Drive	NB	551	58.3	E	45.5	D
		SB	2,023	42.1	D		
		EB	541	55.0	D		
		WB	439	33.4	C		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	NB	720	38.1	D	214.6	F
		SB	1,062	98.6	F		
		EB	1,242	416.2	F		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	NB	716	31.3	C	79.5	E
		SB	669	139.0	F		
		WB	596	70.8	E		
14	Spring Hill Road and Lewinsville Road	NB	730	117.2	F	125.7	F
		SB	333	124.8	F		
		EB	378	223.7	F		
		WB	532	68.5	E		
23	Georgetown Pike and Helga Place/ Linganore Drive	NB	19	0.0	A	86.1	F
		SB	8	86.1	F		
		EB	1,019	20.9	C		
		WB	848	1.3	A		
20	Georgetown Pike and I-495 Southbound Ramps	SB	720	29.2	C	39.7	D
		EB	1,041	44.1	D		
		WB	795	43.6	D		
19	Georgetown Pike and I-495 Northbound Ramps	NB	740	126.7	F	53.9	D
		EB	1,280	32.1	C		
		WB	920	25.7	C		
18	Georgetown Pike and Balls Hill Road	NB	395	45.8	D	24.2	C
		SB	103	41.8	D		
		EB	1,229	15.6	B		
		WB	640	24.5	C		
22	Georgetown Pike and Dead Run Drive	NB	114	13.8	B	14.7	B
		EB	897	2.1	A		
		WB	628	1.6	A		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	255	15.1	B	11.2	B
		SB	55	15.7	B		
		EB	240	10.5	B		
		WB	1,040	7.4	A		
16	Old Dominion Drive at Swinks Mill Road	NB	145	24.5	C	14.6	B
		SB	210	26.6	C		
		EB	840	12.2	B		
		WB	205	5.3	A		
17	Old Dominion Drive at Balls Hill Road	NB	225	108.0	F	87.0	F
		SB	345	91.8	F		
		EB	560	78.7	E		
		WB	245	79.7	E		
21	Route 123 at Old Dominion Drive	NB	225	32.6	C	45.0	D
		SB	345	27.0	C		
		EB	560	85.2	F		
		WB	245	82.0	F		
24	Georgetown Pike at Swinks Mill Road	NB	450	59.3	F	15.8	C
		SB	0	0.0	A		
		EB	585	0.0	A		
		WB	830	2.2	A		
25	Georgetown Pike at Spring Hill Road	NB	65	23.5	C	2.0	A
		EB	610	0.0	A		
		WB	640	0.9	A		
		SB	140	19.0	C		
26	Lewinsville Road at Swinks Mill Road	EB	835	1.3	A	2.6	A
		WB	450	0.0	A		
		NB	2,050	0.5	A		
27	Route 123 at Ingleside Avenue	SB	1,210	0.9	A	1.7	A
		EB	190	18.3	C		
		WB	50	23.2	C		
		NB	2,050	236.7	F		
28	Douglass Drive at Route 193 (Georgetown Pike)	SB	1,210	36.9	E	29.3	D
		EB	190	0.2	A		
		WB	50	1.1	A		
		NB	2,050	236.7	F		

2045 No-Build PM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,013	490.2	F	206.0	F
		SB	2,605	42.1	D		
		EB	1,561	169.5	F		
		WB	690	78.1	E		
4	Westpark Drive and Tysons Connector	NB	867	20.9	C	15.8	B
		SB	1,079	9.7	A		
		WB	328	22.3	C		
5	Tysons Connector and Express Lanes Ramps	NB	135	21.3	C	13.8	B
		SB	194	7.1	A		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	EB	1,549	14.0	B	80.2	F
		NB	2,803	58.2	E		
		SB	2,259	45.8	D		
		WB	458	128.3	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	694	249.8	F	80.3	F
		SB	2,199	41.4	D		
		EB	1,694	77.2	E		
		WB	942	113.4	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	1,115	133.7	F	192.9	F
		SB	2,100	59.4	E		
		EB	1,329	433.5	F		
		WB	159	47.0	D		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	436	155.6	F	230.1	F
		SB	2,005	44.6	D		
		EB	1,308	401.7	F		
		WB	1,179	69.3	E		
2	Lewinsville Road and Balls Hill Road	NB	487	922.0	F	168.7	F
		SB	197	290.7	F		
		EB	1,066	228.8	F		
		WB	545	7.2	A		
9	Jones Branch Drive and Jones Branch Connector	NB	647	229.4	F	76.6	E
		SB	1,477	35.9	D		
		EB	1,016	38.7	D		
		WB	80	73.9	E		
10	Jones Branch Connector and Express Lanes Ramps	NB	224	497.4	F	132.6	F
		SB	1,140	188.2	F		
		EB	1,324	26.5	C		
		WB	730	70.9	E		
29	Jones Branch Drive and Capital One (West)	NB	104	54.3	D	93.5	F
		SB	718	211.8	F		
		EB	849	17.6	B		
		WB	140	431.3	F		
30	Jones Branch Drive and Capital One (East)	NB	221	64.6	E	72.3	E
		SB	781	81.9	F		
		EB	1,047	18.9	B		
		WB	629	53.8	D		
11	International Drive and Spring Hill Road/ Jones Branch Drive	NB	764	43.8	D	47.6	D
		SB	672	50.9	D		
		EB	877	44.1	D		
		WB	1,309	14.5	B		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	NB	628	8.3	A	21.6	C
		SB	364	70.2	E		
		EB	1,043	34.2	C		
		WB	541	17.2	B		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	NB	207	56.3	E	31.6	C
		SB	741	106.3	F		
		EB	257	64.9	E		
		WB	433	47.3	D		
14	Spring Hill Road and Lewinsville Road	NB	695	38.6	D	67.2	E
		SB	257	64.9	E		
		EB	433	47.3	D		
		WB	695	38.6	D		
23	Georgetown Pike and Helga Place/ Linganore Drive	NB	1	0.0	A	125.6	F
		SB	4	125.6	F		
		EB	599	27.0	D		
		WB	1,198	3.1	A		
20	Georgetown Pike and I-495 Southbound Ramps	NB	866	22.5	C	24.5	C
		SB	615	38.8	D		
		EB	1,110	18.0	B		
		WB	315	305.1	F		
19	Georgetown Pike and I-495 Northbound Ramps	NB	822	45.9	D	60.3	E
		SB	1,601	19.5	B		
		EB	284	80.1	F		
		WB	145	35.9	D		
18	Georgetown Pike and Balls Hill Road	NB	419	9.3	A	40.7	D
		SB	1,285	42.9	D		
		EB	284	80.1	F		
		WB	145	35.9	D		
22	Georgetown Pike and Dead Run Drive	NB	345	1.4	A	40.6	E
		SB	229	0.6	A		
		WB	934	56.9	F		

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	285	16.2	B	11.0	B
		SB	130	13.8	B		
		EB	455	8.1	A		
		WB	605	10.1	B		
16	Old Dominion Drive at Swinks Mill Road	NB	285	15.4	B	11.7	B
		SB	165	13.7	B		
		EB	470	9.7	A		
		WB	585	11.0	B		
17	Old Dominion Drive at Balls Hill Road	NB	365	225.2	F	209.9	F
		SB	495	233.5	F		
		EB	420	227.3	F		
		WB	675	173.6	F		
21	Route 123 at Old Dominion Drive	NB	1,965	19.9	B	35.2	D
		SB	1,835	21.6	C		
		EB	460	84.9	F		
		WB	655	86.7	F		
24	Georgetown Pike at Swinks Mill Road	NB	290	25.8	D	5.6	A
		SB	0	0.0	A		
		EB	325	0.0	A		
		WB	1,255	0.9	A		
25	Georgetown Pike at Spring Hill Road	NB	60	20.1	C	2.3	A
		SB	325	0.0	A		
		EB	1,135	0.6	A		
		WB	195	35.9	E		
26	Lewinsville Road at Swinks Mill Road	NB	725	2.7	A	5.7	A
		SB	650	0.0	A		
		EB	1,760	3.2	A		
		WB	1,715	0.3	A		
27	Route 123 at Ingleside Avenue	NB	160	28.5	D	3.1	A
		SB	55	17.5	C		
		EB	1760	3.2	A		
		WB	1,715	0.3	A		
28	Douglass Drive at Route 193 (Georgetown Pike)	NB	255	898.5	F	118.8	F
		SB	55	269.2	F		
		EB	240	0.4	A		
		WB	1,040	1.7	A		

2045 Build PM - Intersection Delay

VISSIM RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
6	Route 123 and Tysons Boulevard	NB	2,020.0	486.4	F	207.4	F
		SB	2,703.0	33.8	C		
		EB	1,356.0	208.3	F		
		WB	684.0	67.9	E		
4	Westpark Drive and Tysons Connector	NB	872.0	27.6	C	19.0	B
		SB	1,121.0	10.9	B		
		WB	348.0	23.5	C		
5	Tysons Connector and Express Lanes Ramps	NB	136.0	23.2	C	13.9	B
		SB	212.0	6.6	A		
		EB	1,629.0	14.0	B		
31	Route 123 and EB DTR/SB I-495 C-D Road	NB	2,375.0	5.0	A	10.1	B
		SB	1,949.0	5.3	A		
		EB	942.0	33.1	C		
32	Route 123 and NB I-495 Ramp	NB	1,924.0	10.4	B	24.1	C
		SB	2,259.0	20.9	C		
		WB	1,466.0	47.2	D		
7	Route 123 and Capital One Tower Drive/ Old Meadow Road	NB	2,721.0	56.9	E	78.1	E
		SB	2,312.0	37.7	D		
		EB	335.0	164.9	F		
		WB	653.0	264.6	F		
8	Route 123 and Scotts Crossing Boulevard/ Colshire Drive	NB	2,057.0	32.5	C	71.9	E
		SB	1,776.0	55.8	E		
		EB	964.0	110.9	F		
		WB	1,103.0	137.4	F		
1	Route 123 and Route 267 Eastbound Off-Ramp/ Anderson Road	NB	2,027.0	45.7	D	86.8	F
		SB	1,259.0	109.8	F		
		EB	477.0	132.0	F		
		WB	418.0	165.3	F		
33	Route 123 & EB DTR Ramps	NB	1,141.0	5.3	A	196.3	F
		SB	1,353.0	357.4	F		
3	Route 123 and Lewinsville Road/ Great Falls Street	NB	2,007.0	43.3	D	253.4	F
		SB	1,140.0	501.7	F		
		EB	1,142.0	76.2	E		
		WB	460.0	995.2	F		
2	Lewinsville Road and Balls Hill Road	SB	191.0	343.4	F	191.5	F
		EB	1,028.0	252.4	F		
		WB	497.0	7.0	A		
9	Jones Branch Drive and Jones Branch Connector	NB	441.0	696.4	F	151.9	F
		SB	1,474.0	68.2	E		
		WB	1,029.0	38.5	D		
10	Jones Branch Connector and Express Lanes Ramps	NB	82.0	51.0	D	139.1	F
		SB	295.0	72.3	E		
		EB	1,060.0	300.0	F		
		WB	1,351.0	32.9	C		
29	Jones Branch Drive and Capital One (West)	NB	729.0	75.8	E	98.3	F
		SB	103.0	54.0	D		
		EB	735.0	220.6	F		
		WB	860.0	18.0	B		
30	Jones Branch Drive and Capital One (East)	NB	149.0	418.0	F	70.8	E
		SB	227.0	58.3	E		
		EB	793.0	77.8	E		
		WB	1,009.0	16.9	B		
11	International Drive and Spring Hill Road/ Jones Branch Drive	NB	658.0	71.6	E	54.1	D
		SB	762.0	42.1	D		
		EB	701.0	52.8	D		
		WB	902.0	52.5	D		
12	Spring Hill Road and Dulles Toll Road Eastbound Ramps	NB	1,412.0	18.3	B	24.3	C
		SB	628.0	11.3	B		
		EB	362.0	70.1	E		
13	Spring Hill Road and Dulles Toll Road Westbound Ramps	NB	1,147.0	40.0	D	39.6	D
		SB	553.0	22.6	C		
		WB	277.0	71.7	E		
14	Spring Hill Road and Lewinsville Road	NB	733.0	118.9	F	70.8	E
		SB	260.0	63.5	E		
		EB	441.0	46.7	D		
		WB	702.0	38.5	D		
23	Georgetown Pike and Helga Place/ Linganore Drive	NB	1.0	0.0	A	13.1	B
		SB	4.0	9.8	A		
		EB	346.0	0.2	A		
		WB	1,268.0	4.1	A		
20	Georgetown Pike and I-495 Southbound Ramps	SB	947.0	21.9	C	21.9	C
		EB	353.0	22.5	C		
		WB	1,110.0	21.6	C		
19	Georgetown Pike and I-495 Northbound Ramps	NB	334.0	319.3	F	63.8	E
		EB	588.0	37.8	D		
		WB	1,303.0	10.1	B		
18	Georgetown Pike and Balls Hill Road	NB	246.0	40.2	D	18.7	B
		SB	131.0	29.6	C		
		EB	473.0	8.7	A		
		WB	1,049.0	16.8	B		
22	Georgetown Pike and Dead Run Drive	NB	289.0	13.6	B	13.8	B
		EB	240.0	0.5	A		
		WB	771.0	1.1	A		

Note : Results reflect updated geometry/signal timings at Georgetown Pike/Balls Hill Road

SYNCHRO RESULTS							
#	Intersection	Approach	Volume	Average Approach Delay (sec/veh)	Approach LOS	Intersection Delay (sec/veh)	Intersection LOS
15	Old Dominion Drive at Spring Hill Road	NB	175	14.8	B	9.9	A
		SB	65	13.4	B		
		EB	465	7.6	A		
		WB	590	10.0	A		
16	Old Dominion Drive at Swinks Mill Road	NB	110	13.0	B	10.1	B
		SB	155	13.7	B		
		EB	435	8.5	A		
		WB	575	9.7	A		
17	Old Dominion Drive at Balls Hill Road	NB	230	231.0	F	174.6	F
		SB	525	203.8	F		
		EB	395	179.3	F		
		WB	670	129.5	F		
21	Route 123 at Old Dominion Drive	NB	2,000	21.8	C	36.4	D
		SB	1,800	22.5	C		
		EB	485	85.8	F		
		WB	700	82.2	F		
24	Georgetown Pike at Swinks Mill Road	NB	180	18.1	C	4.0	A
		SB	0	0.0	A		
		EB	200	0.0	A		
		WB	1,260	0.8	A		
25	Georgetown Pike at Spring Hill Road	NB	45	19.6	C	2.1	A
		EB	215	0.0	A		
		WB	1,140	0.6	A		
		SB	85	29.1	D		
26	Lewinsville Road at Swinks Mill Road	EB	735	0.9	A	2.1	A
		WB	700	0.0	A		
		NB	1,830	1.4	A		
27	Route 123 at Ingleside Avenue	SB	1,695	0.3	A	2.0	A
		EB	145	26.1	D		
		WB	55	19.4	C		
28	Douglass Drive at Route 193 (Georgetown Pike)	NB	235	513.1	F	70.4	F
		SB	55	98.0	F		
		EB	260	0.3	A		
		WB	915	1.9	A		

**Appendix E: I-495 NEXT Traffic Operations Analysis
Framework Memorandum**

MEMORANDUM

To: Ivan Horodyskyj, P.E., VDOT NoVA District Traffic Engineer
Abi Lerner, P.E., VDOT Project Manager

From: Rob Prunty, P.E.
Raj Paradkar, P.E.
Anthony Gallo, P.E.
Kimley-Horn and Associates, Inc.

Date: August 29, 2018

Subject: I-495 NEXT Traffic Operations Analysis Framework

Introduction

This memorandum documents the traffic operations analysis framework associated with the I-495 NEXT Project. This memorandum is intended to supplement the overarching I-495 NEXT Project Scoping Framework Document.

The following elements of the traffic operations analysis are laid out in detail in this document:

- Traffic data collection
- Traffic analysis tools and measures of effectiveness (MOEs)
- Traffic simulation model calibration methodology and assumptions

Traffic Data Collection

Traffic Volumes

The following intersection locations will have traffic counts conducted in the year 2018 and be analyzed as part of the traffic operations analysis:

1. Westpark Drive Connector at I-495 Express Lane ramp terminals
2. Westpark Drive Connector at West Park Drive
3. Route 123 at Tysons Boulevard / Entrance to Tysons Mall Ring Road
4. Route 123 at Old Meadow Road / Capital One Tower Drive
5. Route 123 at Scotts Crossing Road / Colshire Drive
6. Route 123 at Anderson Road / Dulles Toll Road Connector ramp terminal
7. Route 123 at Great Falls Street / Lewinsville Road
8. Lewinsville Road at Balls Hill Road
9. Lewinsville Road at Swinks Mill Road
10. Lewinsville Road at Spring Hill Road
11. Spring Hill Road at Dulles Toll Road WB ramp terminals
12. Spring Hill Road at Dulles Toll Road EB ramp terminals
13. Spring Hill Road at International Drive / Jones Branch Drive

14. Jones Branch Drive at Jones Branch Connector
15. Jones Branch Connector at I-495 Express Lane ramp terminals
16. Old Dominion at Spring Hill Road
17. Old Dominion at Swinks Mill Road
18. Old Dominion at Balls Hill Road
19. Georgetown Pike at Dead Run Drive
20. Georgetown Pike at Balls Hill Road
21. Georgetown Pike at NB I-495 GP NB ramp terminals
22. Georgetown Pike at SB I-495 GP NB ramp terminals
23. Georgetown Pike at Linganore Drive / Helga Place
24. Georgetown Pike at Swinks Mill Road
25. Georgetown Pike at Spring Hill Road
26. Georgetown Pike at Douglass Drive
27. Route 123 at Ingleside Avenue
28. Route 123 at Old Dominion Drive

The following interchanges will have traffic counts conducted in the year 2018 and will be analyzed as part of the traffic operations analysis:


1. I-495 GP at Route 123
2. I-495 Express Lanes at Westpark Drive Connector
3. I-495 Express Lanes at Jones Branch Connector
4. I-495 GP at Dulles Toll Road and Dulles Airport Access Road
5. I-495 Express Lanes at Dulles Toll Road
6. I-495 at Georgetown Pike
7. I-495 at George Washington Memorial Parkway
8. I-495 at Clara Barton Parkway
9. Dulles International Airport Access Highway ramps to / from Dulles Toll Road (VA Route 267), east and west of I-495
10. Dulles Toll Road (VA Route 267) at Spring Hill Road (VA Route 684)
11. Dulles Toll Road (VA Route 267) at Dolley Madison Road (VA Route 123)
12. George Washington Memorial Parkway and Turkey Run Park

Traffic count locations are shown in Figure 1.

Traffic volumes used in the traffic and operations analysis will consist of the following:

- **Existing (2018)** – Developed from field counts (ramps, freeway mainline, and intersection turning movements) conducted in June 2018. Count data will be post-processed and balanced between all adjacent locations in the traffic operations analysis study area.
- **Opening Year (2025)** – No Build and one Build alternative developed through modifications to the MWCOG 2025 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.
- **Design Year (2045)** – No Build and one Build alternative developed through modifications to the MWCOG 2045 travel demand model for the I-495 corridor and post-processed based on 2018 data collection.

Figure 1: Traffic Count Locations



Origin-Destination Data

The traffic simulation modeling effort will route vehicles through the traffic network according to origin-destination routing. Origin-destination data will be reviewed from the following sources:

- StreetLight Data, which via a VDOT subscription provides customized origin-destination data with a very high level of spatial accuracy based on aggregated cellular device GPS/location-based services data. StreetLight Data allows for a user to provide custom origins and destinations, such as on- and off-ramps for all freeways in a study area or entry/exit links to a study area. It is anticipated that StreetLight Data will be used as the basis for origin-destination routing for the existing conditions traffic analysis, at the very least for the freeway and ramp segments of the study area.
- MWCOC regional travel demand model, which outputs O-D matrices for various vehicle types between each traffic analysis zone (TAZ) in the Washington, DC, metropolitan area. The travel patterns within the model base year (2017) have been calibrated against 2007/2008 regional household travel survey data, so the travel patterns are somewhat dated. Additionally, this dataset is not as granular as needed to account for freeway weaving proportions. However, given that the travel demand model provides O-D matrices for future years, it is anticipated that these may be used as the basis for vehicle routing in future analysis year scenarios.

Speeds and Travel Times

Floating car travel time runs were conducted in June 2018 during the AM and PM peak periods for the following segments:

Corridor #	Corridor Name
1	I-495 Northbound – From south of Route 123 to River Road CD road;
3	I-495 Southbound – From River Road CD road to south of Route 123;
2	I-495 Northbound to DTR Westbound – From Route 123 to Spring Hill Road;
8	DTR Eastbound to I-495 Southbound – From west of Spring Hill Road to south of Route 123
4	I-495 Southbound to DTR Connector Eastbound from River Road CD road to east of Route 123
10	DTR Westbound Connector to I-495 Northbound – from east of Route 123 to River Road CD road.
5	I-495 Southbound to DTR Westbound – From River Road CD road to Spring Hill Road;
7	DTR Eastbound to I-495 Northbound – From west of Spring Hill Road to River Road CD road;
6	DTR Eastbound – From west of Spring Hill Road to east of Route 123;
9	DTR Westbound – From east of Route 123 to west of Spring Hill Road

In addition, INRIX vehicle probe speed data has been queried for the corridor using the RITIS Congestion Scan tool, which provides a “heat map” of vehicle speeds temporally and spatially along a corridor. This data has been pulled for “average weekdays” (Tuesday, Wednesday, and Thursday) for the 12 most recently available months of data (July 2017 through June 2018).

Queueing Data

Queueing along the freeway segments of the corridor will be provided via the INRIX heat map and verified against Google Maps’ typical traffic. Queueing along arterials and ramps will be obtained via screen captures from Google Maps’ typical traffic. Targeted spot locations will be verified in the field.

Traffic Operational Analysis Tools and Measures


Traffic Analysis Tools

VISSIM Version 9.0 will be used for a comprehensive network traffic analysis for the freeways, interchanges, and adjacent intersections within the traffic operations analysis area limits. (Reference analysis tool selection matrix, *VDOT Traffic Operations and Safety Analysis Manual [TOSAM] V1.0*¹, Appendix D.) Additional calibration, based on simulated volume processed, travel times, queues, and speed profiles, will be performed against 2018 measured field conditions and traffic data.

Surface street intersection operations will be evaluated through a combination of Synchro 10 (in order to develop preliminary optimization for phasing and signal timing) and VISSIM (for microsimulation and analysis). The expanded arterial network beyond intersections immediately adjacent to freeway interchanges in the corridor will be evaluated solely through Synchro. Transit routes and stops will be coded into the study area VISSIM network where they affect or could affect I-495 and related facility operations. The VISSIM and Synchro study areas are shown in Figure 2.

¹ <http://www.virginiadot.org/business/resources/TOSAM.pdf>

Figure 2. I-495 NEXT Traffic Operations VISSIM and Synchro Analysis Areas



Vehicle Classes

The following vehicle classes will be assumed for the traffic operations analysis VISSIM modeling:

- General purpose (non-toll-paying) cars
- HOV3+ cars
- HOT (toll paying) cars
- GP (non-toll-paying) trucks
- HOT (toll paying) trucks

Measures of Effectiveness

The following measures of effectiveness (MOEs) will be used for the operational analysis of the roadway network under existing and future Build and No-Build conditions.

Freeway Performance Measures

- Simulated Average Speed (mph)
- Simulated Average Density (pc/ln/mile, color-coded similar to the equivalent Density-Based LOS Thresholds)
- Simulated Volume (vehicles per hour)

The VISSIM freeway MOEs will be reported for each freeway segment. In addition, the following freeway MOEs also are proposed for reporting in the IJR:

- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).
- **Simulated Ramp Queue Length.** Reported for 50th and 95th percentiles (feet).
- **Simulated Travel Time.** Reported for select network origin-destination travel paths (seconds).
- **Congestion Heat Maps.** Incremental speeds reported for aggregated lanes, by time interval (mph).

Arterial/Intersection Performance Measures

- **Simulated Intersection Level of Service (LOS) and Average Control Delay.** Reported by approach and by intersection (sec/veh, color-coded in similar fashion as the equivalent Highway Capacity Manual (HCM) Delay-Based LOS Thresholds).
- **Simulated Intersection Approach Queue.** Reported by movement (feet).
- **Percent of Demand Served.** Simulated Volume (*processed volumes*) divided by Actual Volume (*input volumes*).

Traffic Modeling Methodology and Assumptions

Calibration Methodology for Base Models

The VISSIM base models will be calibrated based on guidance from *VDOT Traffic Operations and Safety Analysis Manual (TOSAM)*, Version 1. A full review of the criteria and acceptance targets is provided in the attached **I-495 NEXT Traffic Analysis Microsimulation Calibration Methodology Memorandum**. This memorandum was approved and signed by the VDOT NoVA District Traffic

Engineer on July 27, 2018. The following criteria and thresholds are proposed for VISSIM model calibration:

Calibration Item	Basis	Criteria	Target
Simulated Traffic Volume (Intersections)	By Intersection Approach	Within $\pm 20\%$ for <100 vph	At least 85% of all Intersection Approaches
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Traffic Volume (Freeways)	By Freeway Segment	Within $\pm 20\%$ for <100 vph	At least 85% of all Freeway Segments
		Within $\pm 15\%$ for ≥ 100 vph to < 300 vph	
		Within $\pm 10\%$ for ≥ 300 vph to $< 1,000$ vph	
		Within $\pm 5\%$ for $\geq 1,000$ vph	
Simulated Travel Time	By Route	Within $\pm 30\%$ for average travel times on arterials	At least 85% of all Travel Time Routes (Including Segments)
		Within $\pm 20\%$ for average travel times on freeways	
Maximum Simulated Queue Length	By Approach for Targeted Critical Locations	Modeled queues qualitatively reflect the impacts of observed queues	Qualitative Visual Match
Visual Review of Bottleneck Locations	Targeted Critical Locations	Speed heat maps qualitatively reflect patterns and duration of congestion	Qualitative Subjective Assessment

The following locations have been proposed for queue length calibration and reporting:

Queue Type	Location
Ramp	Ramp from SR 267 EB to I-495 NB GP
Ramp	Ramp from DAAR EB to I-495 NB GP
Ramp	Ramp from SR 267 EB to I-495 SB GP
Ramp	Ramp from SR 267 EB to Route 123 NB
Ramp	Ramp from Georgetown Pike (SR 193) to I-495 NB GP
Ramp	Ramp from George Washington Memorial Parkway NB to I-495 NB GP
Approach	Georgetown Pike (SR 193) EB approaching I-495 NB GP ramps
Approach	Georgetown Pike (SR 193) WB approaching I-495 NB GP ramps

Approach	Balls Hill Rd NB approaching Georgetown Pike
Approach	Spring Hill Rd NB approaching Lewinsville Road
Approach	Route 123 NB approaching Great Falls St
Approach	Lewinsville Road EB approaching Balls Hill Road

Potential Adjustments for Calibration

Adjustments to the VISSIM model during the calibration process will follow guidance from the VDOT TOSAM. These adjustments could include modifications to lane change distance for connectors, driver behavior along freeways and arterials, adjustments to desired speeds for vehicles at the network termini (such as along I-495 northbound leaving the study area), etc. The technical memorandum detailing calibration results will identify any potential deviations from TOSAM guidance.

Simulation Time, Seeding Time, and Number of Runs

The I-495 NEXT traffic operations study area is a severely oversaturated network during the weekday AM and PM peak periods, with several hours of congestion in both directions along I-495, especially along I-495 northbound approaching the American Legion Bridge. During these congested periods, traffic volume throughput is constrained due to low speeds and can be much lower than the actual maximum counted volumes along the freeway. Due to the oversaturated conditions, the analysis period was selected based on the heaviest periods of congestion and slowest speeds experienced along the corridor.

Figure 3 shows 15-minute average speeds along the I-495 northbound general purpose lanes through the study area for average weekdays (Tuesday, Wednesday, and Thursday) from July 2017 through June 2018. Note that during both the AM and PM peak periods, speeds along I-495 northbound are slower than speeds along I-495 southbound due to the downstream bottleneck at the American Legion Bridge. Thus, the analysis period and peak hours have been selected specifically based on congestion in the I-495 northbound general purpose lanes.

Figure 3 also show the proposed simulation analysis periods, which were also approved by the VDOT NoVA District Traffic Engineer as documented in the attached memorandum. These analysis periods would each be preceded by a 30-minute seeding period in the VISSIM models:

- AM peak: 6:45 AM to 9:45 AM (peak hour 7:45 AM to 8:45 AM). This will capture the onset of queueing back from the American Legion Bridge and the start of the dissipation of the queue. The peak hour captures the current worst extent of queueing.
- PM peak: 2:45 PM to 5:45 PM (peak hour 3:45 PM to 4:45 PM). This peak period is intended to capture queue formation from the American Legion Bridge *before the queue from points further north in Maryland spill back and create a single continuous queue*. This can be observed in the figure, as prior to approximately 3:30 PM, congestion in Virginia does not continue into Maryland. By approximately 4:00 PM, a single continuous area of congestion is present from north of the study area through the Route 123 interchange. Between approximately 4:00 PM and 7:00 PM, however, the extent of queueing stays relatively consistent – to the Route 123 interchange. The congestion does not fully dissipate until after 8:00 PM on average – note that the proposed traffic analysis period is not recommended to last until this point. Rather, the proposed traffic analysis period captures the onset of queueing (from when the queue is not due to spillback from Maryland) until it reaches its maximum.

Although the peak period in the afternoon and evening typically extends beyond six hours of congestion, the proposed analysis periods will still capture the onset of congestion and maximum extents of congestion, while allowing for the analysis to proceed in a streamlined manner within the scope and schedule of the project.

Conclusion

The VISSIM calibration criteria and simulation analysis peak hours and peak periods have been reviewed and approved by the VDOT NoVA District Traffic Engineer. The elements of the traffic analysis framework were presented to VDOT staff on July 20, 2018. The analysis tools and framework described in this document will be carried forward for the I-495 NEXT project.

Appendix F: Sample MOVE Run Specification for MSAT Analysis

Sample MOVES2014b Run-Spec

2021 Scenario Run for Diesel PM

```
<runspec version="MOVES2014b-20181203">
  <description><![CDATA[I-495 NEXT MSAT Analysis - DPM
Year: 2017
Scenario: Existing
County: Fairfax]]></description>
  <models>
    <model value="ONROAD"/>
  </models>
  <modelscale value="Inv"/>
  <modeldomain value="SINGLE"/>
  <geographicselections>
    <geographicselection type="COUNTY" key="51059" description="VIRGINIA - Fairfax
County"/>
  </geographicselections>
  <timespan>
    <year key="2017"/>
    <month id="1"/>
    <month id="4"/>
    <month id="7"/>
    <month id="10"/>
    <day id="5"/>
    <beginhour id="1"/>
    <endhour id="24"/>
    <aggregateBy key="Hour"/>
  </timespan>
  <onroadvehicleselections>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="62"
sourcetyname="Combination Long-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="61"
sourcetyname="Combination Short-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="41"
sourcetyname="Intercity Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="32"
sourcetyname="Light Commercial Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="54"
sourcetyname="Motor Home"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="21"
sourcetyname="Passenger Car"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="31"
sourcetyname="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="51"
sourcetyname="Refuse Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="43"
sourcetyname="School Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="53"
sourcetyname="Single Unit Long-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="52"
sourcetyname="Single Unit Short-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="42"
sourcetyname="Transit Bus"/>
  </onroadvehicleselections>
```

```

    <offroadvehicleselections>
    </offroadvehicleselections>
    <offroadvehiclesccs>
    </offroadvehiclesccs>
    <roadtypes separateramps="false">
        <roadtype roadtypeid="2" roadtypename="Rural Restricted Access" modelCombination="M1"/>
        <roadtype roadtypeid="3" roadtypename="Rural Unrestricted Access"
modelCombination="M1"/>
        <roadtype roadtypeid="4" roadtypename="Urban Restricted Access" modelCombination="M1"/>
        <roadtype roadtypeid="5" roadtypename="Urban Unrestricted Access"
modelCombination="M1"/>
    </roadtypes>
    <pollutantprocessassociations>
        <pollutantprocessassociation pollutantkey="118" pollutantname="Composite - NonECPM" processkey="1"
processname="Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="112" pollutantname="Elemental Carbon" processkey="1"
processname="Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="119" pollutantname="H2O (aerosol)" processkey="1"
processname="Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="100" pollutantname="Primary Exhaust PM10 - Total"
processkey="1" processname="Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="100" pollutantname="Primary Exhaust PM10 - Total"
processkey="15" processname="Crankcase Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="110" pollutantname="Primary Exhaust PM2.5 - Total"
processkey="1" processname="Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="110" pollutantname="Primary Exhaust PM2.5 - Total"
processkey="15" processname="Crankcase Running Exhaust"/>
        <pollutantprocessassociation pollutantkey="115" pollutantname="Sulfate Particulate" processkey="1"
processname="Running Exhaust"/>
    </pollutantprocessassociations>
    <databaseselections>
        <databaseselection servername="" databasename="MOVES2014_early_NLEV" description=""/>
        <databaseselection servername="" databasename="va_stage2_input_20161104" description=""/>
    </databaseselections>
    <internalcontrolstrategies>
<internalcontrolstrategy
classname="gov.epa.otaq.moves.master.implementation.ghg.internalcontrolstrategies.rateofprogress.RateOfProgress
Strategy"><![CDATA[
useParameters    No

]]></internalcontrolstrategy>
    </internalcontrolstrategies>
    <inputdatabase servername="" databasename="" description=""/>
    <uncertaintyparameters uncertaintymodeenabled="false" numberofrunsersimulation="0"
numberofsimulations="0"/>
    <geographicoutputdetail description="COUNTY"/>
    <outputemissionsbreakdownselection>
        <modelyear selected="false"/>
        <fueltype selected="true"/>
        <fuelsubtype selected="false"/>
        <emissionprocess selected="true"/>
        <onroadoffroad selected="true"/>
        <roadtype selected="true"/>
        <sourceusetype selected="true"/>
        <movesvehicletype selected="false"/>
        <onroadsc selected="false"/>

```

```

        <estimateuncertainty selected="false" numberOfIterations="2" keepSampledData="false"
keepIterations="false"/>
        <sector selected="false"/>
        <engtechid selected="false"/>
        <hpclass selected="false"/>
        <regclassid selected="false"/>
    </outputemissionsbreakdownselection>
    <outputdatabase servername="localhost" databasename="I495_MSAT_51059_2017_4Seasons_mo"
description=""/>
    <outputtimestep value="24-Hour Day"/>
    <outputvmtdata value="true"/>
    <outputsho value="false"/>
    <outputsh value="false"/>
    <outputshp value="false"/>
    <outputshidling value="false"/>
    <outputstarts value="false"/>
    <outputpopulation value="true"/>
    <scaleinputdatabase servername="localhost" databasename="I495_MSAT_51059_2017_4Seasons_mi"
description=""/>
    <pmsize value="0"/>
    <outputfactors>
        <timefactors selected="true" units="Days"/>
        <distancefactors selected="true" units="Miles"/>
        <massfactors selected="true" units="Grams" energyunits="Million BTU"/>
    </outputfactors>
    <savedata>

    </savedata>

    <donotexecute>

    </donotexecute>

    <generatordatabase shouldsave="false" servername="" databasename="" description=""/>
    <donotperformfinalaggregation selected="false"/>
    <lookuptableflags scenarioid="" truncateoutput="false" truncateactivity="false" truncatebaserates="true"/>
</runspec>

```

2021 Scenario Run for MSAT Pollutants without Diesel PM

```
<runspec version="MOVES2014b-20181203">
  <description><![CDATA[I-495 NEXT MSAT Analysis - No Diesel PM
Year: 2017
Scenario: Existing
County: Fairfax]]></description>
  <models>
    <model value="ONROAD"/>
  </models>
  <modelscale value="Inv"/>
  <modeldomain value="SINGLE"/>
  <geographicselections>
    <geographicselection type="COUNTY" key="51059" description="VIRGINIA - Fairfax
County"/>
  </geographicselections>
  <timespan>
    <year key="2017"/>
    <month id="1"/>
    <month id="4"/>
    <month id="7"/>
    <month id="10"/>
    <day id="5"/>
    <beginhour id="1"/>
    <endhour id="24"/>
    <aggregateBy key="Hour"/>
  </timespan>
  <onroadvehicleselections>
    <onroadvehicleselection fueltypeid="3" fueltypedesc="Compressed Natural Gas (CNG)" sourcetypeid="42"
sourcetyname="Transit Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="62"
sourcetyname="Combination Long-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="61"
sourcetyname="Combination Short-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="41"
sourcetyname="Intercity Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="32"
sourcetyname="Light Commercial Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="54"
sourcetyname="Motor Home"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="21"
sourcetyname="Passenger Car"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="31"
sourcetyname="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="51"
sourcetyname="Refuse Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="43"
sourcetyname="School Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="53"
sourcetyname="Single Unit Long-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="52"
sourcetyname="Single Unit Short-haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="42"
sourcetyname="Transit Bus"/>
    <onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="32"
sourcetyname="Light Commercial Truck"/>
```

```
<onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="21"
sourcetypername="Passenger Car"/>
<onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="31"
sourcetypername="Passenger Truck"/>
<onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="32"
sourcetypername="Light Commercial Truck"/>
<onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="21"
sourcetypername="Passenger Car"/>
<onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="31"
sourcetypername="Passenger Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="61"
sourcetypername="Combination Short-haul Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="32" sourcetypername="Light
Commercial Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="54" sourcetypername="Motor
Home"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="11"
sourcetypername="Motorcycle"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="21"
sourcetypername="Passenger Car"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="31"
sourcetypername="Passenger Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="51"
sourcetypername="Refuse Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="43"
sourcetypername="School Bus"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="53" sourcetypername="Single
Unit Long-haul Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="52" sourcetypername="Single
Unit Short-haul Truck"/>
<onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="42"
sourcetypername="Transit Bus"/>
</onroadvehicleselections>
<offroadvehicleselections>
</offroadvehicleselections>
<offroadvehiclesccs>
</offroadvehiclesccs>
<roadtypes separateramps="false">
<roadtype roadtypeid="2" roadtypename="Rural Restricted Access" modelCombination="M1"/>
<roadtype roadtypeid="3" roadtypename="Rural Unrestricted Access"
modelCombination="M1"/>
<roadtype roadtypeid="4" roadtypename="Urban Restricted Access" modelCombination="M1"/>
<roadtype roadtypeid="5" roadtypename="Urban Unrestricted Access"
modelCombination="M1"/>
</roadtypes>
<pollutantprocessassociations>
<pollutantprocessassociation pollutantkey="24" pollutantname="1,3-Butadiene" processkey="1"
processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="24" pollutantname="1,3-Butadiene" processkey="15"
processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="170" pollutantname="Acenaphthene gas" processkey="1"
processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="170" pollutantname="Acenaphthene gas" processkey="15"
processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="70" pollutantname="Acenaphthene particle" processkey="1"
processname="Running Exhaust"/>
```

<pollutantprocessassociation pollutantkey="70" pollutantname="Acenaphthene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="171" pollutantname="Acenaphthylene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="171" pollutantname="Acenaphthylene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="71" pollutantname="Acenaphthylene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="71" pollutantname="Acenaphthylene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="26" pollutantname="Acetaldehyde" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="26" pollutantname="Acetaldehyde" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="27" pollutantname="Acrolein" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="27" pollutantname="Acrolein" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="172" pollutantname="Anthracene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="172" pollutantname="Anthracene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="72" pollutantname="Anthracene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="72" pollutantname="Anthracene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="173" pollutantname="Benz(a)anthracene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="173" pollutantname="Benz(a)anthracene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="73" pollutantname="Benz(a)anthracene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="73" pollutantname="Benz(a)anthracene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="20" pollutantname="Benzene" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="20" pollutantname="Benzene" processkey="11" processname="Evap Permeation"/>
<pollutantprocessassociation pollutantkey="20" pollutantname="Benzene" processkey="13" processname="Evap Fuel Leaks"/>
<pollutantprocessassociation pollutantkey="20" pollutantname="Benzene" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="174" pollutantname="Benzo(a)pyrene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="174" pollutantname="Benzo(a)pyrene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="74" pollutantname="Benzo(a)pyrene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="74" pollutantname="Benzo(a)pyrene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="175" pollutantname="Benzo(b)fluoranthene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="175" pollutantname="Benzo(b)fluoranthene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="75" pollutantname="Benzo(b)fluoranthene particle" processkey="1" processname="Running Exhaust"/>

<pollutantprocessassociation pollutantkey="75" pollutantname="Benzo(b)fluoranthene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="176" pollutantname="Benzo(g,h,i)perylene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="176" pollutantname="Benzo(g,h,i)perylene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="76" pollutantname="Benzo(g,h,i)perylene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="76" pollutantname="Benzo(g,h,i)perylene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="177" pollutantname="Benzo(k)fluoranthene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="177" pollutantname="Benzo(k)fluoranthene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="77" pollutantname="Benzo(k)fluoranthene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="77" pollutantname="Benzo(k)fluoranthene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="178" pollutantname="Chrysene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="178" pollutantname="Chrysene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="78" pollutantname="Chrysene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="78" pollutantname="Chrysene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="118" pollutantname="Composite - NonECPM" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="168" pollutantname="Dibenzo(a,h)anthracene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="168" pollutantname="Dibenzo(a,h)anthracene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="68" pollutantname="Dibenzo(a,h)anthracene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="68" pollutantname="Dibenzo(a,h)anthracene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="41" pollutantname="Ethyl Benzene" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="41" pollutantname="Ethyl Benzene" processkey="11" processname="Evap Permeation"/>
<pollutantprocessassociation pollutantkey="41" pollutantname="Ethyl Benzene" processkey="13" processname="Evap Fuel Leaks"/>
<pollutantprocessassociation pollutantkey="41" pollutantname="Ethyl Benzene" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="169" pollutantname="Fluoranthene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="169" pollutantname="Fluoranthene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="69" pollutantname="Fluoranthene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="69" pollutantname="Fluoranthene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="181" pollutantname="Fluorene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="181" pollutantname="Fluorene gas" processkey="15" processname="Crankcase Running Exhaust"/>

<pollutantprocessassociation pollutantkey="81" pollutantname="Fluorene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="81" pollutantname="Fluorene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="25" pollutantname="Formaldehyde" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="25" pollutantname="Formaldehyde" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="119" pollutantname="H2O (aerosol)" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="182" pollutantname="Indeno(1,2,3,c,d)pyrene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="182" pollutantname="Indeno(1,2,3,c,d)pyrene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="82" pollutantname="Indeno(1,2,3,c,d)pyrene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="82" pollutantname="Indeno(1,2,3,c,d)pyrene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="185" pollutantname="Naphthalene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="185" pollutantname="Naphthalene gas" processkey="11" processname="Evap Permeation"/>
<pollutantprocessassociation pollutantkey="185" pollutantname="Naphthalene gas" processkey="13" processname="Evap Fuel Leaks"/>
<pollutantprocessassociation pollutantkey="185" pollutantname="Naphthalene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="23" pollutantname="Naphthalene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="23" pollutantname="Naphthalene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="79" pollutantname="Non-Methane Hydrocarbons" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="79" pollutantname="Non-Methane Hydrocarbons" processkey="11" processname="Evap Permeation"/>
<pollutantprocessassociation pollutantkey="79" pollutantname="Non-Methane Hydrocarbons" processkey="13" processname="Evap Fuel Leaks"/>
<pollutantprocessassociation pollutantkey="111" pollutantname="Organic Carbon" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="183" pollutantname="Phenanthrene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="183" pollutantname="Phenanthrene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="83" pollutantname="Phenanthrene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="83" pollutantname="Phenanthrene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="184" pollutantname="Pyrene gas" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="184" pollutantname="Pyrene gas" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="84" pollutantname="Pyrene particle" processkey="1" processname="Running Exhaust"/>
<pollutantprocessassociation pollutantkey="84" pollutantname="Pyrene particle" processkey="15" processname="Crankcase Running Exhaust"/>
<pollutantprocessassociation pollutantkey="115" pollutantname="Sulfate Particulate" processkey="1" processname="Running Exhaust"/>

```

    <pollutantprocessassociation pollutantkey="1" pollutantname="Total Gaseous Hydrocarbons" processkey="1"
processname="Running Exhaust"/>
    <pollutantprocessassociation pollutantkey="1" pollutantname="Total Gaseous Hydrocarbons"
processkey="11" processname="Evap Permeation"/>
    <pollutantprocessassociation pollutantkey="1" pollutantname="Total Gaseous Hydrocarbons"
processkey="13" processname="Evap Fuel Leaks"/>
    <pollutantprocessassociation pollutantkey="87" pollutantname="Volatile Organic Compounds"
processkey="1" processname="Running Exhaust"/>
    <pollutantprocessassociation pollutantkey="87" pollutantname="Volatile Organic Compounds"
processkey="11" processname="Evap Permeation"/>
    <pollutantprocessassociation pollutantkey="87" pollutantname="Volatile Organic Compounds"
processkey="13" processname="Evap Fuel Leaks"/>
  </pollutantprocessassociations>
  <databaseselections>
    <databaseselection servername="" databasename="MOVES2014_early_NLEV" description=""/>
    <databaseselection servername="" databasename="va_stage2_input_20161104" description=""/>
  </databaseselections>
  <internalcontrolstrategies>
<internalcontrolstrategy
classname="gov.epa.otaq.moves.master.implementation.ghg.internalcontrolstrategies.rateofprogress.RateOfProgress
Strategy"><![CDATA[
useParameters    No

]]></internalcontrolstrategy>
  </internalcontrolstrategies>
  <inputdatabase servername="" databasename="" description=""/>
  <uncertaintyparameters uncertaintymodeenabled="false" numberofruns persimulation="0"
numberofsimulations="0"/>
  <geographicoutputdetail description="COUNTY"/>
  <outputemissionsbreakdownselection>
    <modelyear selected="false"/>
    <fueltype selected="false"/>
    <fuelsubtype selected="false"/>
    <emissionprocess selected="true"/>
    <onroadoffroad selected="true"/>
    <roadtype selected="true"/>
    <sourceusetype selected="true"/>
    <movesvehicletype selected="false"/>
    <onroadscc selected="false"/>
    <estimateuncertainty selected="false" numberOfIterations="2" keepSampledData="false"
keepIterations="false"/>
    <sector selected="false"/>
    <engtechid selected="false"/>
    <hpclass selected="false"/>
    <regclassid selected="false"/>
  </outputemissionsbreakdownselection>
  <outputdatabase servername="localhost" databasename="I495_MSAT_51059_2017_4Seasons_mo"
description=""/>
  <outputtimestep value="24-Hour Day"/>
  <outputvmtdata value="true"/>
  <outputsho value="false"/>
  <outputsh value="false"/>
  <outputshp value="false"/>
  <outputshidling value="false"/>
  <outputstarts value="false"/>
  <outputpopulation value="true"/>

```

```
<scaleinputdatabase servername="localhost" databasename="I495_MSAT_51059_2017_4Seasons_mi"
description=""/>
<pmsize value="0"/>
<outputfactors>
  <timefactors selected="true" units="Days"/>
  <distancefactors selected="true" units="Miles"/>
  <massfactors selected="true" units="Grams" energyunits="Million BTU"/>
</outputfactors>
<savedata>

</savedata>

<donotexecute>

</donotexecute>

<generatordatabase shouldsave="false" servername="" databasename="" description=""/>
  <donotperformfinalaggregation selected="false"/>
  <lookuptableflags scenarioid="" truncateoutput="false" truncateactivity="false" truncatebaserates="true"/>
</runspec>
```

Appendix G: Sample MOVE Run Specification for CO Analysis

Sample MOVES2014b Run-Spec

2021 Scenario Run

```
<runspec version="MOVES2014b-20181203">
  <description><![CDATA[]]></description>
  <models>
    <model value="ONROAD"/>
  </models>
  <modelscale value="Inv"/>
  <modeldomain value="PROJECT"/>
  <geographicselections>
    <geographicselection type="COUNTY" key="51059" description="VIRGINIA - Fairfax County"/>
  </geographicselections>
  <timespan>
    <year key="2021"/>
    <month id="1"/>
    <day id="5"/>
    <beginhour id="18"/>
    <endhour id="18"/>
    <aggregateBy key="Hour"/>
  </timespan>
  <onroadvehicleselections>
    <onroadvehicleselection fueltypeid="3" fueltypedesc="Compressed Natural Gas (CNG)" sourcetypeid="42"
sourcetype="Transit Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="62" sourcetype="Combination Long-
haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="61" sourcetype="Combination Short-
haul Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="41" sourcetype="Intercity Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="32" sourcetype="Light Commercial
Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="54" sourcetype="Motor Home"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="21" sourcetype="Passenger Car"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="31" sourcetype="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="51" sourcetype="Refuse Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="43" sourcetype="School Bus"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="53" sourcetype="Single Unit Long-haul
Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="52" sourcetype="Single Unit Short-haul
Truck"/>
    <onroadvehicleselection fueltypeid="2" fueltypedesc="Diesel Fuel" sourcetypeid="42" sourcetype="Transit Bus"/>
    <onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="32" sourcetype="Light Commercial
Truck"/>
    <onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="21" sourcetype="Passenger Car"/>
    <onroadvehicleselection fueltypeid="9" fueltypedesc="Electricity" sourcetypeid="31" sourcetype="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="32" sourcetype="Light Commercial
Truck"/>
    <onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="21" sourcetype="Passenger Car"/>
    <onroadvehicleselection fueltypeid="5" fueltypedesc="Ethanol (E-85)" sourcetypeid="31" sourcetype="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="61" sourcetype="Combination Short-haul
Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="32" sourcetype="Light Commercial
Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="54" sourcetype="Motor Home"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="11" sourcetype="Motorcycle"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="21" sourcetype="Passenger Car"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="31" sourcetype="Passenger Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="51" sourcetype="Refuse Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="43" sourcetype="School Bus"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="53" sourcetype="Single Unit Long-haul
Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="52" sourcetype="Single Unit Short-haul
Truck"/>
    <onroadvehicleselection fueltypeid="1" fueltypedesc="Gasoline" sourcetypeid="42" sourcetype="Transit Bus"/>
  </onroadvehicleselections>
  <offroadvehicleselections>
  </offroadvehicleselections>
  <offroadvehiclesscs>
  </offroadvehiclesscs>
  <roadtypes separatoramps="false">
    <roadtype roadtypeid="4" roadtypename="Urban Restricted Access" modelCombination="M1"/>
    <roadtype roadtypeid="5" roadtypename="Urban Unrestricted Access" modelCombination="M1"/>
  </roadtypes>
  <pollutantprocessassociations>
    <pollutantprocessassociation pollutantkey="2" pollutantname="Carbon Monoxide (CO)" processkey="1"
processname="Running Exhaust"/>
  </pollutantprocessassociations>
</runspec>
```

```

        <pollutantprocessassociation pollutantkey="2" pollutantname="Carbon Monoxide (CO)" processkey="15"
processname="Crankcase Running Exhaust"/>
    </pollutantprocessassociations>
    <databaseselections>
        <databaseselection servername="" databasename="MOVES2014_early_NLEV" description=""/>
        <databaseselection servername="" databasename="va_stage2_input_20161104" description=""/>
    </databaseselections>
    <internalcontrolstrategies>
<internalcontrolstrategy
classname="gov.epa.otaq.moves.master.implementation.ghg.internalcontrolstrategies.rateofprogress.RateOfProgressStrategy"><![CDATA[
useParameters      No
]]></internalcontrolstrategy>
    </internalcontrolstrategies>
    <inputdatabase servername="" databasename="" description=""/>
    <uncertaintyparameters uncertaintymodeenabled="false" numberofrunspersimulation="0" numberofsimulations="0"/>
    <geographicoutputdetail description="LINK"/>
    <outputemissionsbreakdownselection>
        <modelyear selected="false"/>
        <fueltype selected="false"/>
        <fuelsubtype selected="false"/>
        <emissionprocess selected="true"/>
        <onroadoffroad selected="true"/>
        <roadtype selected="true"/>
        <sourceusetype selected="false"/>
        <movesvehicletype selected="false"/>
        <onroadsc selected="false"/>
        <estimateuncertainty selected="false" numberOfIterations="2" keepSampledData="false" keepIterations="false"/>
        <sector selected="false"/>
        <engtechid selected="false"/>
        <hpclass selected="false"/>
        <regclassid selected="false"/>
    </outputemissionsbreakdownselection>
    <outputdatabase servername="" databasename="I495_51059_2021_01_05_CO_pmo" description=""/>
    <outputtimestep value="Hour"/>
    <outputvmtdata value="true"/>
    <outputsho value="false"/>
    <outputsh value="false"/>
    <outputshp value="false"/>
    <outputshidling value="false"/><outputstarts value="false"/>
    <outputpopulation value="true"/>
    <scaleinputdatabase servername="localhost" databasename="I495_51059_2021_01_05_CO_pmi" description=""/>
    <pmsize value="0"/>
    <outputfactors>
        <timefactors selected="true" units="Hours"/>
        <distancefactors selected="true" units="Miles"/>
        <massfactors selected="true" units="Grams" energyunits="Million BTU"/>
    </outputfactors>
    <savedata>
</savedata>

    <donotexecute>
</donotexecute>

    <generatordatabase shouldsave="false" servername="" databasename="" description=""/>
        <donotperformfinalaggregation selected="false"/>
    <lookupableflags scenarioid="" truncateoutput="true" truncateactivity="true" truncatebaserates="true"/>
</runspec>

```

Emission Factor Charts

linkID	roadTypeID	linkAvgSpeed	linkDescription	linkAvgGrade (%)	2025	2045	EF Unit
1	5	0	Urban unrestricted queue (idle) link	5	5.4247	1.9233	g/veh-hr
2	5	0	Urban unrestricted queue (idle) link	4	5.4247	1.9233	g/veh-hr
3	5	0	Urban unrestricted queue (idle) link	3	5.4247	1.9233	g/veh-hr
4	5	0	Urban unrestricted queue (idle) link	2	5.4247	1.9233	g/veh-hr
5	5	0	Urban unrestricted queue (idle) link	1	5.4247	1.9233	g/veh-hr
6	5	0	Urban unrestricted queue (idle) link	0	5.4247	1.9233	g/veh-hr
7	5	0	Urban unrestricted queue (idle) link	-1	5.4247	1.9233	g/veh-hr
8	5	0	Urban unrestricted queue (idle) link	-2	5.4247	1.9233	g/veh-hr
9	5	0	Urban unrestricted queue (idle) link	-3	5.4247	1.9233	g/veh-hr
10	5	0	Urban unrestricted queue (idle) link	-4	5.4247	1.9233	g/veh-hr
11	5	0	Urban unrestricted queue (idle) link	-5	5.4247	1.9233	g/veh-hr
12	5	25	Urban unrestricted free flow link	5	4.9648	1.8297	g/mi
13	5	25	Urban unrestricted free flow link	4	3.8881	1.3961	g/mi
14	5	25	Urban unrestricted free flow link	3	3.2845	1.1579	g/mi
15	5	25	Urban unrestricted free flow link	2	2.9175	1.0190	g/mi
16	4	25	Urban unrestricted free flow link	1	2.5684	0.8714	g/mi
17	4	25	Urban unrestricted free flow link	0	2.2031	0.7269	g/mi
18	4	25	Urban unrestricted free flow link	-1	1.9350	0.6321	g/mi
19	4	25	Urban unrestricted free flow link	-2	1.7274	0.5650	g/mi
20	4	25	Urban unrestricted free flow link	-3	1.5753	0.5174	g/mi
21	4	25	Urban unrestricted free flow link	-4	1.3967	0.4571	g/mi
22	4	25	Urban unrestricted free flow link	-5	1.2415	0.4042	g/mi
23	4	35	Urban unrestricted free flow link	5	4.8004	1.8173	g/mi
24	4	35	Urban unrestricted free flow link	4	3.9844	1.4837	g/mi
25	4	35	Urban unrestricted free flow link	3	3.3230	1.2219	g/mi
26	4	35	Urban unrestricted free flow link	2	2.8168	1.0254	g/mi
27	4	35	Urban unrestricted free flow link	1	2.3300	0.8370	g/mi
28	4	35	Urban unrestricted free flow link	0	1.9512	0.6911	g/mi
29	4	35	Urban unrestricted free flow link	-1	1.6535	0.5799	g/mi
30	5	35	Urban unrestricted free flow link	-2	1.4113	0.4900	g/mi
31	5	35	Urban unrestricted free flow link	-3	1.2107	0.4152	g/mi
32	5	35	Urban unrestricted free flow link	-4	1.0399	0.3560	g/mi
33	5	35	Urban unrestricted free flow link	-5	0.9047	0.3104	g/mi
34	5	45	Urban unrestricted free flow link	5	5.3305	2.1100	g/mi
35	5	45	Urban unrestricted free flow link	4	4.3510	1.7167	g/mi
36	5	45	Urban unrestricted free flow link	3	3.4640	1.3578	g/mi
37	5	45	Urban unrestricted free flow link	2	2.7792	1.0789	g/mi
38	5	45	Urban unrestricted free flow link	1	2.2270	0.8521	g/mi
39	5	45	Urban unrestricted free flow link	0	1.7454	0.6561	g/mi
40	5	45	Urban unrestricted free flow link	-1	1.4356	0.5340	g/mi
41	5	45	Urban unrestricted free flow link	-2	1.1912	0.4426	g/mi
42	5	45	Urban unrestricted free flow link	-3	0.9935	0.3690	g/mi
43	5	45	Urban unrestricted free flow link	-4	0.8188	0.3046	g/mi
44	5	45	Urban unrestricted free flow link	-5	0.6888	0.2557	g/mi
45	4	55	Urban restricted free flow link	5	5.6865	2.2890	g/mi
46	4	55	Urban restricted free flow link	4	4.6250	1.8691	g/mi
47	4	55	Urban restricted free flow link	3	3.6985	1.5034	g/mi
48	4	55	Urban restricted free flow link	2	2.8809	1.1654	g/mi
49	4	55	Urban restricted free flow link	1	2.2203	0.8866	g/mi
50	4	55	Urban restricted free flow link	0	1.6834	0.6590	g/mi
51	4	55	Urban restricted free flow link	-1	1.3188	0.5102	g/mi
52	4	55	Urban restricted free flow link	-2	1.0649	0.4119	g/mi
53	4	55	Urban restricted free flow link	-3	0.8770	0.3436	g/mi
54	4	55	Urban restricted free flow link	-4	0.7232	0.2858	g/mi
55	4	55	Urban restricted free flow link	-5	0.5693	0.2245	g/mi

Appendix H: Sample CAL3i Input / Output Files

Sample CAL3QHC Inputs
As generated using the FHWA Cal3i Model
 2023 Worst Case Build Scenario

'I-495 NEXT'	60	108	0	0	28	0.3048	1	1		
'RCP N Leg E Side - Corner'		58.0	82.0	5.9						
'RCP N Leg E Side - 25 m'		58.0	154.0	5.9						
'RCP N Leg E Side - 50 m'		58.0	236.0	5.9						
'RCP N Leg E Side - Midblk'		58.0	672.0	5.9						
'RCP N Leg W Side - Corner'		-58.0	82.0	5.9						
'RCP N Leg W Side - 25 m'		-58.0	154.0	5.9						
'RCP N Leg W Side - 50 m'		-58.0	236.0	5.9						
'RCP N Leg W Side - Midblk'		-58.0	672.0	5.9						
'RCP S Leg. E Side - Corner'		58.0	-82.0	5.9						
'RCP S Leg. E Side - 25 m'		58.0	-154.0	5.9						
'RCP S Leg. E Side - 50 m'		58.0	-236.0	5.9						
'RCP S Leg. E Side - Midblk'		58.0	-672.0	5.9						
'RCP S Leg. W Side - Corner'		-58.0	-82.0	5.9						
'RCP S Leg. W Side - 25 m'		-58.0	-154.0	5.9						
'RCP S Leg. W Side - 50 m'		-58.0	-236.0	5.9						
'RCP S Leg. W Side - Midblk'		-58.0	-672.0	5.9						
'RCP E Leg N Side - 25 m'		130.0	82.0	5.9						
'RCP E Leg N Side - 50 m'		212.0	82.0	5.9						
'RCP E Leg N Side - Midblk'		648.0	82.0	5.9						
'RCP W Leg N Side - 25 m'		-130.0	82.0	5.9						
'RCP W Leg N Side - 50 m'		-212.0	82.0	5.9						
'RCP W Leg N Side - Midblk'		-648.0	82.0	5.9						
'RCP E Leg S Side - 25 m'		130.0	-82.0	5.9						
'RCP E Leg S Side - 50 m'		212.0	-82.0	5.9						
'RCP E Leg S Side - Midblk'		648.0	-82.0	5.9						
'RCP W Leg S Side - 25 m'		-130.0	-82.0	5.9						
'RCP W Leg S Side - 50 m'		-212.0	-82.0	5.9						
'RCP W Leg S Side - Midblk'		-648.0	-82.0	5.9						
'2023 Rt123 & Tysons Blvd'		12	1	0	'c'					
1										
'N Leg App - FreeFlow'		'AG'	-24.0	0.0	-24.0	1200.0	4920	5.3305	0	67.7
1										
'N Leg Dep - FreeFlow'		'AG'	24.0	0.0	24.0	1200.0	4920	5.3305	0	67.7
1										
'S Leg App - FreeFlow'		'AG'	24.0	0.0	24.0	-1200.0	4920	5.3305	0	67.7
1										
'S Leg Dep - FreeFlow'		'AG'	-24.0	0.0	-24.0	-1200.0	4920	5.3305	0	67.7
1										
'E Leg App - FreeFlow'		'AG'	0.0	36.0	1200.0	36.0	7380	5.3305	0	91.7
1										
'E Leg Dep - FreeFlow'		'AG'	0.0	-36.0	1200.0	-36.0	7380	5.3305	0	91.7
1										
'W Leg App - FreeFlow'		'AG'	0.0	-36.0	-1200.0	-36.0	7380	5.3305	0	91.7
1										
'W Leg Dep - FreeFlow'		'AG'	0.0	36.0	-1200.0	36.0	7380	5.3305	0	91.7
2										
'N Leg App - Queue'		'AG'	-24.0	72.0	-24.0	1200.0	0	48.0	4	
2	120	68	2	4920	5.4247	1900	1	3		
2										
'S Leg App - Queue'		'AG'	24.0	-72.0	24.0	-1200.0	0	48.0	4	
2	120	68	2	4920	5.4247	1900	1	3		
2										
'E Leg App - Queue'		'AG'	48.0	36.0	1200.0	36.0	0	72.0	6	
2	120	68	2	7380	5.4247	1900	1	3		
2										
'W Leg App - Queue'		'AG'	-48.0	-36.0	-1200.0	-36.0	0	72.0	6	
2	120	68	2	7380	5.4247	1900	1	3		
1	0	4	1000	0	'Y'	10	1	36		

Sample CAL3QHC Output
2023 Worst Case Build Scenario

*** EPA CAL3QHC Model Run implemented using the FHWA Resource Center CAL3i graphical user interface

CAL3QHC: LINE SOURCE DISPERSION MODEL - VERSION 2.0 Dated 13045

PAGE 1

JOB: I-495 NEXT

RUN: 2023 Rt123 & Tysons Blvd

DATE : 12/19/19

TIME : 23:54: 2

The MODE flag has been set for calculating concentrations for POLLUTANT: CO

SITE & METEOROLOGICAL VARIABLES

```

-----
VS = 0.0 CM/S      VD = 0.0 CM/S      Z0 = 108. CM
U = 1.0 M/S       CLAS = 4 (D)      ATIM = 60. MINUTES      MIXH = 1000. M      AMB =
0.0 PPM
  
```

LINK VARIABLES

VPH	LINK DESCRIPTION				LINK COORDINATES (FT)				* *	LENGTH (FT)	BRG TYPE (DEG)
	EF	H	W	V/C QUEUE	X1	Y1	X2	Y2			
(G/MI)	(FT)	(FT)	(VEH)								
4920.	1.	N Leg App - FreeFlow*			-24.0	0.0	-24.0	1200.0	*	1200.	360. AG
	5.3	0.0	67.7								
4920.	2.	N Leg Dep - FreeFlow*			24.0	0.0	24.0	1200.0	*	1200.	360. AG
	5.3	0.0	67.7								
4920.	3.	S Leg App - FreeFlow*			24.0	0.0	24.0	-1200.0	*	1200.	180. AG
	5.3	0.0	67.7								
4920.	4.	S Leg Dep - FreeFlow*			-24.0	0.0	-24.0	-1200.0	*	1200.	180. AG
	5.3	0.0	67.7								
7380.	5.	E Leg App - FreeFlow*			0.0	36.0	1200.0	36.0	*	1200.	90. AG
	5.3	0.0	91.7								
7380.	6.	E Leg Dep - FreeFlow*			0.0	-36.0	1200.0	-36.0	*	1200.	90. AG
	5.3	0.0	91.7								
7380.	7.	W Leg App - FreeFlow*			0.0	-36.0	-1200.0	-36.0	*	1200.	270. AG
	5.3	0.0	91.7								
7380.	8.	W Leg Dep - FreeFlow*			0.0	36.0	-1200.0	36.0	*	1200.	270. AG
	5.3	0.0	91.7								
33.	9.	N Leg App - Queue *			-24.0	72.0	-24.0	5372.1	*	5300.	360. AG
100.0	0.0	48.0	1.62 269.2								
33.	10.	S Leg App - Queue *			24.0	-72.0	24.0	-5372.1	*	5300.	180. AG
100.0	0.0	48.0	1.62 269.2								
49.	11.	E Leg App - Queue *			48.0	36.0	5348.1	36.0	*	5300.	90. AG
100.0	0.0	72.0	1.62 269.2								
49.	12.	W Leg App - Queue *			-48.0	-36.0	-5348.1	-36.0	*	5300.	270. AG
100.0	0.0	72.0	1.62 269.2								

DATE : 12/19/19

TIME : 23:54: 2

ADDITIONAL QUEUE LINK PARAMETERS

SIGNAL	LINK DESCRIPTION	* CYCLE	RED	CLEARANCE	APPROACH	SATURATION	IDLE
TYPE	ARRIVAL	* LENGTH	TIME	LOST TIME	VOL	FLOW RATE	EM FAC
	RATE	* (SEC)	(SEC)	(SEC)	(VPH)	(VPH)	(gm/hr)
3	9. N Leg App - Queue	* 120	68	2.0	4920	1900	5.42 1
3	10. S Leg App - Queue	* 120	68	2.0	4920	1900	5.42 1
3	11. E Leg App - Queue	* 120	68	2.0	7380	1900	5.42 1
3	12. W Leg App - Queue	* 120	68	2.0	7380	1900	5.42 1

RECEPTOR LOCATIONS

RECEPTOR	* X	COORDINATES (FT)	* Y	Z	*
1. RCP N Leg E Side - C	* 58.0	82.0	5.9	*	*
2. RCP N Leg E Side - 2	* 58.0	154.0	5.9	*	*
3. RCP N Leg E Side - 5	* 58.0	236.0	5.9	*	*
4. RCP N Leg E Side - M	* 58.0	672.0	5.9	*	*
5. RCP N Leg W Side - C	* -58.0	82.0	5.9	*	*
6. RCP N Leg W Side - 2	* -58.0	154.0	5.9	*	*
7. RCP N Leg W Side - 5	* -58.0	236.0	5.9	*	*
8. RCP N Leg W Side - M	* -58.0	672.0	5.9	*	*
9. RCP S Leg. E Side -	* 58.0	-82.0	5.9	*	*
10. RCP S Leg. E Side -	* 58.0	-154.0	5.9	*	*
11. RCP S Leg. E Side -	* 58.0	-236.0	5.9	*	*
12. RCP S Leg. E Side -	* 58.0	-672.0	5.9	*	*
13. RCP S Leg. W Side -	* -58.0	-82.0	5.9	*	*
14. RCP S Leg. W Side -	* -58.0	-154.0	5.9	*	*
15. RCP S Leg. W Side -	* -58.0	-236.0	5.9	*	*
16. RCP S Leg. W Side -	* -58.0	-672.0	5.9	*	*
17. RCP E Leg N Side - 2	* 130.0	82.0	5.9	*	*
18. RCP E Leg N Side - 5	* 212.0	82.0	5.9	*	*
19. RCP E Leg N Side - M	* 648.0	82.0	5.9	*	*
20. RCP W Leg N Side - 2	* -130.0	82.0	5.9	*	*
21. RCP W Leg N Side - 5	* -212.0	82.0	5.9	*	*
22. RCP W Leg N Side - M	* -648.0	82.0	5.9	*	*
23. RCP E Leg S Side - 2	* 130.0	-82.0	5.9	*	*
24. RCP E Leg S Side - 5	* 212.0	-82.0	5.9	*	*
25. RCP E Leg S Side - M	* 648.0	-82.0	5.9	*	*
26. RCP W Leg S Side - 2	* -130.0	-82.0	5.9	*	*
27. RCP W Leg S Side - 5	* -212.0	-82.0	5.9	*	*
28. RCP W Leg S Side - M	* -648.0	-82.0	5.9	*	*

260.	*	0.0000	3.5000	3.3000	3.1000	2.5000	2.5000	2.2000	1.6000	1.3000	1.0000	0.9000
0.9000		0.7000										
270.	*	0.0000	2.8000	2.7000	2.3000	1.9000	1.9000	1.6000	2.8000	2.6000	2.3000	2.0000
2.0000		1.7000										
280.	*	0.0000	1.5000	1.3000	1.0000	0.8000	0.8000	0.6000	3.4000	3.2000	3.0000	2.6000
2.6000		2.3000										
290.	*	0.0000	1.0000	0.8000	0.5000	0.3000	0.3000	0.3000	3.4000	2.9000	2.8000	2.7000
2.6000		2.4000										
300.	*	0.3000	0.8000	0.6000	0.3000	0.1000	0.1000	0.1000	3.0000	2.6000	2.4000	2.3000
2.3000		2.3000										
310.	*	0.5000	0.8000	0.6000	0.3000	0.1000	0.1000	0.1000	2.8000	2.6000	2.3000	2.2000
2.2000		2.2000										
320.	*	0.5000	1.0000	0.7000	0.3000	0.1000	0.1000	0.1000	2.5000	2.4000	2.1000	1.9000
1.9000		1.8000										
330.	*	0.5000	1.0000	0.7000	0.3000	0.1000	0.1000	0.1000	2.5000	2.3000	1.9000	1.7000
1.7000		1.7000										
340.	*	0.6000	0.9000	0.5000	0.0000	0.0000	0.0000	0.0000	2.6000	2.3000	1.7000	1.7000
1.7000		1.7000										
350.	*	1.2000	0.8000	0.3000	0.0000	0.1000	0.0000	0.0000	2.6000	2.1000	1.7000	1.8000
1.7000		1.7000										
360.	*	2.1000	0.3000	0.1000	0.0000	0.3000	0.1000	0.0000	2.2000	2.0000	1.8000	2.2000
2.0000		1.8000										
-----*												

MAX	*	2.6000	3.5000	3.3000	3.1000	3.4000	3.2000	3.0000	3.4000	3.2000	3.0000	3.5000
3.3000		3.1000										
DEGR.	*	10	250	260	260	100	100	100	290	280	280	70
80		80										

THE HIGHEST CONCENTRATION OF 4.1000 PPM OCCURRED AT RECEPTOR 5.

**Appendix I: Memorandum of the Proposed Air Quality
Modeling and Analysis Approach for the VDOT I-495 Northern
Extension Project (I-495 NEXT)**

MEMORANDUM

To: Jim Ponticello, Air Quality Program Manager – VDOT Environmental Division
Chris Voigt – VDOT Environmental Division

From: Robert d’Abadie, Michael Baker International
John Frohning, Jacobs

Date: September 10, 2019

Subject: Proposed Air Quality Modeling and Analysis Approach for the VDOT I-495 Northern Extension Project (I-495 NEXT)

General Project Overview

The Virginia Department of Transportation (VDOT) is conducting an environmental study regarding plans to extend the 495 Express Lanes by approximately three miles from the I-495 and Dulles Toll Road interchange to the vicinity of the American Legion Bridge.

Virginia's 495 Express Lanes Northern Extension study, also referred to as I-495 NEXT, is being developed as an independent, stand-alone project that will be closely coordinated and compatible with plans for I-495 (Capital Beltway) in Maryland.

The environmental study, specifically an Environmental Assessment or EA, will be completed according to the requirements of the National Environmental Policy Act of 1969 (NEPA), as amended, and 23 CFR Part 771, will evaluate site-specific conditions and potential effects the proposed improvements may have on air quality, noise, neighborhoods, parks, recreation areas, historic properties, wetlands and streams, and other resources. This document focuses primarily on the proposed approach to evaluate the air quality impacts of this project and ensure it is consistent with the air quality goals of the region.

Project Goals and Objectives

VDOT, in coordination with the Federal Highway Administration (FHWA), developed the project’s goals and objectives through a comprehensive process that included a review of previous studies and recent or planned projects; an analysis of traffic, environmental, and socioeconomic conditions in the region; and feedback from the public and federal, regional, state, and local agencies through a scoping process.

The project will address the following needs:

- Reduce congestion and improve roadway safety: As population and employment within the Washington, D.C. region continue to grow, the increase in traffic volumes and travel demand along the I-495 corridor will result in increased congestion, delays, and safety concerns. There is

a need to address existing and future travel demand and relieve pressure on the general-purpose lanes and the surrounding roadway network.

- Provide additional travel choices: The existing 495 Express Lanes end at Old Dominion Drive, limiting travel choices for HOV and single-occupant vehicles within the study area, with no good options to bypass congestion or bottlenecks. As such, an additional option is needed to allow users to bypass congestion in the general-purpose lanes and to choose a mode that best suits their individual needs.
- Improve travel reliability: Congestion along the I-495 corridor results in highly variable travel speeds and travel times, which are expected to worsen as the population, employment, and traffic volumes in the region increase. Consistent, reliable, predictable travel times are needed for commuters and freight movement.

Development of the Air Quality Approach

The VDOT Project-Level Air Quality Resource Document (Resource Document, December 2018), was used to inform the development of the air quality analysis approach. The Resource Document provides a comprehensive listing of models, methods and assumptions, as well as an associated online data repository for transportation project-level air quality studies to be conducted by or on behalf of the Commonwealth. In December 2015, the draft document and associated data were subjected to inter-agency consultation for conformity (IACC), with a subsequent update in 2018. VDOT also has Programmatic Agreements with FHWA that may be utilized in this air quality evaluation. All these references can be found on the VDOT Air Quality Website¹. In a review of the preliminary traffic evaluation for this project, it appears all predetermined conditions and thresholds contained within the Resource Document and applicable Programmatic Agreements will be met. The models, methods/protocols and assumptions as specified or referenced in the VDOT Resource Document will be applied without change or without substantive change as defined in that document.

The following sections provide an overview of the proposed approach for assessing the potential for local air quality impacts of the project, addressing all related air quality requirements under the Clean Air Act (CAA) - as amended – specifically the Conformity requirements. Any additional analysis required under the NEPA regulations will also be addressed. Note, for regional conformity, the project is currently included in the most recent regional conformity demonstration approved by the MWCOG Transportation Planning Board, thereby addressing regional conformity requirements. As this is an ongoing effort, VDOT will continue to coordinate with MWCOG to ensure that regional conformity requirements are met.

¹ https://www.virginiadot.org/projects/environmental_air_section.asp

Air Quality Status

The EPA Green Book² lists non-attainment, maintenance, and attainment areas across the nation. It lists the jurisdictions within the area in which the project is located as being in attainment for all the NAAQS except ozone. Specifically, the EPA designated the Metropolitan Washington, DC, (DC-MD-VA) region as ‘marginal’ non-attainment for the 2015 Ozone Standard effective August 3, 2018. Previously in 2012, EPA designated the Metropolitan Washington, DC, (DC-MD-VA) region as ‘marginal’ nonattainment for the 2008 Ozone Standard, with a re-designation to attainment-maintenance on August 15, 2019. Having the project explicitly addressed in the most recent regional conformity demonstration by the MWCOG Transportation Planning Board and satisfies project-level Conformity required for this pollutant for both standards under the CAA³.

Previous designations for Carbon Monoxide (CO) and Fine Particulate Matter (PM_{2.5}) pertained to National Ambient Air Quality Standards (NAAQS) that have expired or been revoked⁴, respectively. As such Transportation conformity requirements under the CAA no longer apply for these pollutants.

General Note on Air Quality Analysis

It is noted that while the opening year of the project is 2023, traffic forecasting has been done for 2025 to account for the multi-year ramp-up period VDOT has observed on other Express-Toll facilities in the Commonwealth and so the modeling can take advantage of the analysis years native to the MWCOG regional transportation model without alternation. Emissions rates trend downward over time, the higher 2023 emission rates will be combined with higher 2025 traffic forecasts ensure the analysis would be conservative if actual forecast volumes (and not assumed worst-case volumes, which are higher) were to be applied.

Carbon Monoxide Model Evaluation

While the project is not currently subject to transportation conformity under the CAA for CO, NEPA analyses in Virginia requires a project level hot-spot screening analysis for CO. A worst-case approach for modeling CO is proposed consistent with the VDOT Resource Document and EPA guidance. The analysis will include the identified three worst-case intersections as well as, potentially, screening of a nearby worst-case interchange that is technically outside of the project area but included in the traffic study area.

- The three worst case intersections will be selected based on the methodology referenced in the Resource Document and appropriate EPA guidance. The modeling methodology set forth in these documents will be used for this analysis.

² <https://www.epa.gov/green-book>

³ This project is included in Visualize2045, the current long-range plan. VDOT will verify that the project as coded reflects best current assumptions sound an update to the conformity determination be necessary.

<https://www.mwcog.org/visualize2045/document-library/>

⁴ EPA revoked the applicable PM_{2.5} annual primary NAAQS effective October 24, 2016 (15 ug/m³). The area is in attainment with the new 2016 Annual Primary PM_{2.5} standard (12 ug/m³).

- Modeling based on the VDOT Resource Document:
 - No exceptions to the models, methods and assumptions/specified in the VDOT Resource Document are planned for this analysis.
 - PM peak hour will be modeled, as higher volumes are generally expected than for the AM peak hour based on preliminary analysis supplied by the traffic team. If this changes the higher of the peak hour volumes will be used.
 - The modeling of any required intersections/interchanges will be conducted using the latest version of EPA's Motor Vehicle Emissions Simulator (MOVES2014b) for emission factors and CAL3QHC for the dispersion modeling.
 - Screening of the worst-case intersections/interchanges will be streamlined by using the FHWA CAL3i tool which generates the input files and executes the selected version of the CALINE3 model (including CAL3QHC) and summarizes the results at the receptor locations it generates.
 - Inputs for MOVES will be based on the available conformity runs for the region made available through the Resource Document. Database conversions may be needed to ensure that the data is in the appropriate format for MOVES2014b.
 - Road grade data will be based on information provided by the traffic team
 - Emission rates will be calculated for the Existing (2018), Opening Year (2023), and Design Year (2045).
 - All other appropriate inputs will be based on the VDOT Project Level Resource Document and applicable guidance.
 - Regarding volumes previous analyses have assumed a volume of 1,900 Vehicles/lane at intersections and 2,200 vehicles/lane on freeways
- Receptor locations will be based on the appropriate EPA/VDOT guidance as set forth in the Resource Document or by the worse-case locations generated by the CAL3i tool. The online data repository accompanying the VDOT Resource Document provides predetermined background concentrations and the 1-hr to 8-hr persistence factor applied to CAL3QHC outputs, which were developed based on ambient air quality monitoring data for the region.

MSAT Evaluation

- Design Year Annual Average Daily Traffic on I-495 is projected to approach or exceed 140,000 to 150,000 vehicles per day and is in close proximity to populated areas. Therefore, a quantitative MSAT analysis will be prepared in accordance with FHWA's Interim Guidance Update on Mobile Source Air Toxic Analysis in NEPA, dated December 6, 2012 and the recommendations contained within Quick Start Guide for Using MOVES for NEPA MSAT Analysis as well as the Resource Document.
- Modeling based on the approach detailed in the VDOT Resource Document:
 - No exceptions to the models, methods and assumptions/specified in the VDOT Resource Document are planned for this analysis.
 - Emission rates will be calculated for the Existing (2018), Opening Year (2023), and Design Year (2045).

- Initially the affected network will be determined using procedures suggested during FHWA NEPA training classes, specifically:
 - Changes of $\pm 5\%$ or more in AADT on congested highway links of LOS D or worse
 - Changes of $\pm 10\%$ or more in AADT on uncongested highway links of LOS C or better
 - Changes of $\pm 10\%$ or more in travel time
 - Changes of $\pm 10\%$ or more in intersection delay
 - Eliminate obvious modeling artifacts from the selected network
- More recently the FHWA has provided recommendations that the MSAT affected network can coincide with the affected area defined for the project. A comparison to the modeled affected network will be undertaken along with a review on how the affected area used in the remainder of the project was defined. The results will be discussed with VDOT and determination will be made on which network is most suitable.

The online data repository accompanying the VDOT Resource Document provides the input data, current assumptions and pre-approved input datasets for executing MOVES are available, insuring consistency with other air quality planning analyses in the region.

Greenhouse Gas Emissions

In the absence of federal guidance pertaining to transportation-oriented greenhouse gases⁵ and given the high-profile of the project, the air quality document will include a qualitative greenhouse gas (GHG) analyses. VDOT has developed a template report for project-level air quality analyses which provides an example of a qualitative analysis for GHGs, and a similar evaluation will be developed for this project.

If you need additional information, please do not hesitate to contact the project team.

⁵ In the absence of applicable federal guidance (following the withdrawal of 2016 guidance issued by the Council on Environmental Quality), Department policy applies.

See: <https://www.gpo.gov/fdsys/pkg/FR-2017-04-05/pdf/2017-06770.pdf>.